

# TUBAC FIRE DISTRICT

2227 EAST FRONTAGE ROAD P.O. BOX 2881 TUBAC, ARIZONA 85646 TELEPHONE: (520)398-2255

### REGULAR MEETING OF THE BOARD OF DIRECTORS

The Tubac Fire District Board of Directors will meet in regular session on August 28, 2024, at 3:00 pm at the Tubac Community Center Building located at 50 Bridge Rd in Tubac. The following topics and any variables thereto, will be subject to Board consideration, discussion, approval, or other action. The Board may consider any item on this agenda in any order and at any time during the meeting. The Board may convene into Executive Session for discussion or consultation for legal advice with its attorney regarding any item on this agenda, in accordance with A.R.S. § 38-431.03(A)(3).

Members of the public may attend the meeting in person, by viewing the livestream on the Tubac Fire District Facebook page, or by telephone by calling (346) 248-7799 and entering the Webinar ID, 827 3360 0975, if prompted.

NOTE: Executive Sessions are CONFIDENTIAL pursuant to A.R.S. § 38-431.03(C). Members of the public may not participate in Executive Sessions.

Members of the public who are not able to attend the meeting in person, may submit comments to the Board by email. The emails will be read out loud during the meeting. Please email any comments to <a href="mailto:bhamric@tubacfire.org">bhamric@tubacfire.org</a>. Emails must be received no later than 5pm the day before the meeting and must include your full name as well as your phone number (to allow District staff to contact you with any questions).

### **Agenda**

- 1. Call to order and Pledge of Allegiance
- 2. Roll call of Board Members
- 3. Reading of public comments submitted via email.
- 4. Call to the Public: "This is the time for the public to comment on items related to the Fire District. Members of the Board may not discuss items that are not on the agenda. Therefore, the Fire Board is not permitted to discuss or act on any items raised in the Call to the Public which is not on the agenda due to restrictions of the Open Meeting Law; however, individual Board members are permitted to respond to criticism directed to them. Otherwise, the Board has discretion to direct the Fire Chief to review the matter or that the matter is placed on a future agenda. Those wishing to address the Board need not request permission in advance. A member of the public may speak for a reasonable time as determined by the Board. If no time is specified, the presumed time limit will be 3 minutes per person. The Fire Board Chair may adjust time limitations and all individuals desiring to address the Fire Board will have the same opportunity."
- 5. Correspondence
- 6. Report from Board Members
- 7. Chief and Staff Report
  - a. Operations Update
  - b. Training
  - c. Administration Update
  - d. Wildland Update

- 8. Monthly Financial Report for July 2024
- 9. Consent Agenda
  - a. Approval of minutes from July 31, 2024.
  - b. Approval of monthly financial report for July 2024.
- 10. Presentation by Breckenridge regarding Tubac Fire Station #1 project intermediate plans.
- 11. **Executive Session** Pursuant to A.R.S. § 38-431.03(A)(3), discussion and consultation for legal advice and/or direction regarding the Santa Cruz County Treasure investigation as it relates to the Fire District.
- 12. Discussion and possible action to provide direction to fire chief regarding the Santa Cruz County investigation.
- 13. Future Agenda Items
- 14. Next meeting: September 25, 2024
- 15. Adjourn meeting.

Notice of Meeting (Agenda) dated and posted August 23, 2024, by 3:00 p.m. local time by B. Hamric.

If any disabled person needs any type of accommodation, please notify the Tubac Fire District prior to the scheduled meeting time.




# Staff Report Tubac Fire Board August 2024


Tubac Fire District is committed to the safety of our community through the delivery of fire suppression, medical services, and public education.

# July Emergency Responses

### Incident Type Categories

Jul 01, 2024 to Jul 31, 2024





• Fire 20

• Public Assist 67

Total Calls 192




Jan 01, 2023 12:00 AM to Aug 21, 2024 07:34 PM

				20	24					2024		2023	
Incident Type Category	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Grand Total - Current	% of Total Incidents - Current	Grand Total - Previous	% of Total Incidents - Previous	YTD % Change
1 - Fire	4	5	3	2	3	7	3	4	31	2.00%	42	4.00%	-26.19%
3 - Rescue & Emergency Medical Service Incident	84	107	123	95	117	115	105	71	817	64.00%	636	59.00%	28.46%
4 - Hazardous Condition (No Fire)	1	3	6	5	4	2	5	5	31	2.00%	24	2.00%	29.17%
5 - Service Call	11	20	16	22	42	57	59	41	268	21.00%	255	24.00%	5.10%
6 - Good Intent Call	6	8	11	13	18	9	8	7	80	6.00%	75	7.00%	6.67%
7 - False Alarm & False Call	5	4	5	7	5	8	12	7	53	4.00%	48	4.00%	10.42%
8 - Severe Weather & Natural Disaster	0	0	0	0	0	0	0	0	0	0.00%	1	0.00%	-100.00%
9 - Special Incident Type	0	2	0	0	0	0	0	0	2	0.00%	0	0.00%	N/A
Grand Total	111	149	164	144	189	198	192	135	1,282	100.00%	1,081	100.00%	18.59%





# YTD Call Volume






### Monthly Call Volume Year over Year

Jan 01, 2023 12:00 AM to Aug 21, 2024 07:50 PM

		2024			
Month Name	Grand Total - Current	% of Total Incidents - Current	Grand Total - Previous	% of Total Incidents - Previous	YTD % Change
January	111	9.00%	110	10.00%	0.91%
February	149	12.00%	128	12.00%	16.41%
March	164	13.00%	125	12.00%	31.20%
April	144	11.00%	145	13.00%	-0.69%
May	191	15.00%	142	13.00%	34.51%
June	198	15.00%	157	15.00%	26.11%
July	192	15.00%	164	15.00%	17.07%
August	135	11.00%	110	10.00%	22.73%
Grand Total	1,284	100.00%	1,081	100.00%	18.78%

# July Ambulance Transports by Destination





### Transports by Destination Summary

Jul 01, 2024 to Jul 31, 2024

Hospital		Tra	ansports	Transport Time		Patient Arrival to Transfer of Care		Patient Arrival to Transfer of Care Signature		Patient Arrival to Unit Back in Service	
Name	ID	Total	% of Total	Median	90th Percentile	Median	90th Percentile	Median	90th Percentile	Median	90th Percentile
BANNER-UAMC University Campus - Tucson	MED0257	9	16.07%	56:03	66:07	11:13	36:09	11:43	30:30	57:58	162:36
Carondelet Holy Cross Hospital - Nogales	MED0343	22	39.29%	18:40	24:21	07:56	15:39	09:08	15:00	22:39	40:00
Carondelet St. Joseph's Hospital - Tucson	MED0253	2	3.57%	79:26	84:43	22:34	22:52	33:16	22:45	103:32	114:27
Carondelet St. Mary's Hospital - Tucson	MED0254	5	8.93%	53:41	58:03	16:05	43:37	14:32	39:42	64:08	93:55
Northwest Sahuarita	MED8984	16	28.57%	31:29	37:16	07:06	12:48	08:37	15:17	44:56	65:35
VA-Southern AZ VA Healthcare System-Tucson	UNK0015	2	3.57%	46:41	50:36	02:11	02:34	01:18	08:16	26:53	29:23
Overall		56	100.00%	30:46	64:06	08:24	21:17	09:08	21:35	37:00	86:18


# July Emergency Responses By Station

# Primary Responses by Station


- Station 1 74
- Station 2 51
- Station 3 25
- Station 4 42

# Secondary Responses by Station

- Station 1 5
- Station 2 36
- Station 3 14
- Station 4 47











# **Combined Primary/Secondary Unit Response**




# July Incidents by shift

- A Shift
- B Shift
- C Shift

Prev	,	Ju		Next		
SU	МО	TU	WE	ТН	FR	SA
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26	27
28	29	30	31			







# Significant Calls

- \* Crews responded to a residence for a reported fall injury. Upon arrival, they discovered that the patient had not fallen but was suffering from a heat stroke. The patient then went into cardiac arrest and unfortunately, the crew was not able to resuscitate the patient.
- \* The crew responded to a significant call involving an elderly male experiencing chest pains and shortness of breath. An EKG indicated an anterior MI, and the patient was airlifted to a nearby hospital for further treatment
- Crew responded to the area of West Frontage Road near Station 2 for a large commercial truck that caught power lines crossing over the road, causing severe damage to one of the power poles. Road closures were in effect from Camino Agosto to Avenida Papalote.
- On Saturday morning, crews responded to Mount Hopkins Road, where several unresponsive cyclists were found after an accident. One critical patient was airlifted to a trauma center, another was transported by ground, and a third left before receiving care.











# **Training**

- \* Rope Rescue: mechanical advantage systems, low to medium angle rescue.
- Hoisting Operations
- Ladder Operations
- Multi Agency drill at Rio Rico Resort















# Public Education/Fire Prevention and Events



- ❖ Attended 4<sup>th</sup> of July Parade in Nogales
- ❖ Attended 4<sup>th</sup> of July Celebration at the Tubac Presidio
- ❖ Tubac Fire participated in the Back-to-School Blitz where over 500 students received school supplies
- ❖ Tubac Fire received recognition from Santa Cruz County Office of Emergency Management for teaching and inspiring the youth of Santa Cruz County

























# Plans Review & Inspections










# Maintenance Requests





# Fire Loss Due To Incident



# **Tubac Fire District**

2227 E I-19 Frontage Rd Tubac, AZ 85646 520.398.2255

# TUBAC FIRE SINCE 1974

### Monthly Financial Report - July 2024

Attached are the following for your information and review:

- 1. Balance Sheet as of July 30, 2024.
- 2. Summary of Reconciled Cash Balances as of July 30, 2024.
- 3. Income Statement of Revenues and Expenditures for July 2024 including budget to actual and year-to-date balances.
- 4. Income vs. Expenses Graph for FY 2024.
- 5. Fixed Asset Additions and Disposals for FY 23/24.
- 6. Liabilities & Securities for FY 23/24.
- 7. Fleet Repairs & Maintenance Expenses.
- 8. Station Utilities, Supplies, and Repairs & Maintenance Expenses.
- 9. Board Presentation.
- 10. Monthly Transaction Report.
- 11. 12-Month Cash Flow.

### Key points:

- Total Revenue for July is \$151,727, which is \$16,440 over budget.
- Non-Levy Revenue is \$130,669 which is \$1,711 over budget due to EMS Revenue offset by lower Wildland Revenue.
- Tax Revenue for July is \$21,059, which is over budget by \$14,730.
- Operating Expenses for July totaled \$342,005, which is under budget by \$62,827, driven by Salaries & Wages, and Employee Benefits.
- Cash balance as of July 2024 is \$10,608,971, which is up \$4,841,820 from last year.

Please contact the Finance Director for any questions or concerns regarding this report.

This report and the attached detail reports ha	we been reviewed and approved by the Fire Board.	Board.
Board Clerk	 Date	

# Tubac Fire District Balance Sheet

As of July 31, 2024

	Jul 31, 24	Jul 31, 23	\$ Change
SSETS			
Current Assets			
Checking/Savings			
1132 · Bond Proceeds Account	4,400,000.00	0.00	4,400,000.00
1133 · LGIP - State Investment Account	4,394,499.64	0.00	4,394,499.64
1127 · Cash with County Treasurer	16,220.79	14.507.26	1.713.53
1129 · Operational	1,055,142.05	825,256.78	229,885.27
1130 · Savings Acct.	448,085.57	4,647,681.07	-4,199,595.50
1131 · Bond Account	295,022.95	279,706.11	15,316.84
Total Checking/Savings	10,608,971.00	5,767,151.22	4,841,819.78
Accounts Receivable			
1245 · Property Tax Receivable	266,992.23	266,992.23	0.00
1200 · Wildland Receivable	0.00	32,351.69	-32,351.69
1205 · Other Receivables	3,276.00	164,035.00	-160,759.00
1250 · Ambulance Receivable	258,541.79	258,541.79	0.00
1251 · Allowance for Ambulance Receiv	-151,616.81	-151,616.81	0.00
Total Accounts Receivable	377,193.21	570,303.90	-193,110.6
Other Current Assets			
1733 · Right to Use Subscription	137,459.31	137,459.31	0.0
1732 · Right to Use Vehicles	59,505.76	59,505.76	0.0
1737 · Right to Use Amortization	-38,272.45	-38,272.45	0.0
1270 · Lease Receivable	213,546.00	213,546.00	0.0
1400 · Prepaid Expense	29,284.79	13,726.08	15,558.7
1499 Undeposited Funds	1,548.00	0.00	1,548.0
Total Other Current Assets	403,071.41	385,964.70	17,106.71
Total Current Assets	11,389,235.62	6,723,419.82	4,665,815.80
Fixed Assets			
1711 · Land - Non-depreciable	257,352.00	257,352.00	0.00
1745 · AD - Equipment	-1,683,339.38	-1,683,339.38	0.0
1735 · AD - Vehicles	-2,499,947.91	-2,499,947.91	0.0
1725 · AD - Building	-2,215,169.14	-2,215,169.14	0.0
1730 · Vehicles	3,041,818.51	2,950,498.83	91,319.6
1740 · Equipment	2,103,284.65	1,989,864.61	113,420.0
1720 · Buildings & Improvements	6,219,894.98	6,146,795.78	73,099.20

# Tubac Fire District Balance Sheet

As of July 31, 2024

	Jul 31, 24	Jul 31, 23	\$ Change
Other Assets			_
1960 · Risk Pool Capitalization	25,881.50	25,881.50	0.00
1958 · Net PSPRS OPEB Asset TR 3	3,021.00	3,021.00	0.00
1957 · Net Pension Asset PSPRS TR3	13,736.00	13,736.00	0.00
1918 · Deferred Outflow PSPRS OPEB TR3	787.00	787.00	0.00
1917 · Deferred Outflows PSPRS TR 3	107.462.00	107,462.00	0.00
1956 · Net OPEB Asset	174,407.00	174,407.00	0.00
1916 · Deferred outflow - PSPRS OPEB	8,018.00	8,018.00	0.00
1915 · Deferred outflows - PSPRS	1,387,833.00	1,387,833.00	0.00
Total Other Assets	1,721,145.50	1,721,145.50	0.00
TOTAL ASSETS	18,334,274.83	13,390,620.11	4,943,654.72
LIABILITIES & EQUITY			
Liabilities			
Current Liabilities			
Accounts Payable	400.000.00	440.004.00	0.40=.00
2000 · Accounts Payable	103,609.60	110,094.89	-6,485.29
Total Accounts Payable	103,609.60	110,094.89	-6,485.29
Credit Cards			
2010 · Bank of America Credit Card	342.35	1,044.59	-702.24
Total Credit Cards	342.35	1,044.59	-702.24
Other Current Liabilities			
2070 · Deferred Inflows - Leases	205,965.00	205,965.00	0.00
2316 · Deferred Inflows - PSPRS OPEB	80,824.00	80,824.00	0.00
2318 · Deferred Inflows PSPRS OPEB TR3	164,454.27	164,454.27	0.00
2317 · Deferred Inflows PSPRS TR3	5,433.00	5,433.00	0.00
2230 · Accrued Interest	1,386.14	1,386.14	0.00
2030 · Compensated Absences Payable	112,803.10	140,557.78	-27,754.68
2020 · Accrued Wages	30,484.91	30,484.91	0.00
2315 · Deferred Inflows - PSPRS	583,470.00	583,470.00	0.00
2100 · Payroll Liabilities			
2102 · PSPRS Payable	39,435.57	-12,881.27	52,316.84
2103 · Pension Payable	0.00	100.00	-100.00
2128 · Health Insurance/Vision Ins.	94,610.78	-3,641.83	98,252.61
2140 · Pre-Paid Legal	-176.80	-44.12	-132.68
Total 2100 · Payroll Liabilities	133,869.55	-16,467.22	150,336.77

# Tubac Fire District Balance Sheet

As of July 31, 2024

	Jul 31, 24	Jul 31, 23	\$ Change
2310 · Deferred revenue 2311 · Deferred Revenue - Grants	-164,157.27	-164,157.27	0.00
Total 2310 · Deferred revenue	-164,157.27	-164,157.27	0.00
Total Other Current Liabilities	1,154,532.70	1,031,950.61	122,582.09
Total Current Liabilities	1,258,484.65	1,143,090.09	115,394.56
Long Term Liabilities			
2321 · 2024 Bonds Payable	4,400,000.00	0.00	4,400,000.00
1738 · SBITA Amortization	24,933.67	24,933.67	0.00
2605 · Subscription Llability	84,756.63	84,756.63	0.00
2335 · F150 Leases Payable	15,062.24	15,062.24	0.00
2330 · Ambulance Lease Payable	59,651.79	88,502.84	-28,851.05
2355 · Net Pension Liability - PSPRS	3,133,079.00	3,133,079.00	0.00
2320 · Bond Payable	1,818,836.37	2,247,641.79	-428,805.42
Total Long Term Liabilities	9,536,319.70	5,593,976.17	3,942,343.53
Total Liabilities	10,794,804.35	6,737,066.26	4,057,738.09
Equity			
3001 · Unrestricted	5,491,556.46	4,726,655.04	764,901.42
3510 · Restricted	-79,899.00	-79,899.00	0.00
3530 · Net Investment in Capital Asset	2,318,091.00	2,318,091.00	0.00
Net Income	-190,277.98	-311,293.19	121,015.21
Total Equity	7,539,470.48	6,653,553.85	885,916.63
TOTAL LIABILITIES & EQUITY	18,334,274.83	13,390,620.11	4,943,654.72

### **Tubac Fire District**


# **Summary of Reconciled Cash Balances**

Period Ending 07/31/2024


	Bank of America Checking	Santa Cruz County General Fund	Bank of America Savings	Santa Cruz County Bond Account	LGIP - State Investment Account
	7/31/2024	7/31/2024	7/31/2024	7/31/2024	7/31/2024
Beginning Balance	1,357,340.01	42,373.42	448,070.39	289,168.54	4,374,586.30
<b>Cleared Transactions</b>					
<b>Checks and Payments</b>	(456,842.35)	(42,373.42)	-	-	-
<b>Deposits and Credits</b>	156,705.34	16,220.79	15.18	5,854.41	19,913.34
<b>Total Cleared Transactions</b>	(300,137.01)	(26,152.63)	15.18	5,854.41	19,913.34
Cleared Balance	1,057,203.00	16,220.79	448,085.57	295,022.95	4,394,499.64
<b>Uncleared Transactions</b>					
<b>Checks and Payments</b>	(2,060.95)	-	-	-	-
<b>Deposits and Credits</b>					
<b>Total Uncleared Transactions</b>	(2,060.95)	-	-	-	-
Register Balance as of 07/31/2024	1,055,142.05	16,220.79	448,085.57	295,022.95	4,394,499.64


# **Tubac Fire District** Profit & Loss Budget Performance July 2024

_	Jul 24	Budget	\$ Over Budget	Jul 24	YTD Budget	\$ Over Budget	Annual Budget
Ordinary Income/Expense Income Tax Revenues	21,058.68	6,329.00	14,729.68	21,058.68	6,329.00	14,729.68	3,856,932.00
Non Tax Levy Revenue 4200 · Miscellaneous Revenue	27,187.70	19,792.00	7,395.70	27,187.70	19,792.00	7,395.70	2,597,440.00
4110 · EMS Revenue	82,640.78	50,833.00	31,807.78	82,640.78	50,833.00	31,807.78	610,000.00
4120 · Wildland Revenue	20,840.04	58,333.00	-37,492.96	20,840.04	58,333.00	-37,492.96	350,000.00
Total Non Tax Levy Revenue	130,668.52	128,958.00	1,710.52	130,668.52	128,958.00	1,710.52	3,557,440.00
Total Income	151,727.20	135,287.00	16,440.20	151,727.20	135,287.00	16,440.20	7,414,372.00
Gross Profit	151,727.20	135,287.00	16,440.20	151,727.20	135,287.00	16,440.20	7,414,372.00
Expense Personnel Expenses	259,964.62	306,777.00	-46,812.38	259,964.62	306,777.00	-46,812.38	3,630,817.00
Buildings & Land	14,244.59	21,888.00	-7,643.41	14,244.59	21,888.00	-7,643.41	262,650.00
Vehicles & Equipment	10,111.01	24,291.00	-14,179.99	10,111.01	24,291.00	-14,179.99	291,500.00
Communications & I.T.	31,749.12	12,811.00	18,938.12	31,749.12	12,811.00	18,938.12	153,730.00
Travel & Training	1,448.00	9,458.00	-8,010.00	1,448.00	9,458.00	-8,010.00	92,500.00
Managerial Expenses	24,487.84	29,607.00	-5,119.16	24,487.84	29,607.00	-5,119.16	250,675.00
Grant Expenses	0.00	0.00	0.00	0.00	0.00	0.00	382,940.00
Total Expense	342,005.18	404,832.00	-62,826.82	342,005.18	404,832.00	-62,826.82	5,064,812.00
Net Ordinary Income	-190,277.98	-269,545.00	79,267.02	-190,277.98	-269,545.00	79,267.02	2,349,560.00
Net Income	-190,277.98	-269,545.00	79,267.02	-190,277.98	-269,545.00	79,267.02	2,349,560.00









Personnel Expenses	76.01%
Communications & I.7	9.28
Managerial Expenses	7.16
Buildings & Land	4.17
Vehicles & Equipment	2.96
Travel & Training	0.42
Total	\$342,005.18

By Account

# Tubac Fire District Fixed Assets Additions and Disposals

### **Recorded in fixed asset accounts:**

Account			Addition/(D Amou	isposal)	
Number	Account name		Amou	unt	Description of Asset
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
			\$	-	
		TOTALS	\$	-	

Prepared


8/22/2024 JVG, Finance Director.

# TUBAC FIRE DISTRICT <u>Liabilities and Securities - FY24/25</u>


LIABILITIES									
Description	TOTAL PRICE	CURRENT BALANCE	INTEREST RATE	FY24/25 PAYMENTS	NEXT PAYMENT	DATE OF PAYOFF			
	<b>#0.705.000.00</b>	<b>#4.040.000.07</b>	0.000/	<b>0.10.1.0.10.77</b>	4/4/0005	7/4/0000			
Bond	\$6,795,000.00	\$1,818,836.37	2.36%	\$481,849.77	1/1/2025	7/1/2028			
2024 Bond Payable	\$4,400,000.00	\$4,400,000.00	5.00%	\$104,910.42	1/1/2025	7/1/2043			
Lease Payable	\$195,131.69	\$59,651.79	3.71%	\$32,134.51	2/1/2025	2/1/2026			
Net Pension Liability -									
PSPRS		\$3,133,079.00							
F150 Lease Payable		\$15,062.24							
	Totals	\$9,426,629.40		\$618,894.70		<u> </u>			

SECURITIES							
Broker	CUSIP#	Description	Market Value	Maturity Date			
		Totals	\$0.00				


# July 2024



# Percentage of Expenses Year to Date



# Cash Position



# **Tubac Fire District** Fleet Repairs & Maintenance July 2024

Date	Source Name	Memo	Amount
Ambulance 1055 07/24/2024	Larry H Miller	Oil Filter change, Replace Crank Case Ventilatio	1,964.92
Total Ambulance 1055			1,964.92
Apparatus Ambulance 1034 07/24/2024	Barnett's Towing Service	Towing Unit # 1034 in 07/24/24	1,075.25
Total Ambulance 1034			1,075.25
Brush 1048 07/27/2024	Jones Ford	2 New tires for unit 1048	1,003.37
Total Brush 1048			1,003.37
Total Apparatus			2,078.62
OTAL			4,043.54

# Tubac Fire District Station Utilities, Supplies, and Repairs & Maintenance July 2024

Date	Source Name	Memo	Amount	
Stations				
Station 1				
07/10/2024	EPCOR	Water bill For June 2024	34.76	
07/10/2024	Century Link 333219165	Monthly Fax and 911 Emergency Call Box Service	179.84	
07/17/2024	Unisource Energy Services (Gas)	Gas Bill for 06/17/24 - 07/16/24 2227 E. Frontage Rd	21.38	
07/17/2024	Unisource Energy Services (Gas)	Gas Bill for 06/17/24 - 07/16/24 2227 E. Frontage Rd	21.38	
07/19/2024	Direct TV - 9236	TV Current Charges for Service Period 07/18/24 - 08/17	164.98	
07/30/2024	John Schwamm	Remove existing Cameras from station 1 and reinstall at	600.00	
07/31/2024	Waste Management of Tucson	Trash Service for 2227 E. Frontage Rd from 08/01/24 - 0	255.3	
Total Station 1			1,277.6	
Station 2				
07/01/2024	Central Alarm	Access Control Full Service, 07/01/24 - 07/30/24	60.00	
07/10/2024	Century Link 333222406	Monthly Fax Service	61.8	
07/11/2024	Terminix	Commercial Pest Control Location: 1360 W. Frontage	60.0	
07/11/2024	Liberty Utilities AZ A/C 200007327162	Water Service	321.1	
07/23/2024	Unisource Energy Services (Electric)	2227 E. frontage 06/17/24 - 07/17/24	235.7	
07/23/2024	Unisource Energy Services (Electric)	563	1,220.3	
07/28/2024	Direct TV - 9885	Direct TV Current Charges for Service Period 07/27/24	152.9	
07/31/2024	Waste Management of Tucson	Trash Service for 1360 W. Frontage Rd from 08/01/24	691.7	
Total Station 2			2,803.68	
Station 3				
07/03/2024	Direct TV - 0393	Direct TV Current Charges for Service Period 07/02/24	172.9	
07/11/2024	Terminix	Commercial Pest Control Location: 1360 W. Frontage	149.0	
07/15/2024	Empire Southwest, LLC	Troubleshoot engine and Generator	619.4	
07/17/2024	Rio Rico Sanitation 85133	6 YRD ONCE A WEEK Aug 20	255.0	
07/30/2024	Applied Rite Doors & docks, Inc.	Bifold door stuck open Align photo eyes	390.00	
Total Station 3			1,586.43	
Station 4				
07/06/2024	Direct TV - 2827	Direct TV Current Charges for Service Period 07/05/24	172.9	
07/11/2024	Terminix	Commercial Pest Control Location: 1360 W. Frontage	152.0	
07/15/2024	Empire Southwest, LLC	Troubleshoot engine & Generator	619.4	
07/17/2024	Rio Rico Sanitation 84863	6 YRD ONCE A WEEK for08/01/24 - 08/031/24	255.0	
07/30/2024	BUSTAMANTE REFRIGERATION, L.L.C.	Replaced Blower Motor and Run Cap and Control Board	1,052.16	
Total Station 4		_	2,251.59	
otal Stations		<u> </u>	7,919.38	
ΓAL			7,919.38	

Туре	Date	Num	Name	Memo	Amount	Balance			
1133 · LGIP -	1133 · LGIP - State Investment Account								
Deposit	07/31/2024			Interest	19,913.34	19,913.34			
Total 1133 · Lo	GIP - State Ir	nvestment	Account	_	19,913.34	19,913.34			
1072 · Bill.cor	n Money Ou	t Clearin	a						
Bill Pmt	_		Unisource Energy Services (Elect	https://app01	-225.85	-225.85			
Bill Pmt			Unisource Energy Services (Elect	https://app01	-687.66	-913.51			
Bill Pmt			Century Link 333219165	https://app01	-206.00	-1,119.51			
Bill Pmt			Unisource Energy Services (Gas)	https://app01	-21.38	-1,140.89			
Bill Pmt	07/01/2024	Bill.com	Terminix	https://app01	-60.00	-1,200.89			
Bill Pmt	07/01/2024	Bill.com	Terminix	https://app01	-152.00	-1,352.89			
Bill Pmt	07/01/2024	Bill.com	Simply Bits, LLC	https://app01	-658.44	-2,011.33			
Bill Pmt	07/01/2024	Bill.com	Rio Rico Sanitation 85133	https://app01	<b>-</b> 510.00	-2,521.33			
Bill Pmt	07/01/2024	Bill.com	Simply Bits, LLC	https://app01	-559.52	-3,080.85			
Bill Pmt	07/01/2024	Bill.com	Direct TV - 9236	https://app01	-164.98	-3,245.83			
Bill Pmt	07/01/2024	Bill.com	Simply Bits, LLC	https://app01	-556.90	-3,802.73			
Bill Pmt	07/01/2024	Bill.com	Municipal Emergency Services	https://app01	-4,132.78	-7,935.51			
Bill Pmt	07/01/2024	Bill.com	Nextrio, LLC	https://app01	-2,024.81	-9,960.32			
Bill Pmt	07/01/2024	Bill.com	Unisource Energy Services (Elect	https://app01	-1,544.40	-11,504.72			
Bill Pmt	07/01/2024	Bill.com	Century Link 333222406	https://app01	-69.68	-11,574.40			
Bill Pmt	07/01/2024	Bill.com	Terminix	https://app01	-60.00	<b>-</b> 11,634.40			
Bill Pmt	07/01/2024	Bill.com	Rio Rico Sanitation 84863	https://app01	-510.00	-12,144.40			
Bill Pmt	07/01/2024	Bill.com	Terminix	https://app01	-149.00	<b>-</b> 12,293.40			
Bill Pmt	07/01/2024	Bill.com	Unisource Energy Services (Gas)	https://app01	-22.13	-12,315.53			
Bill Pmt	07/01/2024	Bill.com	Simply Bits, LLC	https://app01	-874.12	-13,189.65			
General J	07/01/2024	2023	· ·	BILL 07/01/2	13,189.65	0.00			
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-410.51	-410.51			
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-78.19	-488.70			
Bill Pmt	07/05/2024	Bill.com	Waste Management of Tucson	https://app01	-255.52	-744.22			
Bill Pmt	07/05/2024	Bill.com	Unisource Energy Services (Elect	https://app01	-1,054.00	-1,798.22			
Bill Pmt			Nogales Tactical LLC*	https://app01	-74.93	-1,873.15			

Туре	Date	Num	Name	Memo	Amount	Balance
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-659.75	-2,532.90
Bill Pmt			Great America Leasing Corp.	https://app01	-217.68	-2,750.58
Bill Pmt			Nogales Tactical LLC*	https://app01	-659.75	-3,410.33
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-156.38	-3,566.71
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-234.58	-3,801.29
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-338.83	-4,140.12
Bill Pmt	07/05/2024	Bill.com	Streamline	https://app01	-500.00	-4,640.12
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-38.01	-4,678.13
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-71.68	-4,749.81
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-135.75	-4,885.56
Bill Pmt	07/05/2024	Bill.com	Nogales Tactical LLC*	https://app01	-533.77	-5,419.33
Bill Pmt	07/05/2024	Bill.com	MetLife	https://app01	-1,569.09	-6,988.42
Bill Pmt	07/05/2024	Bill.com	Waste Management of Tucson	https://app01	-241.73	-7,230.15
Bill Pmt	07/05/2024	Bill.com	The Mahoney Group	https://app01	-703.00	-7,933.15
Bill Pmt			Nogales Tactical LLC*	https://app01	-683.64	-8,616.79
Bill Pmt			Direct TV - 9885	https://app01	-152.99	-8,769.78
General J	07/05/2024			BILL 07/05/2	8,769.78	0.00
Bill Pmt			J1 Plumbing	https://app01	-885.00	-885.00
Bill Pmt			J1 Plumbing	https://app01	-835.00	-1,720.00
Bill Pmt			J1 Plumbing	https://app01	-785.00	-2,505.00
Bill Pmt			Bound Tree	https://app01	-488.79	-2,993.79
Bill Pmt			Dreamseat	https://app01	-1,693.20	-4,686.99
Bill Pmt			Ricardo Rodriguez*	https://app01	-16.79	-4,703.78
Bill Pmt			PIMA COMMUNITY COLLEGE	https://app01	-16,700.00	-21,403.78
Bill Pmt			Unisource Energy Services (Elect	https://app01	-1,541.75	-22,945.53
General J	07/09/2024			BILL 07/09/2	22,945.53	0.00
Bill Pmt			Advanced Technical Services	https://app01	-2,662.50	-2,662.50
General J	07/12/2024			BILL 07/12/2	2,662.50	0.00
Bill Pmt	07/16/2024			https://app01	-468.75	-468.75
Bill Pmt			Valley Imaging Solutions Inc.	https://app01	-51.46	-520.21
Bill Pmt			Direct TV - 2827	https://app01	-172.98	-693.19
Bill Pmt	07/16/2024	Bill.com	Liberty Utilities AZ A/C 20000732	https://app01	-200.25	-893.44

Туре	Date	Num	Name	Memo	Amount	Balance
Bill Pmt	07/16/2024	Bill.com	Verizon	https://app01	-600.15	-1,493.59
Bill Pmt	07/16/2024	Bill.com	Streamline	https://app01	-500.00	-1,993.59
Bill Pmt	07/16/2024	Bill.com	Nextrio, LLC	https://app01	-711.72	-2,705.31
Bill Pmt	07/16/2024	Bill.com	CenturyLink	https://app01	-0.46	-2,705.77
Bill Pmt	07/16/2024	Bill.com	Santa Cruz County Landfill	https://app01	-32.85	-2,738.62
Bill Pmt	07/16/2024	Bill.com	Nextrio, LLC	https://app01	-4,517.00	-7,255.62
Bill Pmt	07/16/2024	Bill.com	Valley Imaging Solutions Inc.	https://app01	-18.76	-7,274.38
Bill Pmt	07/16/2024	Bill.com	Human Resource Strategies	https://app01	-500.00	-7,774.38
Bill Pmt	07/16/2024	Bill.com	Modular Solutions	https://app01	-800.00	-8,574.38
Bill Pmt	07/16/2024	Bill.com	Liberty Utilities AZ A/C 20000732	https://app01	<b>-</b> 570.85	-9,145.23
Bill Pmt	07/16/2024	Bill.com	Central Alarm	https://app01	-60.00	-9,205.23
Bill Pmt	07/16/2024	Bill.com	James Vincent Group	https://app01	-6,200.00	-15,405.23
General J	07/16/2024	2023		BILL 07/16/2	15,405.23	0.00
Bill Pmt			Green Valley Fire District	https://app01	-391.00	-391.00
Bill Pmt			Quill Corporation	https://app01	-239.74	-630.74
Bill Pmt			J2 Laboratories	https://app01	-28.00	-658.74
Bill Pmt			Pima County Fire Chief Association	https://app01	-150.00	-808.74
Bill Pmt	07/18/2024	Bill.com	Ohana Direct Primary Care, LLC	https://app01	-28,000.00	-28,808.74
Bill Pmt			Valley Imaging Solutions Inc.	https://app01	-79.51	-28,888.25
General J	07/18/2024			BILL 07/18/2	28,888.25	0.00
Bill Pmt			Bound Tree	https://app01	-3,197.20	-3,197.20
Bill Pmt			Nogales Tactical LLC*	https://app01	<b>-</b> 228.06	-3,425.26
Bill Pmt	07/29/2024			https://app01	-100.08	-3,525.34
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	<b>-</b> 95.57	-3,620.91
Bill Pmt			Holy Cross Hospital Pharmacy	https://app01	<b>-</b> 4.50	-3,625.41
Bill Pmt	07/29/2024		Terminix	https://app01	-149.00	-3,774.41
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-32.58	-3,806.99
Bill Pmt	07/29/2024	Bill.com	Terminix	https://app01	<b>-</b> 60.00	-3,866.99
Bill Pmt	07/29/2024	Bill.com	Direct TV - 0393	https://app01	-172.98	-4,039.97
Bill Pmt	07/29/2024	Bill.com	Terminix	https://app01	-152.00	-4,191.97
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-484.36	-4,676.33
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-38.01	-4,714.34

Туре	Date	Num	Name	Memo	Amount	Balance
Bill Pmt	07/29/2024	Bill.com	Legal Shield	https://app01	-233.35	-4,947.69
Bill Pmt	07/29/2024	Bill.com	Voyager Fleet Systems Inc	https://app01	-5,613.86	-10,561.55
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-193.31	-10,754.86
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-301.91	-11,056.77
Bill Pmt	07/29/2024	Bill.com	Canyon State Wireless	https://app01	-32,846.31	-43,903.08
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-410.86	-44,313.94
Bill Pmt	07/29/2024	Bill.com	Unisource Energy Services (Gas)	https://app01	-21.38	-44,335.32
Bill Pmt	07/29/2024	Bill.com	Unisource Energy Services (Gas)	https://app01	-21.38	-44,356.70
Bill Pmt	07/29/2024	Bill.com	Linde Gas & Equipment Inc.	https://app01	-215.10	-44,571.80
Bill Pmt	07/29/2024	Bill.com	EPCOR	https://app01	-34.76	-44,606.56
Bill Pmt	07/29/2024	Bill.com	Bound Tree	https://app01	-439.56	-45,046.12
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-156.38	-45,202.50
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-32.58	-45,235.08
Bill Pmt	07/29/2024	Bill.com	Rio Rico Sanitation 84863	https://app01	-255.00	-45,490.08
Bill Pmt	07/29/2024		Nogales Tactical LLC*	https://app01	-103.17	-45,593.25
Bill Pmt	07/29/2024		•	https://app01	-78.19	-45,671.44
Bill Pmt	07/29/2024		•	https://app01	-32.58	<b>-</b> 45,704.02
Bill Pmt			Senergy Petroleum	https://app01	-2,024.69	-47,728.71
Bill Pmt			3am Innovations, Inc	https://app01	-45,273.02	-93,001.73
Bill Pmt			Napa Auto Parts	https://app01	-493.97	-93,495.70
Bill Pmt			AKM Builders	https://app01	-14,730.00	-108,225.70
Bill Pmt	07/29/2024	Bill.com	Rio Rico Sanitation 85133	https://app01	-255.00	-108,480.70
Bill Pmt	07/29/2024	Bill.com	Linde Gas & Equipment Inc.	https://app01	-799.21	-109,279.91
Bill Pmt	07/29/2024	Bill.com	Linde Gas & Equipment Inc.	https://app01	-601.53	-109,881.44
Bill Pmt	07/29/2024	Bill.com	Fry Fire District*	https://app01	-1,795.76	-111,677.20
Bill Pmt	07/29/2024	Bill.com	United Fire Equipment Co.	https://app01	-1,337.37	-113,014.57
Bill Pmt	07/29/2024			https://app01	-164.98	-113,179.55
Bill Pmt	07/29/2024		Century Link 333219165	https://app01	-179.84	-113,359.39
Bill Pmt	07/29/2024	Bill.com	Liberty Utilities AZ A/C 20000732	https://app01	-321.11	-113,680.50
Bill Pmt			Nogales Tactical LLC*	https://app01	-24.98	-113,705.48
Bill Pmt	07/29/2024	Bill.com	Waxie Sanitary Supply	https://app01	<b>-</b> 457.70	-114,163.18
Bill Pmt	07/29/2024	Bill.com	United Fire Equipment Co.	https://app01	-54.77	-114,217.95

Туре	Date	Num	Name	Memo	Amount	Balance
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-301.91	-114,519.86
Bill Pmt	07/29/2024		Handtevy	https://app01	-2,353.84	-116,873.70
Bill Pmt	07/29/2024	Bill.com	Nogales Tactical LLC*	https://app01	-139.01	-117,012.71
General J	07/29/2024	2023	•	BILL 07/29/2	117,012.71	0.00
Bill Pmt	07/30/2024	Bill.com	Simply Bits, LLC	https://app01	-562.03	-562.03
Bill Pmt	07/30/2024	Bill.com	Simply Bits, LLC	https://app01	-558.85	-1,120.88
Bill Pmt	07/30/2024	Bill.com	Simply Bits, LLC	https://app01	-876.80	-1,997.68
Bill Pmt	07/30/2024	Bill.com	Simply Bits, LLC	https://app01	-125.00	-2,122.68
Bill Pmt	07/30/2024	Bill.com	Simply Bits, LLC	https://app01	-661.22	-2,783.90
General J	07/30/2024	2023		BILL 07/30/2	2,783.90	0.00
General J	07/31/2024	2023		_	590.65	590.65
Total 1072 · Bi	II.com Mone	y Out Cle	aring		590.65	590.65
1127 · Cash w	_		r			
Deposit	07/10/2024			County chec	-42,373.42	-42,373.42
General J	07/31/2024	2023		to record pro	16,017.18	-26,356.24
Deposit	07/31/2024			Interest	203.61	-26,152.63
Total 1127 · Ca	ash with Cou	nty Treas	eurer		-26,152.63	-26,152.63
1129 · Operati	onal					
General J	07/01/2024	2023		BILL 07/01/2	-13,189.65	-13,189.65
Deposit	07/01/2024			Deposit	1,170.08	-12,019.57
Deposit	07/01/2024			Deposit	2,830.12	-9,189.45
Check	07/01/2024	ACH	PUBLIC SAFETY PERSONAL R	Pay Period	-18,872.09	-28,061.54
Deposit	07/02/2024			Deposit	20,840.04	-7,221.50
Check	07/02/2024		Bank of America	Merchant Se	-794.83	-8,016.33
Deposit	07/03/2024			Deposit	831.23	-7,185.10
Deposit	07/03/2024			Deposit	164.48	-7,020.62
Deposit	07/03/2024			Deposit	3,306.76	-3,713.86
Deposit	07/03/2024			Deposit	1,141.36	-2,572.50
Deposit	07/03/2024			Deposit	4,215.60	1,643.10

Туре	Date	Num	Name	Memo	Amount	Balance
General J	07/05/2024	2023		BILL 07/05/2	-8,769.78	-7,126.68
Deposit	07/05/2024			Deposit	1,835.13	-5,291.55
Deposit	07/05/2024			Deposit	2,367.54	-2,924.01
Check	07/05/2024	ACH	Aetna	July 2024- Bi	-19,769.12	-22,693.13
Deposit	07/08/2024			Deposit	3,523.96	-19,169.17
Deposit	07/08/2024			Deposit	120.00	-19,049.17
Deposit	07/08/2024			Deposit	15,180.12	-3,869.05
Deposit	07/08/2024			Deposit	453.28	-3,415.77
Check	07/08/2024	EFT	Bill.com		-199.75	-3,615.52
General J	07/09/2024	2023		BILL 07/09/2	-22,945.53	-26,561.05
Deposit	07/09/2024			Deposit	456.14	-26,104.91
Deposit	07/09/2024			Deposit	1,893.69	-24,211.22
Deposit	07/09/2024			Deposit	30.38	-24,180.84
Deposit	07/09/2024			Deposit	1.40	-24,179.44
Deposit	07/10/2024			Deposit	46,736.23	22,556.79
Deposit	07/10/2024			Deposit	5,789.31	28,346.10
Check	07/10/2024				-3,255.59	25,090.51
Check	07/11/2024		Security Benefit	Pay Period	-75.00	25,015.51
Check	07/11/2024	26069	Green Valley F.F.A.	Pay Period	-324.00	24,691.51
Deposit	07/11/2024			Deposit	320.53	25,012.04
Deposit	07/11/2024			Deposit	2,625.95	27,637.99
General J	07/12/2024			BILL 07/12/2	-2,662.50	24,975.49
General J	07/12/2024				-62,504.38	-37,528.89
General J	07/12/2024				-733.57	-38,262.46
General J	07/12/2024				-11,794.85	-50,057.31
General J	07/12/2024				-402.25	-50,459.56
General J	07/12/2024				-14,022.30	-64,481.86
Check	07/15/2024		Nationwide Retirement Solutions	Pay Period	-1,215.24	-65,697.10
Check	07/15/2024	ACH	Nationwide Retirement Solutions	Pay Period	-2,166.92	-67,864.02
Deposit	07/15/2024			Deposit	7,352.96	-60,511.06
General J	07/16/2024	2023		BILL 07/16/2	-15,405.23	-75,916.29
Deposit	07/16/2024			Deposit	2,743.49	-73,172.80

Туре	Date	Num	Name	Memo	Amount	Balance
General J	07/16/2024	2023		FDMS Pymt	-42.93	-73,215.73
Check	07/17/2024	ACH	Aflac	INVOICE# 4	-216.72	-73,432.45
Deposit	07/17/2024			Deposit	149.38	-73,283.07
Deposit	07/17/2024			Deposit	492.22	-72,790.85
General J	07/18/2024	2023		BILL 07/18/2	-28,888.25	-101,679.10
Deposit	07/19/2024			Deposit	127.29	-101,551.81
Deposit	07/22/2024			Deposit	350.00	-101,201.81
Check	07/23/2024	ACH	PUBLIC SAFETY PERSONAL R	Pay Period	-21,618.77	-122,820.58
Deposit	07/24/2024			Deposit	8,044.79	-114,775.79
Deposit	07/24/2024			Deposit	1,970.53	-112,805.26
Deposit	07/24/2024			Deposit	2,188.85	-110,616.41
Deposit	07/24/2024			Deposit	150.00	-110,466.41
Check	07/25/2024	26070	Lopez, Anthony	Reimbursem	-213.49	-110,679.90
Deposit	07/25/2024			Deposit	100.00	-110,579.90
Deposit	07/25/2024			Deposit	5,659.91	-104,919.99
General J	07/26/2024				-63,746.29	-168,666.28
General J	07/26/2024				-748.09	-169,414.37
General J	07/26/2024				-12,858.60	-182,272.97
General J	07/26/2024				-414.55	-182,687.52
General J	07/26/2024	2023			-3,172.30	-185,859.82
General J	07/26/2024	2023			-738.94	-186,598.76
General J	07/26/2024	2023			-110.15	-186,708.91
General J	07/26/2024	2023			-208.09	-186,917.00
Check	07/29/2024	EFT			-4,119.51	-191,036.51
General J	07/29/2024	2023		BILL 07/29/2	-117,012.71	-308,049.22
Deposit	07/29/2024			Deposit	1,149.44	-306,899.78
Deposit	07/29/2024			Deposit	1,371.01	-305,528.77
Deposit	07/29/2024			Deposit	1,792.23	-303,736.54
Deposit	07/29/2024			Deposit	290.00	-303,446.54
Check	07/30/2024	26071	Security Benefit	Pay Period 7	<b>-</b> 75.00	-303,521.54
Check	07/30/2024		Green Valley F.F.A.	Pay Period	-342.00	-303,863.54
General J	07/30/2024	2023		BILL 07/30/2	-2,783.90	-306,647.44

#### Tubac Fire District Monthly Transaction Report July 2024

Type	Date	Num	Name	Memo	Amount	Balance
Deposit	07/30/2024			Deposit	4,212.82	-302,434.62
Check	07/30/2024	ACH	Public Safety Cancer Insurance	PSPRS Can	-1,150.00	-303,584.62
Deposit	07/30/2024		·	Deposit	1,250.00	-302,334.62
Deposit	07/30/2024			Deposit	993.16	-301,341.46
Deposit	07/30/2024			Deposit	238.07	-301,103.39
Deposit	07/31/2024			Deposit	245.86	-300,857.53
Total 1129 ·	Operational				-300,857.53	-300,857.53
1130 · Savir	ngs Acct.					
Deposit	07/28/2024			Interest	15.18	15.18
Total 1130 ·	Savings Acct.				15.18	15.18
1131 · Bond	l Account					
General J.	07/31/2024	2023		to record pro	5,041.50	5,041.50
Deposit	07/31/2024			Interest	812.91	5,854.41
Total 1131 ·	Bond Account			_	5,854.41	5,854.41
TOTAL				_	-300,636.58	-300,636.58

08/22/2024

#### **Tubac Fire District**

Twelve-Month Cash Flow

Fiscal Year
Begins:

Jul-24

														Monthly
	Beginning	Jul-24	Aug-24	Sep-24	Oct-24	Nov-24	Dec-24	Jan-25	Feb-25	Mar-25	Apr-25	May-25	Jun-25	Average Overview
Cash Summary														
Cash on Hand (beginning of month)	10,909,608	10,909,608	10,608,971	10,366,174	10,252,886	10,845,500	11,323,274	11,500,624	11,348,240	11,241,787	11,130,481	11,578,461	11,463,065	11,047,423
Cash Available (on hand + receipts, before cash out)	10,909,608	11,066,534	10,772,332	10,512,024	11,237,560	11,733,149	12,055,936	11,740,750	11,574,005	11,462,876	11,999,832	11,915,226	13,920,128	11,665,863 ıllııll
Cash Position (end of month)	10,909,608	10,608,971	10,366,174	10,252,886	10,845,500	11,323,274	11,500,624	11,348,240	11,241,787	11,130,481	11,578,461	11,463,065	10,909,607	11,047,423
Line of Credit Available	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	
Cash Receipts														
Tax Levy Revenue		21,059	34,403	16,892	914,049	817,024	482,067	169,501	155,140	150,464	740,393	207,807	148,133	321,411 _
Other Cash Inflows		135,868	128,958	128,958	70,625	70,625	250,595	70,625	70,625	70,625	128,958	128,958	2,308,930	297,029
Line of Credit		0	0	0	0	0	0	0	0	0	0	0	0	0
Total Cash Receipts		156,927	163,361	145,850	984,674	887,649	732,662	240,126	225,765	221,089	869,351	336,765	2,457,063	618,440
Cash Paid Out														
Disbursements		457,563	406,158	259,138	392,060	409,875	555,312	392,510	332,218	332,395	421,371	452,161	3,010,521	618,440
Repayment of LOC		0	0	0	0	0	0	0	0	0	0	0	0	0
Total Cash Paid Out		457,563	406,158	259,138	392,060	409,875	555,312	392,510	332,218	332,395	421,371	452,161	3,010,521	618,440
	(	(Actual)	(Budget)	(Budget)	(Budget)	(Budget) (	Budget)	(Budget)	(Budget)	(Budget)	(Budget)	(Budget)	(Budget)	

Intermediate Plans

AUGUST 2024

REVISION SCHEDULE: # DATE DESCRIPTION

DRAWN BY: JCG

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT.
ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED


COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS




# Tubac Fire Station #1

2227 I-19 Frontage Rd., Tubac, Arizona 85646

Intermediate Plans AUGUST 2024








architects

Occupo	ancy Loads					P
-	BUILDING		OCCUPANCY (65 TOTAL))	Occupancy	LOAD FACTOR	
Number	Name	AREA	IBC 2012 Chapter 3	Туре	IBC 2012 Table 1004.1.2	
·						
	Room	Not Placed				
101	LOBBY	114 SF	1	В	100	
102	OPEN OFFICE	659 SF	7	В	100	
103	CONFERENCE ROOM	308 SF	3	В	100	
104	IT	55 SF	1	В	100	
105	FIRE CHIEF	172 SF	2	В	100	
106	ASSISTANT CHIEF	103 SF	1	В	100	
107	BREAK	120 SF	1	В	100	
108	WOMEN'S	86 SF	1	В	100	
109	MEN'S	85 SF	1	В	100	
110	F.F STUDY	104 SF	1	В	200	
112	KITCHEN/ DAYROOM	726 SF	3	В	200	
113	FITNESS	405 SF	8	В	50	
114	OFFICE	90 SF	1	В	100	
115	AIRLOCK	50 SF	0	В	200	
116	SHOWER	73 SF	1	В	200	
117	SHOWER	73 SF	1	В	200	
118	HALL	260 SF	1	В	200	
119	DORM	114 SF	1	R2	50	
120	DORM	116 SF	1	R2	50	
121	DORM	116 SF	1	R2	50	
122	DORM	116 SF	1	R2	50	
123	STOR.	23 SF				
124	DORM	115 SF	1	R2	50	
125	MED STO.	87 SF	1	В	300	
126A	JAN.	Not Placed	0	В	200	
126B	MECH. ROOM	81 SF	1	В	200	
127	APPARATUS BAYS	4064 SF	20	В	200	
128	GENERAL STORAGE	70 SF	1	В	300	
129	TURN-OUT ROOM	227 SF	1	В	300	
130	ELECTRIC	112 SF	1	В	300	
131	FIRE RISER	40 SF				
			ı	1		

DESCRIPTION	IBC 2012 SECTION	IBC 2012 REQUIREMENTS	COMPLIANT
BUILDING HEIGHT AND AREA LIMITATIONS	SECTION 503, TABLE 503		
FIRESTATION BUILDING			
TYPE OF CONSTRUCTION	VB		
TUBULAR BUILDING AREA	9,000		
BUILDING HEIGHT	2- STORY		
BUILDING AREA MODIFICATIONS	SECTION 506		
	$Aa = \{ At + [At X If] + [At X Is] \}$		
BUILDING AREAS SHALL BE PERMITTED TO BE	$A\alpha = ALLOWABLE AREA$ $A\alpha = ALLOWABLE BUILDING AREA$		
INCREASED DUE TO FRONTAGE & AUTOMATIC	At = TUBULAR BUILDING AREA / STORY		
SPRINKLER PROTECTION	If = AREA INCREASE FACTOR DUE TO FRONTAGE		
	Is = AREA INCREASE DUE SPRINKLER PROTECTION $A\alpha = \{ 14,500 + [ 14,500 \times 2 ] \} = 43,500$		
INCIDENTAL USE SEPARATION AND/ OR PROTECTION	SECTION 509.2	INCIDENTAL USES SHALL NOT BE INDIVIDUALLY	V
INCIDENTAL USE SEI AKAHON AND, OK I KOTECHON	3ECHON 307.2	CLASSIFIED IN ACCORDANCE WITH SECTION	у у
		302.1	у
FIRE- RESISTANCE RATING REQUIREMENTS	SECTION 601, TABLE 601	PRIMARY STRUCTURAL FRAME O	
FOR BUILDING ELEMENTS	CONSTRUCTION TYPE VB	EXTERIOR BEARING WALLS 0	у у
I ON DOILDING ELLIALINIS	CONSTRUCTION TITE VD	INTERIOR BEARING WALLS 0	у у
		EXT. NONBEARING WALLS 0	у
		INT. NONBEARING WALLS 0	у у
		FLOOR CONSTRUCTION 0	у
		ROOF CONSTRUCTION 0	у у
MAXIMUM AREA OF EXTERIOR WALL OPENING	SECTION 705, TABLE 705.8	NOT REQUIRED	
BASED ON THE FIRE SEPARATION DISTANCE	3ECTION 703, TABLE 703.8	NOT REQUIRED	у
DAGED ON THE TIRE GET ARATION DIGITALISE			, ,
VERTICAL SEPARATION OF OPENINGS	SECTION 705.8.5	THIS SECTION DOES NOT APPLY TO BUILDINGS	У
		THAT ARE THREE STORIES OR LESS	у у
		ABOVE GRADE	у
SHAFT ENCLOSURES	SECTION 713.4	1 HR WHERE CONNECTING LESS	У
OTA T EL VEEGGOREE	FIRE RESISTANCE RATED	THAN FOUR STORIES	у
AUTOMATIC SYSTEM	SECTION 903.2.3	NOT REQUIRED	У
			,
MINIMUM STAIR WIDTH	TABLE 1005.3.1	0.2 INCH X OCCUPANT	У
REQUIRED CAPACITY BASED ON OCCUPANCY LOAD	TABLE 1005.3.1	0.2 INCH X OCCUPANT	у
MINIMUM DOOR WIDTH	TABLE 1005.3.2	0.15 INCH PER OCCUPANT	у
MAXIMUM TRAVEL DISTANCE BEFORE COMMON	TABLE 1014.3	100 FEET	у
PATH OF EGRESS			,
EXIT TRAVEL DISTANCE	TABLE 1016.2	250 FEET	у
CORRIDOR FIRE- RESISTANCE RATING	TABLE 1018.1	WITH SPRINKLER SYSTEM	У
COMMON TIME REGISTANCE NATION	IABLE TOTO!!	0.5	у у
AIN HARLES CORRESCO A SECTION	T1015 1010 0	4415100100	
MINIMUM CORRIDOR WIDTH	TABLE 1018.2	44 INCHES	у
		MECHANICAL, PLUMBING, ELECTRICAL= 24 INCHES	У
DEAD END CORRIDORS	TABLE 1018.4	NOT EXEED 50 FEET	
DEAD EIND COKKIDOKS	IADLE 1010.4	INOT EVEED ON LEET	У




AREA/OCCP. = 50

OCCP.= 8



OCCUPANCY TYPE BUSINESS (B)	<u>WC MALE</u> 1 PER 25*	WC FEMALE 1 PER 25*	<u>LAV MALE</u> 1 PER 40**	<u>LAV FEMALE</u> 1 PER 40**	BATHTUBS/ SHOWERS -	<u>Service Sink</u> 1 required
RESIDENTIAL (R2)	1 PER 10	1 PER 10	1 PER 8	1 PER 8	-	1 REQUIRED
OCCUPANCY LOAD =	= 65 (33M + 3	3F)				
REQUIRED:	2	2	1	1	1	1
PROVIDED:	2	2	2	2	1	1
* 1 PER 25 FOR THE F	IRST 50 AND 1	PER 50 FOR THE	REMAINDER E	EXCEEDING 50		
** 1 PER 40 FOR THE	FIRST 80 AND 1	PER 80 FOR TH	ie remainder	EXCEEDING 80		
Occupants: 65	WC M	1: 33 LAV	M: 33 W	/C F: 33 L/	AV F: 33 Bathtubs	/ Showers

Exiting Data



architects planners 1735 e ft. lowell rd. #12

> tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Occupancy Legend



**R2** OCCUPANCY

1 HR RATED PARTITION



**B** OCCUPANCY



\$1 OCCUPANCY



**\$2** OCCUPANCY

#### Site Data

CURRENT ZONING: HB2

USE RESTRICTIONS: HB2

SITE AREA: 150,762.03 SF.

MAXIMUM LOT COVERAGE: ACTUAL: 21.33% ALLOWABLE:

**DEVELOPMENT STANDARDS:** MINIMUM FRONT YARD -MINIMUM REAR YARD -

MINIMUM SIDE YARD -**BUILDING HEIGHT RESTRICTIONS:** MAXIMUM BUILDING HEIGHT = 2 STORIES

ACTUAL BUILDING HEIGHT = 1 STORY, 26FT.


PARKING CALCULATIONS:

PER SANTA CRUZ COUNTY DEVELOPMENT CODE PARKING SPACES = 1 SPACE / 500 SQ. FT.

18 REGULAR SPACES + 2 ADA SPACES

REQUIRED - 20 PARKING SPACES PROVIDED - 20 PARKING SPACES

# Fire Station **Tubac** 



Plans

Intermediate

PROJECT NO: 23.21.00

AUGUST 2024

REVISION SCHEDULE: # DATE DESCRIPTION

DRAWN BY: JCG

CHECKED BY: CDA

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR

DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Code Check Egress Plan

Safety Plan

Plumbing Fixture Count

PER IBC 2012 TABLE 2902.1:

WOMEN'S 1.3 0.81 1.3 0.81 1 REQ. 1.3 0.81 1.3 0.81 1 REQ.

#### **GENERAL NOTES**

- 1. EXCESS SOIL GENERATED FORM EARTHWORK OPERATIONS SHALL BE REMOVED FROM THE SITE AND LAWFULLY DISPOSED OF OF, OR IF ALLOWED AND APPROVED BY THE TOWN ENGINEER, SITE MATERIAL MAY BE PLACED SO AS TO BECOME AN INTEGRAL PART OF THE SITE DEVELOPMENT, ALL IN ACCORDANCE WITH THE HILLSIDE DEVELOPMENT REGULATIONS.
- 2. CUT AND FILL SLOPES AND LOPE TREATMENT TO BE IN COMPLIANCE WITH THE REQUIREMENTS OF THE ACCEPTED GEOTECHNICAL ENGINEERING INVESTIGATION.
- 3. EXCESS SOIL MATERIAL GENERATED FROM EARTHWORK OPERATIONS SHALL NOT BE DISPOSED OF BY PUSHING OR PLACING SID MATERIAL INTO THE AREAS DESIGNATED AS 100 YEAR FLOODPLAIN AREAS.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ASSURING PROPER AND ADEQUATE DRAINAGE.
- 5. ELEVATION OF FINISHED PADS SHALL BE CERTIFIED BY A REGISTERED LAND SURVEYOR PRIOR TO POURING FOUNDATIONS.
- 6. EXISTING UTILITY INFORMATION BASED ON FIELD SURVEY INFORMATION AND AS-BUILT PLANS. CONTRACTOR TO VERIFY LOCATION OF EXISTING UTILITIES AND RELOCATE, IF NECESSARY, TO REMOVE UTILITIES FROM PROPOSED BUILDING FOOTPRINTS. CONTRACTOR TO COORDINATE RELOCATION WITH UTILITY COMPANY IF NECESSARY.
- 7. CONCRETE SPLASH BLOCKS SHALL BE PLACED AT ALL ROOF DRAIN OUTLETS. CONTRACTOR MAY CONSTRUCT RIP-RAP SPLASH PADS OVER FILTER FABRIC OR GROUTED RIP-RAP IN LIEU OF SPLASH BLOCKS.
- 8. CONTRACTOR TO COORDINATE FINAL UTILITY ROUTING AND SIZE.
- 9. FINISHED SLOPES MUST CONFORM TO THE FOLLOWING: 3:1 (HORIZONTAL/VERTICAL FOR FLATTER SHALL BE REVEGETATED SIMILAR TO SURROUNDING DÉSERT.

SLOPES 2:1 OR FLATTER BUT STEEPER THAN 3:1 SHALL BE STABILIZED WITH ROCK RIP-RAP OVER FILTER FABRIC.

SLOPES STEEPER THAN 2:1 SHALL BE STABILIZED WITH GROUTED RIP-RAP OR RETAINING WALLS AS APPROPRIATE. SLOPES SHALL NOT EXCEED 1:1.

ALTERNATIVE METHODS OF STABILIZATION MAY BE ALLOWED WHEN SUPPORTED BY A GEOTECHNICAL REPORT PREPARED BY AN ARIZONA REGISTRANT.

#### PAVING AND GRADING NOTES

- 1. ALL CONSTRUCTION AND TEST METHODS SHALL BE IN CONFORMANCE WITH PIMA COUNTY/CITY OF TUCSON STANDARD SPECIFICATIONS FOR PUBLIC IMPROVEMENTS (PC/COT SSPI) 2003 EDITION.
- 2. ALL CONCRETE SHALL COMPLY TO PC/COT SSPI SECTION 1006, CLASS S, 3,000 P.S.I. COMPRESSIVE STRENGTH AT 28 DAYS, UNLESS OTHERWISE SPECIFIED.
- 3. THE CONTRACTOR SHALL FURNISH, HAUL, AND APPLY ALL WATER REQUIRED FOR COMPACTION AND FOR THE CONTROL OF DUST FROM CONSTRUCTION ACTIVITY.
- 4. A SOILS ENGINEER SHALL OBSERVE, INSPECT AND TEST ALL EARTHWORK AND PAVING OPERATIONS, INCLUDING BUT NOT LIMITED TO: CLEARING, GRUBBING, SUBGRADE PREPARATION, STRUCTURAL AND TRENCH EXCAVATION AND BACK FILL, TOGETHER WITH PLACEMENT AND COMPACTION OF FILL, PARKING ARE SURFACING, PAVING AND CONCRETE WORK.
- 5. THE CONTRACTOR SHALL ADJUST BOTH EXISTING AND NEW WATER VALVES, BOX COVERS, WATER METER BOXES, SANITARY SEWER MANHOLES AND CLEANOUT RING AND COVERS, TELEPHONE AND ELECTRIC MANHOLE RINGS AND COVERS TO FINISHED GRADE.
- 6. EXCAVATION AND BACKFILL FOR STRUCTURES SHALL CONFORM TO PC/COT SSPI, SECTION 203-5.

#### **EXISTING UTILITY NOTE**

EXISTING UTILITY LOCATIONS, AS SHOWN ON THE PLANS, WERE COMPILED FROM UTILITY COMPANY BASE MAPS, RECORD PLANS AND ABOVE GROUND FEATURES. HOWEVER, UTILITY LOCATIONS ARE NOT TO BE CONSIDERED EXACT OR COMPLETE. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL WITH THE APPROPRIATE ORGANIZATION AND, IF NECESSARY, POTHOLE ANY AND ALL UTILITY LOCATIONS IN QUESTION. THE CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES "IN-PLACE" UNLESS OTHERWISE NOTED ON THE CONSTRUCTION DOCUMENTS.

## **LEGEND**


EXISTING SUBJECT PROPERTY LINE  EXISTING EASEMENT  EXISTING RIGHT-OF-WAY  EXISTING INDEX (MAJOR) CONTOUR EXISTING INTERMEDIATE (MINOR) CONTOUR EXISTING FENCE LINE  EXISTING ROADWAY CENTERLINE  EXISTING ASPHALT PAVEMENT  EXISTING WATER LINE  SS SS EXISTING SANITARY SEWER LINE  EXISTING GAS LINE  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE  PROPOSED SIDEWALK		
EXISTING RIGHT—OF—WAY		EXISTING SUBJECT PROPERTY LINE
EXISTING INDEX (MAJOR) CONTOUR EXISTING INTERMEDIATE (MINOR) CONTOUR EXISTING FENCE LINE EXISTING ROADWAY CENTERLINE EXISTING ASPHALT PAVEMENT EXISTING WATER LINE EXISTING SANITARY SEWER LINE EXISTING GAS LINE EXISTING OVERHEAD WIRE EXISTING ELECTRIC LINE EXISTING UNDERGROUND ELECTRIC LIN PROPOSED CONCRETE		EXISTING EASEMENT
EXISTING INTERMEDIATE (MINOR) CONTOUR EXISTING FENCE LINE EXISTING ROADWAY CENTERLINE EXISTING ASPHALT PAVEMENT EXISTING WATER LINE EXISTING SANITARY SEWER LINE EXISTING GAS LINE EXISTING OVERHEAD WIRE EXISTING ELECTRIC LINE EXISTING UNDERGROUND ELECTRIC LIN PROPOSED CONCRETE		EXISTING RIGHT-OF-WAY
EXISTING ROADWAY CENTERLINE  EXISTING ASPHALT PAVEMENT  EXISTING WATER LINE  EXISTING SANITARY SEWER LINE  EXISTING GAS LINE  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE		EXISTING INTERMEDIATE (MINOR)
EXISTING ASPHALT PAVEMENT  W EXISTING WATER LINE  EXISTING SANITARY SEWER LINE  EXISTING GAS LINE  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE	xx	EXISTING FENCE LINE
EXISTING WATER LINE  SS—SS—EXISTING SANITARY SEWER LINE  EXISTING GAS LINE  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE		EXISTING ROADWAY CENTERLINE
EXISTING SANITARY SEWER LINE  EXISTING GAS LINE  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE		EXISTING ASPHALT PAVEMENT
EXISTING GAS LINE  OH-E  EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LIN  PROPOSED CONCRETE	———— W————	EXISTING WATER LINE
EXISTING OVERHEAD WIRE  EXISTING ELECTRIC LINE  EXISTING UNDERGROUND ELECTRIC LINE  PROPOSED CONCRETE	2222	EXISTING SANITARY SEWER LINE
EXISTING ELECTRIC LINE  WG-E  EXISTING UNDERGROUND ELECTRIC LIN  PROPOSED CONCRETE	G	EXISTING GAS LINE
EXISTING UNDERGROUND ELECTRIC LIN PROPOSED CONCRETE	———— OH-E———	EXISTING OVERHEAD WIRE
PROPOSED CONCRETE	——— E———	EXISTING ELECTRIC LINE
The state of the s	——————————————————————————————————————	EXISTING UNDERGROUND ELECTRIC LIN
PROPOSED SIDEWALK	A	PROPOSED CONCRETE
		PROPOSED SIDEWALK



#### SITE KEY NOTES

- 1 NEW ASPHALT PAVEMENT.
- (2) NEW CONCRETE PAVEMENT.
- 3 NEW CONCRETE VERTICAL CURB, TYPE 2, PER PAG SD 209.
- 4 NEW CONCRETE HEADER PER PAG SD 213.
- 5 NEW CONCRETE SIDEWALK PER PAG SD 200. ALL ACCESSIBLE ROUTE SLOPES ARE TO COMPLY WITH 2010 ADASAD SECTION 403.3, 5% MAXIMUM RUNNING SLOPE AND 2% MAXIMUM CROSS SLOPE.
- 6 NEW CONCRETE CURB ACCESS RAMP.
- (7) STANDARD PARKING SPACE.
- (8) HANDICAP PARKING SPACE.
- 9 NEW TRASH ENCLOSURE.

- NEW CONCRETE VERTICAL CURB AND GUTTER, TYPE 1G, PER PAG SD 209.
- $\langle 11 \rangle$  NEW GATE.
- (12) NEW COMMUNICATIONS SHELTER PAD.
- (13) NEW TOWER PAD.
- (14) NEW BIKE RACK.
- (15) BASIN AREA.
- (16) NEW VALLEY GUTTER PER PAG SD 208.
- (17) CURB OPENING.






architects planners

#

Tubac



PROJECT NO:


DRAWN BY: BDB CHECKED BY: RRS THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF

BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE

SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &






- DEMO BUILDING STRUCTURE
- DEMO ASPHALT PAVING
- DEMO CONCRETE SLAB
- DEMO CONCRETE SIDEWALK
- REMOVE MODULAR BUILDING
- DEMO STACKED STONE W/ WALL
- DEMO PERIMETER CHAIN LINK FENCE
- DEMO + REMOVE FLAG POLE & DEMO CONC. BASE
- DEMO SLAB
- REMOVE GAS TANK
- DEMO CANOPY STRUCTURE
- REMOVE STEEL STORAGE SHED
- REMOVE MECHANICAL EQUIPMENT
- REMOVE VEGETATION



architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# **Station Tubac Fire** 



Intermediate Plans

PROJECT NO: 23.21.00

AUGUST 2024 REVISION SCHEDULE:
# DATE DESCRIPTION ISSUED TO


DRAWN BY: JCG

CHECKED BY: CDA THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS





## Keynotes


- 8 CONCRETE VERTICAL CURB AND GUTTER
- (12) THERMOPLASTIC ASPHALT STRIPPING
- (13) SAND/ OIL INTERCEPTOR
- (15) CHAINLINK FENCE
- (16) WROUGHT IRON FENCE
- (18) COMMUNICATIONS SHELTER PAD



architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# Station **Tubac Fire** 



Intermediate Plans

PROJECT NO: 23.21.00

AUGUST 2024

REVISION SCHEDULE:
# DATE DESCRIPTION


DRAWN BY: JCG


CHECKED BY: CDA THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Architectural Site Plan







#### General Notes

- 1. ALL DIMENSIONS OF METAL STUD WALLS ARE TO THE FACE OF THE STUD.
- 2. ALL DOORS ON METAL STUD PARTITION WALLS TO BE 4" FROM PERPENDICULAR WALL TO OUTSIDE OF FRAME, UNO.
- 3. STRUCTURAL GRID LINES ARE TO COLUMN CENTERLINE.
- 4. REFER TO STRUCTURAL DRAWINGS FOR CONCRETE SLAB CONTROL JOINT LOCATION.
- 5. FLOOR AND WALL OPENINGS, SLEEVES, VARIATIONS IN THE STRUCTURAL SLAB ELEVATIONS, DEPRESSED AREAS, AND ALL OTHER ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND OR CIVIL REQUIREMENTS MUST BE COORDINATED BY THE CONTRACTOR BEFORE THE CONTRACTOR PROCEEDS WITH CONSTRUCTION.
- 6. DETAILS MARKED "TYP" SHALL APPLY IN ALL CASES UNLESS SPECIFICALLY INDICATED OTHERWISE.
- 7. WHERE NO SPECIFIC DETAIL IS SHOWN, THE FRAMING OR CONSTRUCTION SHALL BE IDENTICAL OR SIMILAR TO THAT INDICATED FOR LIKE CASES OF CONSTRUCTION ON THE PROJECT.
- 8 . DETAILS MARKED "SIM" MEANS COMPARABLE CHARACTERISTS FOR THE CONDITIONS NOTED. VERIFY SIMILAR DIMENSIONS OR NOTES ON THE DRAWINGS.
- 9. USE MOISTURE RESISTANT GYPSUM WALLBOARD ON ALL PARTITIONS WHICH ARE EXPOSED TO WATER OR MOISTURE FOR EXAMPLE, JANITOR'S CLOSETS, RESTROOMS, AND LAUNDRY ROOMS.
- 10. SLOPE FLOORS TO DRAINS AS SHOWN ON DRAWINGS.
- 11. SLOPE ALL CONCRETE SIDEWALKS AWAY FROM EXTERIOR DOORS A MAXIMUM OF 2%.

#### Keynotes


- GENERATOR ANNUNCIATOR PANEL, REFER TO ELECTRICAL
- 2 ELECTRICAL PANELS
- (3) RETURN GRILLE ON WALL, COORDINATE LOCATION WITH MECHANICAL
- 4) AIR COMPRESSOR, REFER TO ME & P DRAWINGS
- (5) ICE READY MACHINE
- (7) CORNER GUARD
- 8 WASHER- O.F.O.I
- 9 DRYER-O.F.O.I
- (10) COMMERCIAL WASHER
- 11) FIRE DEPARTMENT CONNECTION
- 12) OVERHEAD DOORS CONTROL STATION, REFER TO ELECTRICAL
- (14) FIRE ALARM CONTROL PANEL
- 15) CARD READER PEDESTAL
- (16) ELECTRICAL EQUIPMENT



#### Breckenridge g r 0 u p a r c h i t e c t s p l a n n e r s

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# Tubac Fire Station #1



Intermediate

PROJECT NO: 23.21.00

ALICUST 200

AUGUST 2024
REVISION SCHEDULE:

# DATE DESCRIPTION

DRAWN BY: JCG CHECKED BY: CDA


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Floor Plan

A2.1



**General Notes** 

Breckenridge g r 0 u a r c h i t e c t p l a n n e r

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Tubac Fire Station #1


# Keynotes

- JOINT (TYP.)
- 2 CONCRETE PAVING
- 3 COLORED CONCRETE
- (4) CONCRETE SLAB
- 5 FIRE FIGHTERS SEAL
- 6) BIKE RACK
- 7) ROOF O.H.
- 9) TOOLED JOINT (TYP.)

CONCRETE SIDEWALK

ASPHALT PAVING

- 7) TOOLED JOHN (TTP
- (11) CONCRETE CURB
- (12) CONCRETE SPILLWAY
- (13) RIP-RAP
- (14) ACCESS RAMP
- 5) EXPOSED AGGREGATE



PROJECT NO: 23.21.00
DATE:

AUGUST 2024

REVISION SCHEDULE:
# DATE DESCRIPTION ISSUED TO

DRAWN BY: JCG

CHECKED BY: CDA

THIS DRAWING IS NOT TO BE USED FOR
CONSTRUCTION PURPOSES UNTIL SEALED AND
SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP
ARCHITECTS/PLANNERS, OR DESIGNATED
CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.


COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS


Hardscape Plan

A2.2

Hardscape Plan

SCALE: 1/16" = 1'-0" 0 16' 32'






1. REFER TO SHEET A3.3.1 FOR TOILET ACCESSORIES KEYNOTES AND MOUNTING HEIGHTS



1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Tubac Fire Station #1 2227 I-19 Frontage RD.,

Intermediate Plans



PROJECT NO: 23.21.00

AUGUST 2024 REVISION SCHEDULE:
# DATE DESCRIPTION


DRAWN BY: JCG


CHECKED BY: CDA

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED

WITHOUT PRIOR WRITTEN CONSENT. COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Interior Elevations





**NOT FOR CONSTRUCTION** 

Intermediate Plans

23.21.00 AUGUST 2024


REVISION SCHEDULE:
# DATE DESCRIPTION ISSUED TO


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Mounting Heights







# **Reflected Ceiling Plan** SCALE: 1/8" = 1'-0" 0


#### **General Notes**

- 1. ALL CEILING HEIGHTS ARE NOTED ON THE FINISH SCHEDULE UNLESS IT IS OPEN STRUCTURE.
- 4. LOCATE ALL CEILING FIXTURES & MECHANICAL OPENINGS PER ARCHITECTURAL REFLECTED CEILING PLAN.
- 5. ALL CEILING GRIDS TO BE CENTERED BETWEEN WALLS U.N.O. CEILING PARTIAL TILES AT ROOM PERIMETERS SHALL NOT BE LESS THAN 6" IN EITHER DIMENSION.
- 6. FOR LOCATION OF EXIT LIGHTS AND EMERGENCY ILLUMINATION, REFER TO ELECTRICAL PLAN. ALL EXIT LIGHTS TO BE WALL MOUNTED, ABOVE DOOR U.N.O. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
- 7. 18" MINIMUM VERTICAL CLEARANCE SHALL BE MAINTAINED BETWEEN THE BOTTOM OF THE EXTENDED SPRINKLER HEADS AND THE TOP OF ANY FILES, SHELVING, LOCKERS, ETC. ALL CEILING ELEMENTS TO BE PLACED IN THE CENTER OF CEILING TILE OR CENTER OF GYP. BOARD CEILING AREA U.N.O.
- 8. CENTER SPRINKLER HEAD IN TILE IN BOTH DIRECTIONS (SPRINKLER HEADS ARE NOT SHOWN ON REFLECTED CEILING PLAN).
- 9. ALL ACCESS PANELS MAY NOT BE SHOWN ON REFLECTED CEILING PLANS. THE GENERAL CONTRACT SHALL COORDINATE ALL REQUIRED ACCESS PANELS WHETHER SHOWN OR
- 11. SMOKE DETECTORS TO BE LOCATED 36" AWAY FROM CEILING FAN BLADES AND AIR SUPPLY REGISTERS.

## Keynotes

- 1) EXPOSED STRUCTURE
- 2) ROOF ACCESS LADDER
- 3) EXPOSED MECH, DUCTWORK, SEE MECH.
- 4) POWER HOSE AND AIR REELS MOUNTED ON A 24"X24"X1/4" STL. PLATE SUSPENDED FROM STRUCTURE WITH UNISTRUTS COORDINATE HEIGHT WITH OWNER
- (5) CAD ALERT DISPLAY- MOUNT J-BOX HORIZONTALLY, BOTTOM OF BOX
- 6) SPRINKLER HEAD
- 7 SOFFIT

# Legend



FLUORESCENT LIGHT FIXTURE

FLUORESCENT LIGHT FIXTURE

TRACK LIGHTING SMOKE DETECTOR CEILING OR PENDANT LIGHT CEILING OR PENDANT LIGHT (continuous duty) WALL MOUNTED LIGHT WALL MOUNTED LIGHT (continuous duty) RECESSED CAN LIGHT SPEAKER

WALL MOUNTED EGRESS SIGNAGE CEILING MOUNTED EGRESS SIGNAGE EMER. EGRESS LIGHTING (wall pack)

SUSPENDED CEILING GRID WITH 'AT' ACOUSTICAL TILE GYPSUM BOARD CEILING

CEILING FAN FLAME SPREAD RATING GYPSUM WALL BOARD NOT APPLICABLE PAINT (PER FINISH SCHEDULE)

POUNDS PER SQUARE FOOT SMOKE DEVELOPMENT RATING

MECHANICAL GRILLE OR CASSETTE FAN COIL

SOLATUBE SKYLIGHT


# architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

# # Station FIFE

Plans



PROJECT NO: 23.21.00

AUGUST 2024 REVISION SCHEDULE:


# DATE DESCRIPTION ISSUED TO

DRAWN BY: JCG CHECKED BY: CDA THIS DRAWING IS NOT TO BE USED FOR

CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR

DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT. COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

> Reflected Ceiling Plan



1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Intermediate Plans


**NOT FOR CONSTRUCTION** 


REVISION SCHEDULE:
# DATE DESCRIPTION ISSUED TO


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS







#### Finish schedule

- 1. INTEGRAL COLOR EXTERIOR INSULATION FINISH SYSTEM (EIFS), PAINT ALL METAL
- COLOR TO MATCH: PT-1 DUNN EDWARDS, WILD MUSTANG DE3A161 PT-2 DUNN EDWARDS, DOVER PLAINS DE6116
- 2. INTEGRAL COLOR CONCRETE MASONRY UNITS (CMU)
- SPLIT FACE SUPERLITE, ANTHEM RED GROUND FACE - SUPERLITE, SIERRA
- 3. PAINT ALL EXPOSED STEEL AND EXPOSED METAL
- CANOPIES, STEEL TUBES, FENCES AND GATES, MECHANICAL SCREENS: METALLIC-COATED STEEL SHEET – CORTEN AZP RAW OR WHEATHERED STEEL.
- 4. STANDING-SEAM METAL ROOF PANELS
- METALLIC-COATED STEEL SHEET CORTEN AZP RAW OR WHEATHERED STEEL.
- 5. EXTERIOR METAL SOFFIT PANELS
- METALLIC-COATED STEEL SHEET APACHE RAWHIDE
- 6. ALUMINUM FRAMES
- WINDOW MULLIONS, ALUMINUM DOORS, FRAMES, AND ADJACENT BREAK METAL TO BE STANDARD MANUFACTURER COLOR EQUAL TO ARCADIA MEDIUM BRONZE,
- 7. GLASS SOLARCOOL SOLARBRONZE, PPG IDEASCAPES

#### Paint Schedule

- PT-1 DUNN EDWARDS WILD MUSTANG DE161
- PT-2 DUNN EDWARDS DOVER PLAINS DE6116
- PT-3 WESTERN STATES METAL SPECKLED RUST
- PAINT TO MATCH

#### Keynotes


- 1) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT-1
- 2) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT- 2
- (3) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT- 3
- 4) RAIN WATER LEADERS (PT-5)
- 5 REVEAL
- (6) WAINSCOT
- 7) LIGHT FIXTURE, REFER TO ELECTRICAL DWGS
- 8 SURFACE RELIEF
- 9 MTL. COPING



architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# Station Fire **Tubac** 



Intermediate

PROJECT NO: 23.21.00

AUGUST 2024

REVISION SCHEDULE: # DATE DESCRIPTION

DRAWN BY: JCG


CHECKED BY: CDA

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED

WITHOUT PRIOR WRITTEN CONSENT. COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Colored Elevations



#### Finish schedule

- 1. INTEGRAL COLOR EXTERIOR INSULATION FINISH SYSTEM (EIFS), PAINT ALL METAL
- COLOR TO MATCH: PT-1 DUNN EDWARDS, WILD MUSTANG DE3A161 PT-2 DUNN EDWARDS, DOVER PLAINS DE6116
- 2. INTEGRAL COLOR CONCRETE MASONRY UNITS (CMU)
- SPLIT FACE SUPERLITE, ANTHEM RED GROUND FACE - SUPERLITE, SIERRA
- 3. PAINT ALL EXPOSED STEEL AND EXPOSED METAL
- CANOPIES, STEEL TUBES, FENCES AND GATES, MECHANICAL SCREENS: METALLIC-COATED STEEL SHEET - CORTEN AZP RAW OR WHEATHERED STEEL.
- 4. STANDING-SEAM METAL ROOF PANELS
- METALLIC-COATED STEEL SHEET CORTEN AZP RAW OR WHEATHERED STEEL.
- 5. EXTERIOR METAL SOFFIT PANELS
- METALLIC-COATED STEEL SHEET APACHE RAWHIDE
- 6. ALUMINUM FRAMES
- WINDOW MULLIONS, ALUMINUM DOORS, FRAMES, AND ADJACENT BREAK METAL TO BE STANDARD MANUFACTURER COLOR EQUAL TO ARCADIA MEDIUM BRONZE,
- 7. GLASS SOLARCOOL SOLARBRONZE, PPG IDEASCAPES

#### Paint Schedule

- PT-1 DUNN EDWARDS WILD MUSTANG DE161
- PT-2 DUNN EDWARDS DOVER PLAINS DE6116
- PT-3 WESTERN STATES METAL SPECKLED RUST
- PAINT TO MATCH

## Keynotes

- 1) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT-1
- 2) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT- 2
- (3) EXTERIOR INSULATION FINISH SYSTEM (EIFS), COLOR- PAINT PT- 3
- 4) RAIN WATER LEADERS (PT-5)
- (6) WAINSCOT
- 7) LIGHT FIXTURE, REFER TO ELECTRICAL DWGS
- 8 SURFACE RELIEF
- 9 MTL. COPING




architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# Station Fire **Tubac** 

Plans

Intermediate



PROJECT NO: 23.21.00

AUGUST 2024

REVISION SCHEDULE: # DATE DESCRIPTION

DRAWN BY: JCG


CHECKED BY: CDA


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS


Elevations







**NOT FOR CONSTRUCTION** 



**NOT FOR** 

CONSTRUCTION


AUGUST 2024


REVISION SCHEDULE:
# DATE DESCRIPTION ISSUED TO

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Wall Sections





architects planners 1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Intermediate Plans **NOT FOR CONSTRUCTION** 


AUGUST 2024


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Wall Sections





_	Floo	r Finish Plan
SCALE: 1/8":	= 1'-0" 0	24'

			Roc	m Fini	sh Scho	edule						
				Walls								
Number	Name	Floor	Base	North	East	South	West	Ht.	Matl.	Fin.	Notes	
	Room											
101	LOBBY	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
102	OPEN OFFICE	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
103	CONFERENCE ROOM	PC	VB	P1	P1	P1	P1		ACT-1	-		
104	IT	PC	VB	P1	P1	P1	P1	-	ACT-2	-		
105	FIRE CHIEF	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
106	ASSISTANT CHIEF	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
107	BREAK	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
108	WOMEN'S	PC	СТ	СТ	СТ	СТ	СТ	8' - 0"	GWB	P1	3	
109	MEN'S	PC	СТ	СТ	СТ	СТ	СТ	8' - 0"	GWB	P1	3	nookonnid
110	F.F STUDY	SC	VB	P1	P1	P1	P1	-	ACT-1	-	K	reckenrid
112	KITCHEN/ DAYROOM	PC	VB	P1	P1	P1	P1	-	GWB	P1		
113	FITNESS	AF	AFB	P1	P1	P1	P1	-	ACT-1	-	2	rv. u
114	OFFICE	PC	VB	P1	P1	P1	P1	-	ACT-1	-	a	rchitec
115	AIRLOCK	PC	VB	P1	P1	P1	P1	-	ACT-1	-	р	lanner
116	SHOWER	PC	СТ	CT	СТ	СТ	СТ	8' - 0"	GWB	P1	3 17	735 e ft. lowell rd.
117	SHOWER	PC	СТ	СТ	СТ	СТ	СТ	8' - 0"	GWB	P1	2	cson arizona 85
118	HALL	PC	VB	P1	P1	P1	P1	-	ACT-1	-		
119	DORM	PC	VB	P1	P1	P1	P1	10'-0"	ACT-3	-	5	2 0 . 8 8 2 . 9 9
120	DORM	PC	VB	P1	P1	P1	P1	10'-0"	ACT-3	-		
121	DORM	PC	VB	P1	P1	P1	P1	10'-0"	ACT-3	-		
122	DORM	PC	VB	P1	P1	P1	P1	10'-0"	ACT-3	-		
123	STOR.											
124	DORM	PC	VB	P1	P1	P1	P1	10'-0"	ACT-3	-		
125	MED STO.	RE	VB	FRP	FRP	FRP	FRP	-	ES	-	1, 4	
126A	JAN.	PC	VB	FRP	FRP	P1	P1	8' - 0"	ACT-2	-		
126B	MECH. ROOM	SC	VB	P1	P1	P1	P1	-	ES	-	1	
127	APPARATUS BAYS	SC	-	P1	P1	P1	P1	-	ES	-		
128	GENERAL STORAGE	RE	VB	FRP	FRP	FRP	FRP	-	ES	-	1, 4	
129	TURN-OUT ROOM	RE	VB	FRP	FRP	FRP	FRP	-	ES	-	1, 4	
130	ELECTRIC	RE	VB	FRP	FRP	FRP	FRP	-	ES	-	-	
131	FIRE RISER											

	ROOM FINISH LEGEND	ROOM FINISH NOTES			
	FLOOR	WALLS	WALLS SHALL HAVE A TYPE 4 LEVEL PAINTED FIN STRUCTURE		
	SC SEALED CONCRETE	CT CERAMIC TILE	- · · · · · · · · · · · · · · · · · · ·		
VB RUBBER WALL BASE		P1 PAINT - FIELD COLOR	2. ATHLETIC FLOORING BASE TO BE 18" HIGH		
	SPF ATHLETIC FLOORING	P2 PAINT - ACCENT COLOR	3. SOLID SURFACE WALLS & PAN @ SHOWER		
	AFB RUBBER WALL BASE	P3 PAINT - DOOR FRAMES	4. RED EPOXY PAINTED FLOOR		
	RE EPOXY FLOOR FINISH	FRP FIBER REINFORCED PANEL			
	PC POLISHED CONCRETE	<u>CEILING</u>			
	CMU CONCRETE MASONRY UNIT	GWB GYPSM WALL BOARD			

Signage Schedule

Sign Message

LOBBY

OPEN OFFICE

CONFERENCE ROOM

IT/ ELECTRICAL

FIRE CHIEF

ASSISTANT CHIEF

BREAKROOM

BATHROOM

BATHROOM

FIRE FIGHTERS STUDY

DAYROOM

KITCHEN

**FITNESS** 

OFFICE

AIRLOCK

AIRLOCK

SHOWER

SHOWER

HALL

HALL

HALL

DORM

DORM

DORM

DORM

DORM

MEDICAL STORAGE

**JANITOR** 

MECHANICAL ROOM

APPARATUS BAYS

GENERAL STORAGE

TURN-OUT ROOM

ELECTRICAL

FIRE RISER

ACT-1 SUSPENDED ACOUSTICAL CEILING ACT-2 CLEAN RM. SUSP. ACOUSITCAL CEILING ACT-3 FIRE RATED SUSP. ACOUSTICAL CEILING

Sign Type Qty

Α

Α

Α

Α

Α

Α

Α

Α

Α

Α

Α

Α

Α

Α

D

1

Room Number

102

103

105

106

107

108

109

110

111

112

113

115

115

11*7* 

118

118

119

120

121

122

125

126

127

127

127

127

127

127

127

127

128

129

130

131

133

Door Number

101A

102A

103A

104

105

106

108

109

112A

113A

114A

11*5*A

11*5*B

116

11*7* 

118A

118B

118C

119A

120A

121A

122A

124A

125

126A

126

127B

127C

127D

127E

127F

127G

127H

1*27*I

127A

128

129

130

131

Room Name

LOBBY

OPEN OFFICE

CONFERENCE ROOM

IT/ ELECT.

FIRE CHIEF

**ASSISTANT CHIEF** 

BREAK

WOMENS

F.F. STUDY

DAYROOM

KITCHEN

**FITNESS** 

OFFICE

AIRLOCK

**AIRLOCK** 

SHOWER

SHOWER

HALL

DORM

DORM

DORM

MED STO.

JAN.

MECH. ROOM

APPARATUS BAYS

GENERAL STORAGE

TURN-OUT ROOM

ELECTRIC

FIRE RISER

ES EXPOSED STRUCTURE V VARIES

1

1


FINISH TO THE BOTTOM OF THE

Notes

Station **Tubac Fire** 

Plans

Intermediate



PROJECT NO: 23.21.00

AUGUST 2024

REVISION SCHEDULE: # DATE DESCRIPTION ISSUED TO

DRAWN BY: JCG CHECKED BY: CDA

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Room Finish Schedule





Intermediate Plans **NOT FOR** 

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

**CONSTRUCTION** 

PROJECT NO: 23.21.00

AUGUST 2024 REVISION SCHEDULE:
# DATE DESCRIPTION


DRAWN BY: JCG


CHECKED BY: CDA THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Furniture/ Equip. Plan





#### STRUCTURAL NOTES

#### **GENERAL STRUCTURAL NOTES:**

- 1. ALL CONSTRUCTION SHALL CONFORM TO THE INTERNATIONAL BUILDING CODE, 2018 EDITION, (IBC 2018).
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AT JOB SITE BEFORE COMMENCING WORK & SHALL REPORT ANY DISCREPANCIES TO THE ARCHITECT.
- 3. OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE DRAWINGS, NOTES, AND DETAILS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT & RESOLVED BEFORE PROCEEDING WITH THE WORK.
- 4. DO NOT USE SCALED DIMENSIONS, USE WRITTEN DIMENSIONS OR WHERE NO DIMENSION IS PROVIDED, CONSULT WITH THE ARCHITECT FOR CLARIFICATION BEFORE PROCEEDING WITH THE WORK.
- 5. DETAILS SHOWN SHALL BE INCORPORATED INTO THE PROJECT AT ALL APPROPRIATE LOCATIONS WHETHER SPECIFICALLY CALLED OUT OR NOT.
- 6. TYPICAL DETAILS SHALL APPLY IN GENERAL CONSTRUCTION THROUGHOUT UNLESS DETAILED OTHERWISE ON DRAWINGS.
- WHERE NO DETAILS ARE GIVEN, CONSTRUCTION SHALL BE AS SHOWN FOR SIMILAR WORK, OR IF THERE IS NO SIMILAR WORK SHALL BE AS IS STANDARD IN THE INDUSTRY.
- 8. REPRODUCTION OF ANY PORTION OF THE STRUCTURAL CONTRACT DOCUMENTS FOR SUBMITTAL AS SHOP DRAWINGS IS PROHIBITED. SHOP DRAWINGS PRODUCED IN SUCH A MANNER WILL BE REJECTED AND RETURNED.
- 9. SEE ARCHITECTURAL DRAWINGS FOR THE FOLLOWING:

SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS SIZE AND LOCATION OF ALL INTERIOR AND EXTERIOR NON-BEARING PARTITIONS.

- SIZE AND LOCATION OF ALL CONCRETE CURBS; FLOOR AND ROOF DRAINS. SLOPES AND DEPRESSED AREAS; CHANGES IN LEVEL; CHAMFERS, CORNER FORMERS, GROOVES, BLOCKOUTS AND INSERTS; PAVING SITE WORK CURBS AND WALLS. DIMENSIONS NOT SHOWN ON STRUCTURAL DRAWINGS. SIZE AND LOCATION OF OPENINGS THRU ROOF AND FLOOR.
- 10. SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR THE FOLLOWING:

WALL AND SLAB OPENINGS FOR MECHANICAL PIPE RUNS
TRENCHES, FLOOR DRAINS, ROOF DRAINS, SUMPS, ETC.
WALL AND SLAB OPENINGS FOR ELECTRICAL CONDUIT RUNS,
BOXES, JUNCTION BOXES IN WALLS, COLUMNS, SLABS, ETC.
SLEEVES, SLEEVE CLUSTERS AND BLOCKOUTS, AND CONCRETE

INSERTS FOR EQUIPMENT AND FIXTURES.
SIZE AND LOCATION OF MACHINE, TRANSFORMER, SWITCHGEAR
AND EQUIPMENT CURBS, BASES AND PADS, AND ANCHORS BOLTS
FOR ANCHORED ITEMS.

SIZE AND LOCATION OF OPENINGS THRU ROOF AND FLOOR

- 11. THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION FOR LOADS DUE TO CONSTRUCTION EQUIP., ETC.
- 12. CONSTRUCTION MATERIALS SHALL BE SPREAD OUT IF PLACED ON FRAMED FLOORS OR ROOF. LOADS SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE STRUCTURE HAS NOT ATTAINED DESIGN STRENGTH AND AS REQUIRED FOR ERECTION.

13. DEAD LOADS: (UNO ON LOADING PLANS)

G) SEISMIC RESPONSE COEFFICIENT:

J) ANALYSIS PROCEDURE USED:

I) RESPONSE MODIFICATION FACTOR:

**EQUIVALENT LATERAL-FORCE** 

H) DESIGN BASE SHEAR:

A) FLOOR DEAD LOAD.

.. C s = \_\_\_\_

#### **FOUNDATION NOTES:**

1. FOUNDATION DESIGN BASED UPON THE FOLLOWING:

GEOTECHNICAL REPORT BY:

FILE NO.
DATED:
ALLOWABLE SOIL PRESSURE:
MIN. FTG. DEPTH BELOW
LOWEST ADJACENT GRADE:

\_\_\_ AT EXTERIOR FOOTINGS
AT INTERIOR FOOTINGS

- 2. REFER GEOTECHNICAL REPORT AND DIVISION 31 OF THE SPECIFICATIONS FOR DETAILS OF EARTHWORK REQUIREMENTS.
- 3. CONTRACTOR SHALL PROVIDE FOR PROPER DE-WATERING OF EXCAVATIONS FROM SURFACE WATER, GROUND WATER, SEEPAGE, ETC.
- 4. ALL EXCAVATION SHALL BE PROPERLY BACKFILLED. SEE SPECIFICATIONS FOR QUALITY AND EXTENT OF BACKFILL MATERIAL. DO NOT PLACE BACKFILL BEHIND RETAINING WALLS BEFORE CONCRETE HAS ATTAINED FULL DESIGN STRENGTH. CONTRACTOR SHALL BRACE OR PROTECT ALL BUILDING AND PIT WALL BELOW GRADE FROM LATERAL LOADS UNTIL ATTACHING FLOORS ARE COMPLETELY IN PLACE AND HAVE ATTAINED FULL STRENGTH. CONTRACTOR SHALL PROVIDE FOR DESIGN, PERMITS AND INSTALLATION OF SUCH BRACING.
- ALL ABANDONED FOOTINGS, UTILITIES, ETC. THAT INTERFERE WITH NEW CONSTRUCTION SHALL BE REMOVED.
- 7. ALL SOIL FILL AND BACKFILL SUPPORTING FOUNDATIONS AND SLABS ON GRADE SHALL BE PLACED AS ENGINEERED FILL.

#### CONCRETE:

 ALL PHASES OF WORK PERTAINING TO THE CONCRETE CONSTRUCTION SHALL CONFORM TO THE "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" (ACI 318) AND THE "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" (ACI 301) LATEST APPROVED EDITIONS, WITH MODIFICATIONS AS NOTED IN THE DRAWINGS OR SPECIFICATIONS.

2. SCHEDULE OF STRUCTURAL CONCRETE 28-DAY DESIGN STRENGTHS:

#### LOCATION IN STRUCTURE

<u>STRENGTH</u>

FOUNDATIONS/FOOTINGS3,000SLABS-ON-GRADE4,000ALL OTHER CONCRETE3,000

- 3. ALL REINFORCING BARS AND DOWELS, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION PRIOR TO PLACING CONCRETE.
- 4. PROVIDE SLEEVES FOR PLUMBING AND ELECTRICAL OPENINGS IN CONCRETE BEFORE PLACING. DO NOT CUT ANY REINFORCING WHICH MAY CONFLICT. CORING IN CONCRETE IS NOT PERMITTED EXCEPT AS SHOWN. NOTIFY THE ARCHITECT IN ADVANCE OF CONDITIONS NOT SHOWN ON THE DRAWINGS.
- 5. PROJECTING EXPOSED CORNERS OF BEAMS, COLUMNS, WALLS, ETC., SHALL BE FORMED WITH A 3/4" CHAMFER U.N.O. ON ARCHITECTURAL DRAWINGS.
- 6. OPENINGS, POCKETS, ETC. SHALL NOT BE PLACED IN CONCRETE SLABS, DECKS, BEAMS, JOISTS, COLUMNS, WALLS, ETC. UNLESS SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS. NOTIFY THE STRUCTURAL ENGINEER WHEN DRAWINGS BY OTHERS SHOW OPENINGS, POCKETS, ETC. NOT SHOWN ON THE STRUCTURAL DRAWINGS, BUT WHICH ARE LOCATED IN STRUCTURAL MEMBERS.
- 7. PROVIDE 1/2" PREFORMED JOINT FILLER WHERE EXTERIOR SLAB ABUTS VERTICAL SURFACES, TYP. U.N.O.
- 8. CLEAR COVERAGE OF CONCRETE OVER OUTER REINFORCING BARS SHALL BE AS FOLLOWS UNLESS SPECIFICALLY DETAILED OTHERWISE:

CONCRETE CAST AGAINST EARTH	MIN COVER, INCHES
FORMED CONCRETE EXPOSED TO EARTH OR WEATHER:  #6 AND LARGER BARS#5 AND SMALLER BARS	
SLABS-ON-GRADE	2 INCHES CLR TO TOP OF SLAB, UNO
STRUCTURAL SLABS	1
BEAMS, COLUMNS, PRIMARY REINF, TIES, STIRRUPS	1 1/2

#### MASONRY:

- 1. DESIGN COMPRESSIVE STRENGTH F'm = 2000 PSI MIN.
- CONCRETE BLOCK SHALL BE NORMAL WEIGHT HOLLOW CONC. MASONRY UNITS CONFORMING TO ASTM C90, GRADE N. F'm = 1900 PSI ON NET AREA.
- 3. PORTLAND CEMENT: ASTM C150, TYPE II.
- 4. MORTAR MIX SHALL CONFORM TO REQUIREMENTS OF ASTM C270 PROPORTION SPECIFICATIONS, THE IBC, AND PROJECT SPECIFICATIONS.
- 5. GROUT SHALL CONFORM TO THE REQUIREMENTS OF ASTM C476 AND THE IBC FOR FINE AND COURSE GROUT. GROUT SHALL BE PROPORTIONED PER TABLE 1 OF STM C476. USE SUFFICIENT WATER FOR GROUT TO FLOW INTO THE MASONRY WITHOUT SEGREGATION. GROUT SHALL ATTAIN COMPRESSIVE STRENGTH OF 2,000 PSI AT 28 DAYS.
- 6. PROVIDE A MINIMUM OF (1) BAR DIA. GROUT BETWEEN MAIN REINFORCING AND MASONRY UNITS.
- 7. ALL CELLS CONTAINING REINFORCING SHALL BE GROUTED SOLID.
- 8. SOLID GROUT ALL MASONRY BELOW GRADE.
- 9. HORIZONTAL JOINT REINFORCEMENT SHALL BE AS FOLLOWS: GALVANIZED CARBON STEEL WELDED WIRE UNITS, LADDER OR TRUSS DESIGN, PREFABRICATED WITH DEFORMED CONTINUOUS SIDE RODS, WITH A MINIMUM STRAIGHT LENGTH OF 10'-0" AND PREFABRICATED CORNER AND TEE UNITS. WIRE DIAMETER FOR SIDE AND CROSS RODS SHALL BE 0.1483 INCH (9 GAGE), SIDE RODS SHALL BE LAPPED 6" MIN. AT SPLICES, SPACE AT 16" O.C., U.N.O.
- 10. FACING BRICK SHALL CONFORM TO ASTM C216, GRADE SW.

#### REINFORCING STEEL:

- 1. ALL REINFORCING STEEL SHALL BE DETAILED AND PLACED IN CONFORMANCE WITH THE "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" (ACI 318 LATEST APPROVED EDITION), AND THE "MANUAL OF STANDARD PRACTICE FOR REINFORCED CONCRETE CONSTRUCTION" (LATEST APPROVED EDITION) BY THE C.R.S.I., AS MODIFIED BY THE DRAWINGS AND SPECIFICATIONS.
- REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-615, GRADE 60 FOR ALL BARS. WHERE REINFORCING IS INDICATED TO BE WELDED, PROVIDE REINFORCING CONFORMING TO THE REQUIREMENTS OF ASTM A706.
- 3. DOWELS BETWEEN FOOTINGS AND WALLS OF COLUMNS SHALL BE THE SAME GRADE, SIZE, SPACING AND NUMBER AS THE VERTICAL REINFORCING ABOVE.
- 4. REINFORCING BAR SPLICES SHALL BE MADE ONLY WHERE INDICATED ON THE DRAWINGS. THE MINIMUM SPLICE LAP LENGTH SHALL BE AS FOLLOWS:

MIN. LAP SPLICE IN CONCRETE: REFER TO DETAIL

MIN. LAP SPLICE IN MASONRY: REFER TO DETAIL

UNLESS SHOWN OTHERWISE ON THE DRAWINGS, SPLICE BARS SHALL BE PLACED AT THE SAME EFFECTIVE DEPTH U.N.O.. REINFORCING BARS MARKED "CONT." OR WITH LENGTH NOT SHOWN SHALL BE FULLY CONTINUOUS AND SPLICED ONLY AS SHOWN

- ALL REINFORCING BAR BENDS AND HOOKS SHALL BE STANDARD ACI BENDS AND HOOKS UNLESS SPECIFICALLY NOTED OTHERWISE ON STRUCTURAL DRAWINGS.
- 6. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A1064. MINIMUM LAP OF WELDED WIRE FABRIC SHALL BE 6 INCHES OR ONE FULL MESH +2 INCHES, WHICHEVER IS GREATER.

#### STRUCTURAL STEEL:

- 1. STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH THE AISC SPECIFICATION FOR THE DESIGN. FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS (LATEST EDITION AND SUPPLEMENTS).
- 2. ALL WELDING SHALL BE PERFORMED IN ACCORDANCE WITH AWS STANDARDS (LATEST EDITION AND SUPPLEMENTS). WELDS SHALL BE PERFORMED USING SHIELDED METAL ARC WELDING WITH E70XX ELECTRODES. ALL WELDS NOT OTHERWISE DETAILED SHALL BE FILLET WELDED, ALL EDGES, CONTINUOUSLY WITH MINIMUM WELD SIZE PER AWS STANDARDS.
- STRUCTURAL STEEL WIDE FLANGE SHAPES: ASTM A992.
- 4. ALL OTHER STRUCTURAL STEEL SHAPES, PLATES AND BARS: ASTM A36.
- 5. SQUARE AND RECTANGULAR HSS: ASTM A500, GRADE C (FY=50 KSI).
- 6. ROUND HSS: ASTM A500, GRADE C (FY = 46 KSI).
- 7. UNFINISHED THREADED BOLTS (MACHINE BOLTS): ASTM A307, GRADE A.
- ANCHOR RODS: ASTM F1554-18 WITH SUPPLEMENT S1, GRADE 55 WELDABLE. NUTS PER ASTM A194 OR A563 TO MATCH ROD GRADE. WASHERS PER ASTM F436 WITH ADEQUATE HOLE COVERAGE.
- 9. PLAIN AND THREADED BARS AND ANCHORS: ASTM A36 OR A307, GRADE A.
- 10. HIGH STRENGTH BOLTS: ASTM A325-N AND SPECIFICATIONS.
- 11. CONCRETE ANCHOR STUDS (CAS) SHALL CONFORM TO ASTM A108, GRADE 1015 OR 1020. ATTACH CAS WITH AUTOMATICALLY TIMED ELECTRIC-ARC STUD WELDING (FULL FUSION) AS PER MFR. AND AWS D1.1:2015 CHAPTER 7.
- 12. DEFORMED BAR ANCHORS SHALL BE ASTM A496 WITH A MIN. TENSILE STRENGTH OF 80 KSI, AS MFR. BY NELSON OR APPROVED EQUAL. ATTACH ANCHORS WITH AUTOMATICALLY TIMED ELECTRIC-ARC STUD WELDING (FULL FUSION) AS PER MFR. AND AWS D1.1:2015 CHAPTER 7.
- 13. DRYPACK UNDER STEEL BASE PLATES SHALL BE ASTM C1107, NON-SHRINK, NON-METALLIC GROUT AS MANUFACTURED BY US GROUT CORP., "FIVE STAR GROUT" OR APPROVED EQUAL.

#### **SPECIAL INSPECTIONS:**

SPECIAL INSPECTIONS, PAID FOR BY THE OWNER, SHALL BE PERFORMED BY A QUALIFIED INSPECTOR, AS REQUIRED BY SECTION 1704 OF THE INTERNATIONAL BUILDING CODE, 2018 EDITION (IBC-2018).

THE FOLLOWING TYPES OF WORK REQUIRE SPECIAL INSPECTION. SEE PROJECT SPECIFICATIONS FOR SPECIFIC REQUIREMENTS.

- A. ENGINEERED FILL PLACEMENT
- B. FOUNDATION EXCAVATIONS PRIOR TO CONCRETE PLACEMENT
- C. STRUCTURAL CONCRETE WORK.
  D. BOLTS INSTALLED IN CONCRETE
- E. REINFORCING STEEL (INCLUDING FLOOR TOPPING REINFORCING)F. STRUCTURAL WELDING (FIELD & SHOP).
- G. HIGH STRENGTH BOLTS (SNUG TIGHT)
- H. POST INSTALLED BOLTS (EXPANSION OR EPOXY TYPE)I. REINFORCING SECURED WITH EPOXY.
- J. ALL MASONRY CONSTRUCTION WORK.



#### p I a n n e r s 1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

## **Tubac, AZ 85646**

Tubac Fire Station #1 2227 I-19 Frontage RD., Tul



PROJECT NO: 23.21.00	

Tune 28, 2024


REVISION SCHEDULE:
# DATE DESCRPITION ISSUED TO

DRAWN BY: SL CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &





### STRUCTURAL NOTES

#### WOOD:

- I. WOOD FRAMING SHALL CONFORM TO THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE, CHAPTER 23-WOOD. STRUCTURAL DIMENSION LUMBER SHALL CONFORM TO THE CURRENT STANDARD GRADING RULES FOR WEST COAST LUMBER OF THE WEST COAST LUMBER INSPECTION BUREAU (WCLIB) OR TO THE CURRENT STANDARD GRADING RULES FOR WESTERN LUMBER OF THE WESTERN WOOD PRODUCTS ASSOCIATION (WWPA).
- 2. STRUCTURAL WOOD FRAMING SHALL BE DOUGLAS FIR-LARCH VISUALLY GRADED DIMENSION LUMBER AND SHALL HAVE THE FOLLOWING MINIMUM PROPERTIES.

<u>TYPE</u>	<u>SPECIES</u>	<u>GRADE</u>	Fb(PSI)*	E(PSI)*
JOISTS	DF-L	#2	875	1,600,000
BEAMS WIDTH 4" OR LESS WIDTH > 4"		#2 #1	875 1350	1,600,000 1,600,000
POSTS 4x44x6 OR LARGER6x6 OR LARGER	DF-L	#2 #2 #1	875 875 1200	1,600,000 1,600,000 1,600,000
STUDS 2x4 2x6 OR LARGER		STUD #2	675 875	1,400,000 1,600,000
LEDGERS AND TOP PLATES	DF-L	#2	875	1,600,000

- \*BASE DESIGN VALUES, ADJUSTMENT FACTORS NOT APPLIED.
- 3. GLUE LAMINATED BEAMS, Fb = 2400 PSI, Fv = 165 PSI. E = 1800 KSI COMBIN. 24F-V8. PROVIDE STANDARD UPWARD CAMBER OF 1500' RADII AT MIDSPAN OF ALL BEAMS, UNLESS NOTED OTHERWISE.
- 4. PLYWOOD: APA RATED SHEATHING; EXTERIOR EXPOSURE DURABILITY CLASSIFICATION; PANEL GRADE STRUCTURAL I, C-C CONFORMING TO PS 1-09, 5 PLY PLYWOOD.
- 5. ALL NAILING SHALL BE WITH COMMON NAILS. ALL NAILING NOT NOTED SHALL BE ACCORDING TO TABLE 2304.10.1 OF THE INTERNATIONAL BUILDING CODE.
- 6. WOOD CONNECTORS, "SIMPSON" OR APPROVED EQUAL (WITH CURRENT ICBO REPORT) WITH ALL HOLES FILLED WITH MANUFACTURER'S SPECIFIED NUMBER AND TYPE OF NAILS. MULTIPLE, SKEWED AND/OR SLOPED HANGERS SHALL BE SUPPLIED BY THE CONTRACTOR WHERE NECESSARY.
- 7. DO NOT NOTCH, DRILL OR SPLICE JOISTS, BEAMS AND LOAD BEARING OR STRUCTURAL STUDS WITHOUT PRIOR APPROVAL OF STRUCTURAL ENGINEER.
- 8. ALL WOOD CONSTRUCTION IN CONTACT WITH THE SLABS-ON-GRADE OR EXPOSED TO OUTSIDE AIR AND MOISTURE SHALL BE WATER-BORNE PRESERVATIVE TREATED IN ACCORDANCE WITH THE AMERICAN WOOD PRESERVERS ASSOCIATION (AWPA) STANDARD T1-19 "ALL TIMBER PRODUCTS PRESERVATIVE TREATMENT BY PRESSURE PROCESSES".
- 9 STANDARD CUT WASHERS SHALL BE USED UNDER BOLT HEADS AND NUTS AGAINST WOOD.

#### PREFABRICATED WOOD JOISTS:

- THE JOIST MANUFACTURER SHALL BE RESPONSIBLE FOR THE STRUCTURAL DESIGNS OF THE JOISTS AND COMPONENTS OF THE JOIST SYSTEM. ALL DESIGN, DETAILS, SHOP AND ERECTION DRAWINGS, AND ALL CALCULATIONS SUBMITTED TO THE ARCHITECT FOR REVIEW SHALL BEAR THE SEAL OF A QUALIFIED PROFESSIONAL ENGINEER, CURRENTLY REGISTERED IN THE STATE OF ARIZONA.
- 2. THE MANUFACTURER SHALL SUBMIT SHOP DRAWINGS AND CALCULATIONS FOR THE ARCHITECTS REVIEW PRIOR TO FABRICATION. THE SHOP DRAWINGS AND CALCULATIONS SHALL INCLUDE, BUT ARE NOT LIMITED TO, THE APPLICABLE DETAILS, DESIGN LOADS, ALLOWABLE STRESSES, ERECTION DRAWINGS, AND ALL NECESSARY INSTALLATION INSTRUCTIONS AND DETAILS.
- THE MANUFACTURER SHALL FURNISH ALL BRIDGING, BLOCKING, AND BRACING REQUIRED FOR THE STABILITY OF THEIR SYSTEMS DURING ALL PHASES OF CONSTRUCTION, AND FINAL COMPLETION.
- 4. THE JOIST SYSTEM SHALL INCLUDE, BUT NOT BE LIMITED TO, ALL JOISTS, WALL OR METAL BRIDGING, BLOCKING PANELS, WEB STIFFENERS AND OTHER ITEMS SHOWN ON DRAWINGS, SPECIFIED HEREIN, OR AS REQUIRED TO COMPLETE THE WORK. ALL MATERIAL SHALL BE NEW, UNUSED AND FREE FROM DEFECTS.
- 5. JOIST FLANGES SHALL BE SOLID SAWN OR LAMINATED LUMBER WITH LATERAL STRENGTH AND RESISTANCE TO WITHDRAWAL VALUES FOR NAILS MEETING OR EXCEEDING THOSE FOR DOUGLAS FIR OR SOUTHERN PINE (SPECIFIC GRAVITY = 0.49 MIN.).
- SUPPLIED JOISTS SHALL NOT BE LESS IN SIZE OR SERIES THAN INDICATED ON PLANS.

THE JOIST MANUFACTURER SHALL SUBMIT DESIGN CALCULATIONS CONFIRMING THE JOIST CAPACITY FOR THE FOLLOWING LOADS:

LIVE LOAD = 20 PSF WITHOUT REDUCTION.
DEAD LOAD = 25 PSF INCLUDING JOIST WEIGHT.

IN ADDITION TO THE UNIFORM LOADS INDICATED, DESIGN FOR ALL ADDITIONAL LOADS SHOWN ON STRUCTURAL DRAWINGS.

- 7. ROOF LOAD DURATION FACTOR = 1.25.
- 8. SEE DRAWINGS FOR CONCENTRATED ROOF LOADS AND OTHER SPECIAL LOADING CONDITIONS. PROVIDE SPECIAL JOISTS OR EXTRA JOISTS TO CARRY THE SUPERIMPOSED LOADS.
- 9. THE TOTAL (DEAD PLUS LIVE) LOAD DEFLECTION OF THE JOIST SHALL NOT EXCEED L/240 OF THE JOIST SPAN.
  THE TOTAL LIVE LOAD DEFLECTION OF THE JOIST SHALL NOT EXCEED L/360 OF THE JOIST SPAN.
- 10. "REDBUILT" PRODUCTS HAVE BEEN SPECIFIED ON THE DRAWINGS. ALTERNATE JOISTS MAY BE PROPOSED PROVIDED THAT ALL JOIST ARE THE SAME DEPTH AND SHALL HAVE EQUAL OR BETTER EI VALUES, MOMENT AND SHEAR CAPACITIES, AND HAVE A CURRENT ICC-ES EVALUATION REPORT.

#### STRUCTURAL COLD-FORMED STEEL STUDS:

- 1. STEEL FOR ALL 14 AND 16 GAGE STUDS AND TRACKS SHALL HAVE A MINIMUM YIELD STRENGTH OF 50,000 PSI. STEEL FOR ALL 18 AND 20 GAGE STUDS AND TRACK, ACCESSORIES AND BRIDGING SHALL HAVE A MINIMUM YIELD STRENGTH OF 33,000 PSI. STEEL SHALL BE GALVANIZED AT LOCATIONS EXPOSED TO WEATHER AND WHENEVER NOTED ON THE DRAWINGS. SEE DETAILS FOR STUD SIZES AND STRUCTURAL PROPERTY REQUIREMENTS.
- 2. PROVIDE HORIZONTAL BRIDGING AT 6'-0" MAXIMUM O.C. AND AS OTHERWISE SHOWN ON THE DRAWINGS.
- 3. FRAME BOTH SIDES OF EXPANSION AND CONTROL JOINTS WITH SEPARATE STUDS.
- 4. PROVIDE ALL ACCESSORY FRAMING AS INDICATED ON THE DETAILS AND AS RECOMMENDED BY THE MANUFACTURER.
- 5. POWER ACTUATED FASTENERS (PAF) FOR LIGHT GAGE STEEL FRAMING (WITH 1"Ø MIN METAL WASHER) SHALL CONFORM TO THE FOLLOWING:

CONCRETE PAF SHANK 0.157"Ø MIN W/ 1 1/4" MIN EMBEDMENT LENGTH INTO CONCRETE, GALVANIZED.

MIN ULTIMATE TENSION (4000PSI NW CONC) = 1,125 LBS MIN ULTIMATE SHEAR (4000 PSI NW CONC) = 1,125 LBS MIN EDGE DISTANCE = 3"

STEEL PAF SHANK 0.157"Ø MIN, SPIRAL KNURLED WITH LENGTHS AS RECOMMENDED BY MANFUCTURER FOR SPECIFIED BASE STEEL THICKNESS.

MIN ULTIMATE TENSION (1/4" A36 STEEL) = 735 LBS MIN ULTIMIATE SHEAR (1/4" A36 STEEL) = 535 LBS


6. SCREWS FOR LIGHT GAGE FRAMING:

SELF TAPPING, GALVANIZED, HEX HEAD SCREWS WITH LENGTH AS REQUIRED TO ENGAGE 3 EXPOSED THREADS MINIMUM PAST BASE STEEL.

#### **DEFERRED SUBMITTALS:**

SUBMITTAL DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD FOR REVIEW, AND THEN FORWARDED TO THE BUILDING OFFICIAL WITH NOTATION THAT THE DEFERRED SUBMITTAL DOCUMENTS ARE IN GENERAL CONFORMANCE WITH THE DESIGN OF THE BUILDING(S). THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL. THE FOLLOWING ITEMS SHALL BE CLASSIFIED AS DEFERRED SUBMITTALS:

1. PREFABRICATED WOOD I JOISTS AND CALCULATIONS



FOR BALANCE OF INFORMATION REFER TO STRUCTURAL NOTES AND SPECIFICATIONS.

TYP EARTHWORK REQUIREMENTS

NO SCALE

MARTIN WHITE GRIFFIS STRUCTURAL ENGINEERS, INC.

Breckenridge

g r 0 u p


a r c h i t e c t s

p l a n n e r s

1735 e ft. lowell rd. #12

tucson arizona 85719 520.882.9944

Tubac Fire Station #1 2227 I-19 Frontage RD., Tub



PROJECT NO:

23.21.00

DATE:

June 28, 2024

REVISION SCHEDULE:

# DATE DESCRPITION ISSUED TO

DRAWN BY: SL
CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

Structural Notes

**SO.2** 

### SPECIAL INSPECTIONS

#### **INSPECTION AND TESTING NOTES:**

- AN INDEPENDENT TESTING AGENCY AND SPECIAL INSPECTORS SHALL BE RETAINED BY THE OWNER TO PERFORM THE TESTS AND INSPECTION AS REQUIRED BY SECTION 1704 OF THE 2018 IBC. THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE SPECIAL INSPECTOR TO THE SITE OR FABRICATION SHOPS AND SHALL FURNISH SAMPLES OF MATERIALS FOR TESTING AS REQUESTED BY THE TESTING AGENCY AND THE GOVERNING CODE. PER SECTION 1704 INSPECTION OF FABRICTIONS, STEEL CONSTRUCTION, CONCRETE CONSTRUCTION, MASONRY CONSTRUCTION, AND SOILS ARE REQUIRED.
- 2. IF INITIAL TESTS OR INSPECTIONS MADE BY THE OWNER'S TESTING AGENCY REVEAL THAT ANY PORTION OF THE WORK DOES NOT COMPLY WITH THE CONTRACT DOCUMENTS, ADDITIONAL TESTS, INSPECTIONS, AND NECESSARY REPAIRS WILL BE MADE AT THE CONTRACTOR'S EXPENSE.
- 3. PROVIDE CONTINUOUS OR PERIODIC SPECIAL INSPECTION FOR ITEMS NOTED IN "TEST AND INSPECTION LIST".
- 4. SPECIAL INSPECTIONS MAY NOT BE REQUIRED WHEN THE WORK IS DONE ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED BY THE BUILDING OFFICIAL OR GOVERNING AGENCY HAVING JURISDICTION OVER THE PROJECT TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION.
- 5. EACH CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A MAIN WIND OR SEISMIC FORCE RESISTING SYSTEM ELEMENT SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND TO THE OWNER'S REPRESENTATIVE, PRIOR TO THE COMMENCEMENT OF THE WORK ON THE SYSTEM OR COMPONENT. THE CONTRACTOR'S STATEMENT OF RESPONSIBILITY SHALL CONTAIN THE FOLLOWING INFORMATION:
- A. ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.
- B. ACKNOWLEDGEMENT THAT CONTROL WILL BE EXERCISED TO OBTAIN CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS APPROVED BY THE BUILDING OFFICIAL.
- C. PROCEDURES FOR EXERCISING CONTROL WITHIN THE CONTRACTOR'S ORGANIZATION, THE METHOD AND FREQUENCY OF REPORTING AND DISTRIBUTION OF THE REPORTS.
- D. IDENTIFICATION AND QUALIFICATIONS OF THE PERSONS EXERCISING SUCH CONTROL AND THEIR POSITIONS IN THE ORGANIZATION.
- SPECIAL INSPECTIONS FOR THE STRUCTURAL STEEL PORTIONS OF THE LATERAL FORCE RESISTING SYSTEM SHALL ALSO COMPLY WITH THE REQUIREMENTS OF AISC 341.
- 7. NON-DESTRUCTIVE WELD TESTING: ULTRASONIC TESTING IS REQUIRED FOR ALL (100%) PARTIAL AND COMPLETE PENETRATION WELDS. TESTING SHALL BE PERFORMED 24 HOURS OR MORE AFTER COMPLETION OF WELDING. WELD BACKING REMOVAL AREAS AND FILLET WELDS SHALL BE SUBJECTED TO MAGNETIC PARTICLE EXAMINATION.
- 8. TEST BY CALIBRATED TORQUE WRENCH A MINIMUM OF ONE (1) HIGH STRENGTH BOLT AT EACH SHEAR CONNECTION. A MINIMUM OF TWO (2) BOLTS PER CONNECTION FOR CONNECTION WITH 8 BOLTS OR MORE AND A MINIMUM OF 2 BOLTS PER FRAME BEAM SHEAR CONNECTION.
- 9. TEST A MINIMUM OF 10% OF FILLET WELDS BY MAGNETIC PARTICLE (ASTM 109 METHOD). TEST A MINIMUM OF 25% OF CONTINUITY PLATE FILLET WELDS AND BEAM FILLET WELDS (100% IN MOMENT ZONES) BY MAGNETIC PARTICLE. ALL FIELD FILLET WELDS SHALL BE 100% VISUALL INSPECTED.
- 10. APPROVAL BY THE INSPECTOR OF MATTERS NOT SPECIFICALLY CONSTRUCTED PER THE APPROVED DRAWINGS DOES NOT MEAN THE FAILURE TO COMPLY WITH THE CONSTRUCTION DOCUMENTS HAS BEEN ACCEPTED. ANY DETAIL THAT FAILS TO BE CLEAR OR IS AMBIGUOUS MUST BE REFERRED TO THE STRUCTURAL ENGINEER FOR INTERPRETATION OR CLARIFICATION.
- 11. INSPECTION AND TESTING REPORTS SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER AND OWNER WITHIN SEVEN DAYS OF WHEN THE INSPECTION WAS MADE OR WHEN THE TESTING WAS PERFORMED.
- 12. THE STRUCTURAL ENGINEER SHALL BE NOTIFIE IMMEDIATELY OF ANY INSPECTION OR TESTING WHICH DOES NOT COMPLY WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

## TABLE 1705.6 REQUIRED VERIFICATION AND INSPECTION OF SOILS

VERIFICATION AND INSPECTION TASK	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED
<ol> <li>Verify materials below shallow foundations are adequate to achieve the design bearing capacity.</li> </ol>	-	X
2. Verify excavations are extended to proper depth and have reached proper material.	-	X
3. Perform classification and testing of controlled fill materials.	-	X
Verify use of proper materials, densities, and lift thicknesses during placement and compaction of compacted fill.	Х	-
<ol><li>Prior to placement of compacted fill, observe subgrade and verify that site has been prepared properly.</li></ol>	-	X

## TABLE 1705.3 REQUIRED VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION

VERIFICATION AND INSPECTION	CONTINUOUS	NUOUS PERIODIC REFERENCED STANDARD <sup>a</sup>		IBC REFERENCE
Inspection of reinforcing steel, including prestressing tendons, and placement.	-	×	ACI 318: 3.5, 7.1-7.7	1910.4
2. Inspection of reinforcing steel, welding in accordance w/ Table 1705.2.2, Item 2b.	-	-	ASW D1.4 ACI 318: 3.5.2	-
Inspection of anchors cast in concrete where allowable loads have been increased or where strength design is used.	-	Х	ACI 318: 8.1.3, 21.2.8	1908.5, 1909.1
<ol> <li>Inspection of anchors post-installed in hardened concrete members<sup>b</sup>.</li> </ol>	-	Х	ACI 318: 3.8.6, 8.1.3, 21.2.8	1909.1
5. Verifying use of required design mix.	-	Х	ACI 318: Ch. 4, 5.2-5.4	1904.2, 1910.2, 1910.3
<ol> <li>At the time fresh concrete is sampled to fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete.</li> </ol>	X	-	ASTM C 172 ASTM C 31 ACI 318: 5.6, 5.8	1910.10
<ol><li>Inspection of concrete and shotcrete placement for proper application techniques.</li></ol>	X	-	ACI 318: 5.9, 5.10	1910.6, 1910.7, 1910.8
<ol><li>Inspection for maintenance of specified curing temperature and techniques.</li></ol>	-	×	ACI 318: 5.11-5.13	1910.9
<ul><li>9. Inspection of prestressed concrete:</li><li>a. Application of prestressing forces.</li><li>b. Grouting of bonded prestressing tendons in the seismic force-resisting system.</li></ul>	X	-	ACI 318: 18.20 ACI 318: 18.18.4	-
10. Erection of precast concrete members.	-	Х	ACI 318: Ch. 16	-
11. Verification of in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms from beams and structural slabs.	-	х	ACI 318: 6.2	-
<ol><li>Inspect formwork for shape, location and dimensions of the concrete member being formed.</li></ol>	-	Х	ACI 318: 6.1.1	-

#### For SI: 1 inch = 25.4mm

- a. Where applicable, see also Section 1705.11, Special inspections for seismic resistance.
- b. Specific requirements for special inspection shall be included in the research report for the anchor issued by an approved source in accordance with ACI 355.2 or other qualification procedures. Where specific requirements are not provided, special inspection requirements shall be specified by the registered design professional and shall be approved by the building official prior to the commencement or the work.

## TABLE C-N5.4-1 INSPECTION TASKS PRIOR TO WELDING

INSPECTION TASKS PRIOR TO WELDING	AWS D1.1/D1.1M REFERENCES*
Welding procedure specifications (WPSs) available	6.3
Manufacturer certifications for welding consumables available	6.2
Material identification (type/grade)	6.2
Welder identification system	6.4 (welder qualification) (identification system not required by AWS D1.1/D1.1M)
Fit-up of groove welds (including joint geometry)  Joint preparation  Dimensions (alignment, root opening, root face, bevel)  Cleanliness (condition of steel surfaces)  Tacking (tack weld quality and location)  Backing type and fit (if applicable)	6.5.2 5.22 5.15 5.18 5.10, 5.22.1.1
Configuration and finish of access holes	6.5.2, 5.17 (also see Section J1.6)
Fit-up of fillet welds Dimensions (alignment, gaps at root) Cleanliness (condition of steel surfaces) Tacking (tack weld quality and location)	5.22.1 5.15 5.18
Check welding equipment	6.2, 5.11

## TABLE C-N5.4-2 INSPECTION TASKS DURING WELDING

INSPECTION TASKS DURING WELDING	AWS D1.1/D1.1M REFERENCES*
Use of qualified welders	6.4
Control and handling of welding consumables - Packaging - Exposure control	6.2 5.3.1 5.3.2 (for SMAW), 5.3.3 (for SAW)
No welding over cracked tack welds	5.18
Environmental conations  - Wind speed within limits  - Precipitation and temperature  WPS followed  - Settings on welding equipment  - Travel speed  - Selected welding materials  - Shielding type/flow rate  - Preheat applied  - Interpass temperature maintained (min./max.)  - Proper position (f, v, h, oh)	5.12.1 5.12.2 6.3.3, 6.5.2, 5.5, 5.21 5.6, 5.7
Welding techniques - Interpass and final cleaning - Each pass within profile limitations - Each pass meets quality requirements	6.5.2, 6.5.3, 5.24 5.30.1
* AWS (2010)	

## TABLE C-N5.4-3 INSPECTION TASKS AFTER WELDING


AWS D1.1/D1.1M REFERENCES*
5.30.1
6.5.1
6.5.3 Table 6.1(1) Table 6.1(2) Table 6.1(3) Table 6.1(4), 5.24 Table 6.1(6) Table 6.1(7) Table 6.1(8)
5.29
not addressed in AWS
5.10, 5.31
6.5.3, 5.26
6.5.4, 6.5.5

MARTIN WHITE GRIFFI STRUCTURAL ENGINEERS, IN



1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

ibac Fire Station #1 227 I-19 Frontage RD., Tubac, AZ 85646



PROJECT NO:
23.21.00

DATE:

June 28, 2024

**REVISION SCHEDULE** 

# DATE DESCRPITION ISSUED TO

DRAWN BY: SL
CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION
PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF

BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

Special Inspections

### STRUCTURAL NOTES

#### TABLE C-N5.6-1 INSPECTION TASKS DRIOR TO BOI TING

INSPECTION TASKS PRIOR TO BOLTING		
INSPECTION TASKS PRIOR TO BOLTING	APPLICABLE RCSC Specification REFERENCES*	
Manufacturer's certifications available for fastener materials	2.1, 9.1	
Fasteners marked in accordance with ASTM requirements	Figure C-2.1, 9.1 (also see ASTM standards)	
Proper fasteners selected for the joint detail (grade, type, bolt length if threads to be excluded from shear plane)	2.3.2, 2.7.2, 9.1	
Proper bolting procedure selected for joint detail	4, 8	
Connecting elements, including the appropriate faying surface condition and hole preparation, if specified, meet applicable requirements	3, 9.1, 9.3	
Pre-installation verification testing by installation personnel observed and documented for fastener assemblies and methods used	7, 9.2	
Proper storage provided for bolts, nuts, washers and other fastener components	2.2, 8, 9.1	
* RCSC (2009)		

#### TABLE C-N5.6-2 INSPECTION TASKS DURING BOLTING

INSPECTION TASKS DURING BOLTING	APPLICABLE RCSC Specification REFERENCES*
Fasteners assemblies, of suitable condition, placed in all holes and washers (if required) are positioned as required	8.1, 9.1
Joint brought to the snug-tight condition prior to the pretensioning operation	8.1, 9.1
Fastener component not turned by the wrench prevented from rotating	8.2, 9.2
Fasteners are pretensioned in accordance with a method approved by RCSC and progressing systematically from the most rigid point toward free edges	8.2, 9.2

#### TABLE C-N5.6-3 INSPECTION TASKS AFTER BOLTING

INSPECTION TASKS AFTER BOLTING	APPLICABLE RCSC Specification REFERENCES*		
Document acceptance or rejection of bolted connections	not addressed by RCSC		
* RCSC (2009)			

#### REQUIRED VERIFICATION AND INSPECTION OF EPOXY AND EXPANSION ANCHORS

VERIFICATION AND INSPECTION TASK	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED
Installation of anchors per manufacturer's reports.	X	-

#### TABLE 4 - Minimum Special Inspection Requirements

INSPECTION TASK	Frequency <sup>(a)</sup>	Reference for	Reference for Criteria	
INSI ECHON TASK	Level 3	TMS 402	TMS 602	
As masonry construction begins, verify that the following are in compliance:				
a. Proportions of site-prepared mortar	Р		Art. 2.1, 2.6 A & 2.6 C	
b. Grade and size of prestressing tendons and anchorages	Р		Art. 2.4 B & 2.4 H	
<ul> <li>Grade, type and size of reinforcement, connectors, anchor bolts, and prestressing tendons and anchorages</li> </ul>	Р		Art. 3.4 & 3.6 A	
d. Prestressing technique	Р		Art. 3.6 B	
e. Properties of thin-bed mortar for AAC masonry	С		Art. 2.1 C.1	
f. Sample panel construction	С		Art. 1.6 D	
Prior to grouting, verify that the following are in compliance:				
a. Grout space	С		Art. 3.2 D, & 3.2 F	
b. Placement of prestressing tendons an anchorages	Р	Sec. 10.8 & 10.9	Art. 2.4 & 3.6	
c. Placement of reinforcement, connectors, and anchor bolts	С	Sec. 6.1, 6.3.1, 6.3.6, & 6.3.7	Art. 3.2 E & 3.4	
d. Proportions of site-prepared grout and prestressing grout for bonded tendons	Р		Art. 2.6 B & 2.4 G.1.b	
3. Verify compliance of the following during construction:				
Materials and procedures with the approved submittals	Р		Art. 1.5	
b. Placement of masonry units and mortar joint construction	Р		Art. 3.3 B	
c. Size and location of structural members	Р		Art. 3.3 F	
<ul> <li>d. Type, Size and location of anchors, including other details of anchorage of masonry to structural members, frames, or other construction</li> </ul>	Р	Sec. 1.2.1 (e), 6.2.1, & 6.3.1		
e. Welding of reinforcement	С	Sec. 6.1.6.1.2		
f. Preparation, construction, and protection of masonry during cold weather (temperature below 40°F (4.4°C)) or hot weather (temperature above 90°F (32.2°C))	Р		Art. 1.8 C & 1.8 D	
g. Application and measurement of prestressing force	С		Art. 3.6 B	
h. Placement of grout and prestressing grout for bonded tendons is in compliance	С		Art. 3.5 & 3.6 C	
Placement of AAC masonry units and construction     of thin-bed mortar joints	С		Art. 3.3 B.9 & 3.3 F.1.	
Observe preparation of grout specimens, mortar specimens and/or prisms	С		Art. 1.4 B.2.a.3, 1.4 B.2.b.3, 1.4 B.2.c.3, 1.4 B.3, & 1.4 B.4	

(a) Frequency refers to the frequency of inspection, which may be continuous during the listed task or periodically during the listed task, as defined in the table.

- NR = Not Required, P = Periodic, C = Continuous
- (b) Required for the first 5000 square feet (465 square meters) of AAC masonry.
- (c) Required after the first 5000 square feet (465 square meters) of AAC masonry.



5 2 0 . 8 8 2 . 9 9 4 4

## **Tubac, AZ 85646 2227 I-19 Frontage RD.**,



PROJECT NO: 23.21.00

June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION

DRAWN BY: SL

CHECKED BY: AD THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



NOTES:

1. Tables taken directly from IBC for reference.



#### () <u>KEYNOTES:</u>

- 1 5" THICK CONCRETE SLAB ON 15 MIL VAPOR BARRIER OVER 4" BASE COURSE. REFER TO DETAIL 2/ S2.2
- 7" THICK CONCRETE SLAB ON 15 MIL VAPOR BARRIER OVER 4" BASE COURSE. REFER TO DETAIL 1/ S2.2
- 3. REFER TO ARCH, CIVIL AND LANDSCAPE DWGS FOR EXTERIOR SITE WORK.
- 4. 'F4.0' INDICATES PAD FOOTING PER SCHEDULE 2/ \$1.1 'WF1' INDICATES WALL FOOTING PER SCHEDULE 2/ \$1.1
  - 'C1' COLUMNS PER SCHEDULE 2/ S1.1
    'MW1' INDICATES MASONRY WALL PER
    SCHEDULE 6/ S3.1

<del>0</del>

3/ S2.1 INDICATES STEP IN FOOTING, REFER TO DETAIL

- 6. (-1'-0") INDICATES TOP OF FOOTING OR TOP OF DRILLED SHAFT REFERENCE ELEVATION.
- 3/ S2.2
  7. 'CJ', 'CTJ' INDICATES SLAB CONTROL JOINTS PER DETAIL
- 8. 2#4x4'-0" AT 3" C/C AT MID-DEPTH OF SLAB, TYP AT ALL SLAB DIS-CONTINUOUS JOINTS AND REPERTURE.
- 9. INDICATES CHANGE IN FLOOR ELEVATION, TYP
- 10. SLOPE SLAB TO DRAIN, REFER TO ARCH DWGS 6/ S2.2
- CONCRETE EQUIPMENT BASE, REFER TO DETAIL
   SEE MECH DWGS FOR SIZE AND LOCATIONS.

	FOOTING (F) (WF) SCHEDULE				
MARK	"W"	"T"	REINFORCING		
F1	x				
F2	x				
WF1	CONT		# CONT.		
WF2	CONT		# CONT.		

COLUMN (C) SCHEDULE				
MARK	COLUMN	BASEPLATES	NOTES	
C1	HSS5x5x1/4	PL5/8"x12"x12"	-	

FOOTING AND COLUMN SCHEDULE

3/4" = 1'-0"

1 FOUNDATION PLAN



Breckenridge g r 0 u p a r c h i t e c t s p l a n n e r s

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

3, AZ 85646

Tubac Fire Station #1 2227 I-19 Frontage RD., Tubac,



PROJECT NO: 23.21.00

DATE:

June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION ISSUED TO

DRAWN BY: SL CHECKED BY: AD

CHECKED BY: AD


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION
PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF
BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR
DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Foundation Plan

**S1.1** 



- 1. 5/8" ROOF SHEATHING, REFER TO DETAIL 1/S4.1
- 2. 7/8" STEEL DECK AT CANOPY, REF DTL 1/S4.4
- 3. SIMPSON 'TB' BRIDGING, MIN ROWS SHOWN, EQUALLY SPACE ALONG JOIST SPAN.
- REFERENCE ELEVATION, VERIFY ALL ELEVATIONS W/ ARCH DWGS.
- 5. ROOF HATCH, FRAME OPENING PER 2/S4.1

#### **KEYNOTES:**

AT HIPS AND VALLEY BEAMS, ATTACH PER

INDICATES BOTTOM OF PLYWOOD


6. ROOF MOUNTED MECH EQUIP & DESIGN UNIT WEIGHTS, REF MECH DWGS FOR EXACT SIZE AND LOCATION. JST MFR TO DESIGN ROOF JOISTS FOR LOADS SHOWN, MIN OF DOUBLE JOISTS AT 24" OC BELOW ALL MECH UNITS. REF 2/S4.1

#### Breckenridge architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4 **AZ 85646** 

**2227 I-19 Frontage RD.**, Station Fire



PROJECT NO: 23.21.00

DATE: June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION

DRAWN BY: SL CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Roof Framing

ROOF FRAMING PLAN - WOOD ROOF APPARATUS BAY

MARTIN WHITE GRIFFI STRUCTURAL ENGINEERS, IN



#### KEYNOTES: (ROOF FRAMING)

- 1. INDICATES 1 1/2"x20GA 'B' GALVANIZED STEEL ROOF DECK, SEE DETAIL 1/ \$4.4
- 2. STEEL JOIST BRIDGING DESIGNED BY JOIST MFR, REF DETAIL 6/S4.4



## Breckenridge architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

**Tubac, AZ 85646 2227 I-19 Frontage RD.**, Tubac Fire Station #1



PROJECT NO: 23.21.00

DATE: June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION

DRAWN BY: SL CHECKED BY: AD


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



ROOF FRAMING PLAN - STEEL ROOF APPARATUS BAY



NOTE: THE CONTRACTOR SHALL BE RESPONSIBLE FOR SHOWING, SHEATHING OR OTHERWISE MAINTAINING THE SIDES OF THE EXCAVATION FROM CAVE-INS UNTIL ALL BACKFILL IS COMPLETED PER SPECIFICATIONS

DOWELS TO LAP

CONC SLAB-ON-

GRADE PER PLAN

30 LB CONT FELT

(2)#5 CONT

**ALT BAR BENDS** 

FOOTING PER PLAN

& MATCH SIZE & SPA

OF VERT WALL REINF

TYP. EXCAVATION DETAILS

NO SCALE

CMU WALL

PER PLAN

**SLAB WHERE** 

**OCCURS** 

FIN. GRADE

SOLID GRŌŪT MĀS

STD. 90° HKS TYP,

SKEW AS REQ'D

NO SCALE

3" CLR 🗡


**BELOW GRADE** 


TOP OF FTG EL PER PLAN

PIPE THRU
FOOTING
WALL

SLEEVES 2" LARGER
THAN O.D. OF PIPES
OTE: FOR PIPES 3'-0" OR LESS BELOW


NOTE: FOR PIPES 3'-0" OR LESS BELOW FTG, PROVIDE SLEEVE AND CONCRETE AS SHOWN; MORE THAN 3'-0" COMPACT BACKFILL OVER PIPE TO 90% AS APPROVED BY SOILS ENGINEER, OR USE STEPPED FOOTING BELOW PIPE.






TYP. CONSTR. JOINT AT COL.

NO SCALE



TYP. STEPPED FOOTING



TYP INTERIOR COL FTG

3/4" = 1'-0"

TYP MASONRY WALL FTG (8" CMU WALL) (

CONC. REINF. LAP SPLICE LENGTH


CONC. REINF. LAP SPLICE LENGTHS (IN.)				
BAR SIZE	LAP SPLICE LENGTH IN INCHES			
BOTTOM BARS T		TOP BARS (SEE NOTE 3)		
#4	29	37		
#5 36		47		
#6	43	56		

NOTES:


1. CONCRETE LAP SPLICE LENGTH IS FOR GRADE 60 REINFORCING, CONCRETE STRENGTH OF 3000 PSI.

- 2. PROVIDE THE SCHEDULED LAP SPLICE UNLESS SPECIFIALLY DETAILED OTHERWISE ON STRUCTURAL DRAWINGS.
- 3. TOP BARS ARE HORIZONTAL BARS IN WHICH 12" OR MORE OF CONCRETE IS PLACED BELOW THE BARS.

CONC. REINF. LAP SPLICE SCHED



TYP CONT WALL FTG (12" CMU WALL)



PLAN VIEW

TYP STEEL COL IN MAS WALL

NO SCALE

L7x4x3/8, CONT
W/ 1/2"x6" CAS
AT 12" OC MAX
AND 4" OC FROM
EDGE


135° STD.
HOOKS

2#6 PER CELL

PLAN VIEW

TYP REINF. AT CONC. WALL & FTG.

PIER DETAIL





Station #1 2227 I-19 Frontage RD., Tubac, AZ 85646

> PRELIMINARY NOT FOR CONSTRUCTION

PROJECT NO: 23.21.00
June 28, 2024
,
REVISION SCHEDULE: # DATE DESCRPITION ISSUED TO
DRAWN BY: SL CHECKED BY: AD
THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.
ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN


Structural Details

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

**S2.1** 

MARTIN WHITE GRIFFIS STRUCTURAL ENGINEERS, INC.

6/28/2024 8:38:03 AM



Breckenridge architects planners 1735 e ft. lowell rd. #12

tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4 85646

AZ Tubac, -19 Frontage RD., Station File

> **PRELIMINARY** NOT FOR CONSTRUCTION

esign

 $\Box$ 

PROJECT NO: 23.21.00 DATE: June 28, 2024 **REVISION SCHEDULE** 

DRAWN BY: SL CHECKED BY: AD


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

Structural Details


MARTIN WHITE GRIFFI STRUCTURAL ENGINEERS, IN



WHERE VERT. OR HORIZ. BARS ARE SHOWN IN THIS DETAIL, PROVIDE BARS OF SAME SIZE AND DETAIL AS SHOWN ON DRAWINGS FOR WALLS. WHERE SIZE IS NOT SHOWN, USE AT LEAST #5 VERTS. AND #4 HORIZ.


NOTES:

) INDICATES LOCATION OF VERT. BARS PLACED AT CENTERLINE OF WALL. (1BAR PER CELL) ) INDICATES LOCATION OF VERT. BARS PLACED AT EÁCH FACE OF WALL, (2 BARS PER CELL). SEE DRAWINGS FOR VERTICAL REINFORCING. POSITION VERT. BARS IN CELLS AS FOLLOWS:




EXTEND MCJ FULL HEIGHT OF MASONRY WALL. ALL HORIZ REINF. TERMINATES AT MCJ EXPECT FOR BOND BEAM REINF. AT FLOORS AND ROOFS, WHICH EXTEND CONTINUOUS THRU LOCATE MCJ's PER PLAN, (DO NOT LOCATE WITHIN 2'-0" OF OPENING)

BOND BEAM 2'-0" MIN. REINF. BOND BM. LAP 4"x4" FILLER **BLOCK** 12" CMU 8" BLOCK BENT REINF. TO 48 BAR DIA MATCH BOND BEAM TYP. REINFORCING 4"x4" FILLER **BLOCK** 



TYP 12" CMU DETAILS

ROOF, FLOOR OR 2'-0" MIN. FROM OPNG. DIAPH LINE ABOVE SEE PLAN FOR LOCATION, TYP. HORIZ. REINF FLR OR DIAPH LINE



1 JAMB BARS (RUN FULL HT FROM DIAPH TO DIAPH):

OPNG. WIDTH	WALL VERTS.
UP TO 4'-0"	2#5
OVER 4'-0" TO 8'-0"	4#5
OVER 8'-0" TO 12'-0"	6#5

- 2 LINTEL PER SCHEDULE, U.N.O.
- SILL BARS: 2#4 IN 8" DEEP BOND BEAM, PROJECT 2'-0" PAST JAMBS.
- (4) 1#4 EACH SIDE, PROJECT 2'-0" PAST OPENING IN SOLID GROUTED 8" CELL OR 8" DEEP BOND BM.
- 5 PIER REINF REQUIRED AT 2'-0" OR LESS IN WALL WIDTHS PER DETAIL (A). PIER VERTS TO RUN FULL HT FROM DIAPH TO DIAPH, TIES TO RUN FULL HT OF JAMB(S).
- 6 #2 TIES AT 8" AT PIER, SEE KEYNOTE 5.

#### CMU REINF LAP SPLICE LENGTHS (IN.

		(1111)
DAD CIZ	BAR SIZE	LAP SPLICE LENGTH IN INCHES
	#4	24
	#5	30
	#6	36

NO SCALE

- MASONRY DESIGN AND LAP SPLICE BASED ON GRADE 40 REINFORCING, (GRADE 60 REINFORCING TO BE USED)
- 2. PROVIDE THE SCHEDULED LAP SPLICE UNLESS SPECIFICALLY **DETAILED OTHERWISE**

MASONRY RIENF LAP SPLICE SCHEDULE


TYPE	REINF. LOCATION	MW1	MW2
ITPE	REINF. LOCATION	8" CMU	12" CMU
VERT	TYP. THROUGHOUT	#5 AT 48" OC	#5 AT 24" OC
VERT	CORNERS, INTERSECTIONS	#5	(4)#5
VERT	EACH SIDE OF MCJ	#5	(4)#5
VERT	JAMB OF OPENING	SEE ELEVATIONS	SEE OPENINGS
HORIZ	TOP OF WALL	(2)#5	(2)#5
HORIZ	ROOF LINES	(2)#5	(2)#5
HORIZ	LINTELS	SEE PLANS / ELEVATIONS	SEE PLANS / ELEVATIONS
HORIZ	SILLS	SEE PLANS / ELEVATIONS	SEE PLANS / ELEVATIONS
HORIZ	JOINT REINF	AT 16" MAX	AT 16" MAX.

PROVIDE THE ABOVE SCHEDULED MINIMUM WALL REINFORCING IN ALL MASONRY UNLESS SPECIFICALLY NOTED OR DETAILED OTHERWISE ON THE DRAWINGS.


8" CMU: MW1 12" CMU: MW2


#### TYP SPECIAL WALL REINFORCING AT OPENING IN MAS WALLS

NO SCALE



В	MAS. OPNG.	D	TOP BARS	BOT. BARS	STIRRUPS & SPA.		
	UP TO 4'-0"	16"	-	2-#5	-		
8",12"	OVER 4'-0" TO 6'-0"	24"	2-#4	2-#5	-		
	OVER 6'-0" TO 8'-0"	32"	2-#5	2-#5	#4 AT 16"		
	OVER 8'-0" TO 10'-0"	40"	2-#5	2-#5	#4 AT 8"		
	OVER 10'-0"	48"	2-#6	2-#6	#4 AT 8"		












NO SCALE





MARTIN WHITE GRIF STRUCTURAL ENGINEERS, IN



**PRELIMINARY** NOT FOR CONSTRUCTION

Breckenridge

architects

planners

1735 e ft. lowell rd. #12

tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

85646

AZ

Tubac,

Frontage RD.,


무

Station

Structural Details


TYP LINTEL REINF. IN CMU WALLS

NO SCALE



STRUCTURAL STEEL STUD WALL ELEVATION

1/4" = 1'-0"



2227 I-19 Frontage RD., Tubac, AZ 85646 Tubac Fire Station #1

Breckenridge g r 0 u p a r c h i t e c t s p l a n n e r s

1735 e ft. lowell rd. #12 tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

**PRELIMINARY** NOT FOR CONSTRUCTION

PROJECT NO: 23.21.00
DATE:

\_\_ June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION

#### DRAWN BY: SL CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Structural Details

STRUCTURAL CMU WALL ELEVATION

1/4" = 1'-0"



Breckenridge

g r 0 u p

a r c h i t e c t s

p l a n n e r s

a r c h i t e c t s p l a n n e r s

1735 e ft. lowell rd. #12

tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

bac Fire Station #1 27 I-19 Frontage RD., Tubac, AZ 85646

PRELIMINARY NOT FOR CONSTRUCTION

 $\Box$ 

PROJECT NO:
23.21.00

DATE:

June 28, 2024

REVISION SCHEDULE:

# DATE DESCRPITION ISSUED TO

DRAWN BY: SL
CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

Structural Details

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

**S4.1** 

MARTIN WHITE GRIF



**AZ 85646 Tubac**, **2227 I-19 Frontage RD.**, Fire Station

architects

1735 e ft. lowell rd. #12

tucson arizona 85719

**PRELIMINARY** NOT FOR CONSTRUCTION

PRO	OJECT NO:		
2	23.21.0	0	
DA1	TE: June 28	3, 2024	
RE\	ISION SCHE	EDULE:	
#	DATE	DESCRPITION	ISSUED


DRAWN BY: SL

CHECKED BY: AD THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Structural Details



MIN DECK CONN ALL SUPPORTS: (4)1/2"Ø PUDDLE WELDS PER SHEET. 1/2"Ø AT 12" OC AT PARALLEL SUPPORTS AND BOUNDRIES. NESTED 1/2"Ø PUDDLE WELDS AT 12" OC

#### **DECK PROFILE**

STL. DECK MIN. SECTION PROPERTIES & DATA			
DECK DEPTH	7/8"		
GAUGE	20		
SPAN RATING	24/32		
FINISH	WEATHERED, REF ARCH DWGS		

NOTES

1. DECK LAYUP SHALL PROVIDE ALL DECK SHEETS OF SUFFICIENT LENGTH TO EXTEND CONTINUOUSLY OVER AT LEAST 3 SPANS.

- 2. ENDS OF ADJOINING DECK SHEETS SHALL BE CENTERED OVER SUPPORTS & ABUTTED OR ACCEPTABLY LAPPED 2". ABUTTED SHEETS REQUIRE 2 TYPICAL SCREWS AT EACH SCREW LOCATION.
- 3. DO NOT SUSPEND CEILINGS, LIGHT FIXTURES AND CONDUITS, DUCTS, PIPING, OR OTHER UTILITIES AND UTILITY COMPONENTS FROM DECK
- 4. SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

TYP CORRUGATED STEEL ROOF DECK AT CANOPY

NO SCALE

Breckenridge

g r 0 u p

a r c h i t e c t s

p I a n n e r s

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Tubac, AZ 85646

Tubac Fire Station #1 2227 I-19 Frontage RD., T

evelopment

PRELIMINARY NOT FOR CONSTRUCTION

PROJECT NO: 23.21.00
DATE:

June 28, 2024

REVISION SCHEDULE:
# DATE DESCRPITION ISSUED T

DRAWN BY: SL

CHECKED BY: AD

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION
PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF
BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR
DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Structural Details

MARTIN WHITE GRIFFIS STRUCTURAL ENGINEERS, INC.

LOT 6/28/2

<u>SUBSTRATE</u> **FASTENER:** THICKNESS:

1/8"-3/8" HILTI 'X-HSN 24'

TYP 1 1/2" STEEL ROOF DECK

1/4"-UNLIMITED HILTI 'X-ENP-19'

POWDER ACTUATED DECK FASTENER:

(5) POWDER ACTUATED FASTENERS, EA SUPPORT. POWDER ACTUATED FASTENERS AT 12" OC. AT PARALLEL SUPPORTS AND BOUNDRIES.

MIN. DECK CONNECTION AT ALL SUPPORTS:


**UP TO 9" SQ OR 9"Ø** 

#10 SCREW

AT 6" OC

AT 4" C/C


BUTTON PUNCH SIDE SEAM CONNECTION AT 12" OC.



1. DECK LAYUP SHALL PROVIDE ALL DECK SHEETS OF SUFFICIENT LENGTH TO EXTEND CONTINUOUSLY OVER AT LEAST 3 SPANS.

- 2. ENDS OF ADJOINING DECK SHEETS SHALL BE CENTERED OVER SUPPORTS & ABUTTED OR ACCEPTABLY LAPPED 2". ABUTTED SHEETS REQUIRE 2 TYPICAL CONNECTIONS AT EACH CONNECTION LOCATION.
- DECK SHALL BEAR 2" MIN ON SUPPORT AT EACH END OF **DECK SPAN**
- DO NOT SUSPEND CEILINGS, LIGHT FIXTURES AND CONDUITS, DUCTS, PIPING, OR OTHER UTILITIES AND UTILITY COMPONENTS
- DECK SHOP DRAWING SUBMITTAL SHALL INCLUDE FASTENER TYPE AND ZONES WHERE USED BASED ON SUBSTRATE THICKNESS
- SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

#### PROVIDE C4x5.4 AT PERIM TYP $\frac{3/16}{}$ $^{2}$ OF BASE AT ROOF MTD. EQUIP. IN ADD'N. TO FRAMING AROUND OPENING C4x5.4 OPEN ≶ C4x5.4 L4x3x1/4x0'-6" (LLV) SPAN OF STL. DECK CL. JOIST CL. JOIST OR BEAM OR BEAM



AT OPENINGS LESS THAN 24", REFER TO DETAIL

OPENINGS INCLUDE ROOF DRAIN RECEPTORS, PIPES, CONDUITS, SLEEVES, DUCTS, ETC. WHERE CLUSTERS OF THESE ITEMS IN ONE LOCATION EXCEED 24", PROVIDE FRAMED OPENING PER THIS DETAIL

TYP ROOF DECK FRAMING AT OPENINGS & ROOF MOUNTED MECH EQUIPMENT NO SCALE

#### L2 1/2x2 1/2x1/4", 18" MIN 24" MAX TYP AT UNDERSIDE **SUPPORTING MEMBERS** OF DECK TYPICAL ANGLE #10 SCREW 12 GA STRENGTHENING TO ANGLE **EACH VALLEY** PL ON TOP OF DECK OR 6" OC (2)#10 SCREWS **METAL DECK** METAL DECK **OPENINGS OVER 9" UP TO 24"**


AT OPENINGS GREATER THAN 24", PROVIDE FRAMED OPENING PER DETAIL

OPENINGS INCLUDE ROOF DRAIN RECEPTORS, PIPES, CONDUITS, SLEEVES, DUCTS, ETC. WHERE CLUSTERS OF THESE ITEMS IN ONE LOCATION EXCEED 24", PROVIDE FRAMED OPENING PER DETAIL

#### TYP SMALL OPENINGS IN ROOF DECK

OPENINGS UP TO 9"(A)

NO SCALE




#### TYP BRIDGING AT WALL


#### TYP BRIDGING AT MECH DUCTS

- NOTES: DO NOT SUSPEND CEILINGS, LIGHT FIXTURES, DUCTS, PIPES OR OTHER UTILITIES FROM JOIST BRIDGING.
- STANDARD SPECS. 2. USE SIM. BRIDGING & CONNECTIONS AT STEEL BEAMS.


#### TYP MIN JOIST CROSS BRIDGING

**NO SCALE** 






TYP STL JOIST (LH SERIES) BRG ON MAS WALL NO SCALE



TYP STEEL DECK BEARING ON MAS WALL NO SCALE



85646 Tubac, **I-19 Frontage RD.**, Station FIFE




PROJECT NO: 23.21.00 DATE:
June 28, 2024
REVISION SCHEDULE: # DATE DESCRPITION ISSUED TO
DRAWN BY: SL CHECKED BY: AD
THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.
ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF


COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN


Structural Details


MARTIN WHITE GRIFF STRUCTURAL ENGINEERS, IN





TYP BASE TRACK CONN AT CONC







STUD SIZE)

#### TYPICAL LINTEL DETAILS(C) TYP. LINTEL BEARING (E)

OPENING SCHEDULE U.N.O.								
ROUGH OPENING LINTEL JAMB STUD(S)								
UP TO 4'-0"	2-6"x18GA.	1 STUD						
+4'-0" TO 8'-0"	2-8"x18GA.	2 STUDS						
+8'-0" TO 10'-0"	4-6"x16GA.	3 STUDS						
+10'-0" - SEE PLANS AND ELEVATIONS								
OPENING	SCHEDU	LE D						





LINTEL PER

x3" FRMG.

SCHED.


12 GA.x3"

CLIP W/ 2#10-16

SCREWS EACH LEG

	MIN. STRUCTURAL PROPERTIES FOR STRUCTURAL STUDS AND TRACKS										
UDS	600S162-43	6" 6" 1.625"	Sx=0.767 IN.	Ix=2.316 IN.							
STRUCTUAL STUDS	600S162-54	6" <u>6"</u> 1.625 <u>"</u>	Sx=0.927 IN.	Ix=2.860 IN.							
UCTU	600S162-68	6" 575"	Sx=1.164 IN.	Ix=3.525 IN.							
STR	600S162-97	6" 6" 1.625"	Sx=1.599 IN.	Ix=4.797 IN.							
CKS	600T125-54	1.25	Sx=0.653 IN.	Ix=2.221 IN.							
STR. TRACKS	600T125-68	1.25	Sx=0.874 IN.	Ix=2.930 IN.							
STR	600T125-97	1.25	Sx=1.374 IN.	Ix=4.281 IN.							








3#10 SCREWS

EACH FLANGE,

EACH SIDE OF

**SPLICE** 

TYP TRACK SPLICE



TOP OR

**BOTTOM** 

**TRACK** 


MAX.

STEEL STUD NESTED INTO


STEEL STUDS


AT 16" O.C.

TRACK














Breckenridge

architects

planners

1735 e ft. lowell rd. #12

tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

AZ 85646

Tubac,

1-19 Frontage RD.,

Station

Fire


Development


Design

PROJECT NO: 23.21.00  DATE: June 28		
REVISION SCHE	:DULE:	
# DATE	DESCRPITION	ISSUED TO
DRAWN BY: SL		
CHECKED BY: A	D	
PURPOSES UNTIL	NOT TO BE USED FOR SEALED AND SIGNED GROUP ARCHITECTS/F NSULTANTS.	BY ARCHITECTS O
SAFEGUARDED B UNAUTHORIZED I THIS DRAWING, V	DRAWINGS AND DESI IY THE FEDERAL COPY USE, REPRODUCTION, WHETHER IN WHOLE O HIBITED WITHOUT PRI	RIGHT ACT. ANY OR DISTRIBUTION R IN PART, IS
COPYRIGHT 2024	BRECKENRIDGE GRO	UP ARCHITECTS &

Structural Details

MARTIN WHITE GRIFFI STRUCTURAL ENGINEERS, IN





2"x20GA. CONTINUOUS STRAP AT EACH SIDE 1 1/2"x1 1/2"x16GA. 50 ksi SUPPORT CLIP, 5" LONG WITH (2)#10-16 SCREWS PER LEG (3) #10-16 SCREWS AT EACH SIDE TO 1 1/2"x1 1/2"x16GA., 50 ksi SUPPORT CLIP, **EACH SOLID BLOCK** 5" LONG WITH (2)#10-16 (1) #10-16 SCREW AT EACH SCREWS PER LÉG SIDE AT EACH INTERSECTION NOTE: SOLID BLOCK FIT IN FIRST AND LAST 2 BAYS, REPEAT IN 1 BAY AT EVERY 8'-0" O.C. USE 1 1/2"x4"x16GA., 50 ksi SUPPORT CLIP, 5" LONG WITH (2)#10-16 SCREWS PER LÉG AT **BRIDGING FOR DOUBLE** 

4#10 SCREWS #10 SCREW **EACH LEG** 14 GA.x 4" BENT PL. 4" TYP. SOFFIT FRAMING PER DETAILS

HSS JAMB COL. PL.1/2x6x0'-8" W/ 2-1/2"Øx4" C.A.S. AT 6" C/C

TYP. SOFFIT CORNER


HSS CONN. AT CONCRETE

MUTIPLE JACK/JAMB STUD DETAIL

**BLOCK AND STRAP BRIDGING** 

TYPICAL STRUCTURAL STEEL STUD WALL FRAMING (CONTINUED)

STUDS



#### NOTES:

PLYWOOD:

(a) WALLS: 1/2" PLYWOOD.

(b) STAGGER SHEETS AS SHOWN. (c) RUN FACE GRAIN HORIZONTAL.

(d) MINIMUM SHEET SIZE SHALL BE 2'-0"x4'-0"

2. MINIMUM ATTACHMENTS: (REFER TO DETAIL AT SHEAR WALLS). (a) SCREWS SHALL BE #8 FLAT HEAD SELF TAPPING WITH MINIMUM

HEAD DIAMETER OF 0.292".

(b) MINIMUM EDGE DISTANCE SHALL BE 3/8", AND SCREWS SHALL NOT BE OVERDRIVEN THRU OUTER PLY.

(c) EDGE CONNETION:

SCREW AT 6" O.C., EDGES AT OPENINGS: SCREWS AT 6" O.C.

(d) INTERMEDIATE:

(1) TYP.: SCREW AT 12" O.C. (e) BLOCK ALL EDGES WITH 16GA. UNPUN. TRACK BLOCKING AND STRAPING PER DETAIL AT SHEAR WALL ONLY.

(f) BRIDGING PER

NOT REQUIRED AT SHEAR WALLS.


## TYP. WALL SHEATHING

	SHEARWALL SCHEDULE									
WALL TYPE										
SW1										

1. FOR LOCATION OF SHEAR WALLS, SEE PLANS. 2. ALL PLYWOOD EDGES SHALL BE BLOCKED WITH STEEL STUD BLOCKING PER DETAIL

3. USE 6 ANCHORS MINIMUM AT SHEAR WALLS.

4. REFER TO DETAIL FOR ADDITIONAL NOTES.



	HOLDOWN (HD) SCHEDULE											
	SIMPSON HOLDOWN		BASE CONN.	NOTES								
HD1	S/HTT14	14#10 SCREWS DOUBLE STUDS	SIMPSON S 'SSTB16'	MIN. EMBED. 12 5/8"								

HOLDOWN DETAIL

June 28, 2024 REVISION SCHEDULE # DATE DESCRPITION DRAWN BY: SL CHECKED BY: AD THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS. ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

PROJECT NO:

DATE:

23.21.00

Breckenridge

architects planners

1735 e ft. lowell rd. #12

tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

AZ 85646

Tubac,

**2227 I-19 Frontage RD.**,

**PRELIMINARY** 

NOT FOR

CONSTRUCTION

Fire Station


Development

Structural Details

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &

SHEAR WALL SCHEDULE

MARTIN WHITE GRIFFI STRUCTURAL ENGINEERS, IN



				WASTE FIXTURE UNITS		WATER FIXTURE I	UNITS*	CONNECTI	ION SIZES (	INCHES) *	*
MARK	FIXTURE	DESCRIPTION	QTY	FU	TOTAL	FU	TOTAL	WASTE	VENT	HOT	COLD
P1	WATER	KOHLER "HIGHCLIFF" #K-96057, 1.6 GAL./FLUSH MAXIMUM, VITREOUS CHINA,	4	4	16	5	20	4	2	_	1 1/4
	CLOSET	FLOOR MOUNTED, FLUSH VALVE WATER CLOSET W/ADA COMPLIANT HIGH BOWL.									
	(ADA)	PROVIDE SLOAN G2 8111-1.6 BATTERY POWERED FLUSH VALVE, CHURCH #9500SSC									
		SELF-SUSTAINING CHECK HINGES, OPEN FRONT SEAT									
P2	LAVATORY	KOHLER "PENNINGTON" #K-2196, VITREOUS CHINA SELF-RIMMING OVAL	2	1	2	1	2	2	1 1/2	1/2	1/2
		LAVATORY. PROVIDE DELTA 520-MPU-DST SINGLE LEVER FAUCET (0.5 GPM) &									
		McGUIRE CHROME PLATED LOOSE KEY QUARTER TURN ANGLE STOPS &									
		SUPPLIES CAST BRASS "P" TRAP & WASTE & STOP INSULATION EQUAL TO									
		TRUEBRO #102. PROVIDE ASSE 1070 CERTIFIED THERMOSTATIC MIXING									
		VALVE EQUAL OF WATTS MODEL # LFUSG-B W/ 3/8" FITTINGS.				ļ					
P3	LAVATORY	KOHLER "PENNINGTON" #K-2196, VITREOUS CHINA SELF-RIMMING OVAL	2	1	2	1	2	2	1 1/2	1/2	1/2
		LAVATORY. PROVIDE SLOAN SF-2350 FAUCET (0.5 GPM, 0.25 GALS. MAX PER CYCLE) &									
		GRID DRAIN, McGUIRE CHROME PLATED LOOSE KEY QUARTER TURN ANGLE STOPS &									
		SUPPLIES CAST BRASS "P" TRAP & WASTE & STOP INSULATION EQUAL TO									
		TRUEBRO #102. PROVIDE ASSE 1070 CERTIFIED THERMOSTATIC MIXING									
		VALVE EQUAL OF WATTS MODEL # LFUSG-B W/ 3/8" FITTINGS.				1				,	ļ.,
P <b>4</b>	SHOWER	SYMMONS MODEL #C-96-500X-B30-L-V THERMOSTATIC PRESSURE BALANCING MIXING	2	-	_	2	4	_	_	1/2	1/2
	TRIM	VALVE, HAND HELD SPRAY UNIT AND FIXED SHOWER HEAD. 60" LONG HOSE, INTEGRAL									
		STOPS, VACUUM BREAKER AND 30" SLIDE BAR FOR HAND HELD SPRAY UNIT.									
		PROVIDE 2" ROUND GRID TYPE SHOWER DRAIN SIMILAR TO KOHLER 22675				1			<u> </u>	,	ļ.,
P5	KITCHEN	ELKAY #LRAD-3322, (33" X 22" X 6-1/2") STAINLESS STEEL, 2-COMPARTMENT,	1	2	2	1.5	1.5	2	1 1/2	1/2	1/2
	SINK	FOUR HOLE PUNCH, W/DELTA 400-DST FAUCET W/1.5 GPM @ AERATOR &									
		SPRAY, TWO STAINLESS STEEL BASKET STRAINERS, McGUIRE CHROME									
		PLATED, LOOSE KEY QUARTER TURN ANGLE STOPS & SUPPLIES & CAST BRASS "P" TRAP.									
		PROVIDE INSINKERATOR BADGER 15SS CONTINUOS FEED GARBAGE DISPOSAL W/									
	2007	3/4 HP MOTOR.			ļ.,		<u>.</u>		/2	. /0	
P6	SINK	ELKAY LRAD252160 SINGLE BOWL, DROP-IN SINK, (25X21-1/4X6) W/BOWL DIMENSIONS (21X15-3/4X5-7/8)	2	2	4	2	4	2	1 1/2	1/2	1/2
		SELF-RIMMING, 18 GA STAINLESS STEEL, THREE HOLE PUNCH, W/DELTA MODEL 100-DST FAUCET									
		W/1.5 GPM AERATOR AT 60 PSI, STAINLESS STEEL BASKET STRAINER, CHROME PLATED									
D.7	LIOD CIVIL	QUARTER TURN ANGLE STOPS AND SUPPLIES AND CAST BRASS P-TRAP.		+ -	7	+ -	-	7		7/4	7/4
P7	MOP SINK	FIAT #MSB-2424 MOP SERVICE BASIN (24 X 24), #231 WHITEDRIFT.	1	3	3	3	3	3	2	3/4	3/4
		PROVIDE "FIAT" CHROME PLATED SERVICE FAUCET #830-AA WITH									
		VACUUM BREAKER, HOSE AND HOSE BRACKET #832—AA, MOP HANGER									
D0	CINIK	#889-CC AND VINYL BUMPER GUARD #E-77-AA.	4	<u> </u>		1			4.4/0	4 /0	1 /0
P8	SINK	ELKAY 14-3C16X20-2-18X FREESTANDING SINK WITH DRAINBOARDS, 18 GA. STAINLESS	1	2	2	2	2	2	1 1/2	1/2	1/2
		STEEL. PROVIDE CHICAGO FAUCET #445-E35ABCP W/ LEVER HANDLES, 1.5 GPM									
		PROVIDE STAINLESS STEEL BASKET DRAIN, CAST BRASS "P" TRAP &									
P9	WASHER	McGUIRE CHROME PLATED LOOSE KEY QUARTER TURN ANGLE STOPS AND SUPPLIES.	1	3	7	1	1 4	1 2	1 2	3/4	3/4
79	WASHER	GUY GRAY #BB200TS, HOSE END VALVES AND WASTE CONNECTION.		] 3	3	4	4	2	2	3/4	3/4
P10	WALL BOX WALL	GUY GRAY #BIM-875, COMPRESSION ANGLE VALVE FOR ICE MAKER HOOK-UP.	4	<del> </del> _							1/2
riu	BOX	GUT GRAT #DIM-8/3, COMPRESSION ANGLE VALVE FOR ICE MAKER HOUK-UP.	4	-		-	-				1/2
FS	FLOOR	J.R. SMITH 3110-12, 12"X12"X6" DEEP W/HALF GRATE	1	3	3	<del>  _</del>	<del>  _</del>	2	1 1/2	_	<del> </del>
13	SINK	J.K. SMITH STID-12, 12 ATZ AD DEEL WYHAEL GRATE	Ų						1 1/2	_	
FD	FLOOR	J.R. SMITH 2005-BP, COATED CAST IRON BODY AND ADJUSTABLE	2	2	4			2	1 1/2		
īυ	DRAIN	5" SQUARE NIKALOY STRAINER W/ TRAP SEAL GUARD			4	-	_	4	' '/'	_	_
HB	HOSE BIBB	WOODFORD #24P-3/4 BRASS HOSE BIBB W/VACUUM BREAKER & REMOVABLE	8	_	_	2.5, 1	9.5				3/4
טוו	HOSE DIDD	LOOSE KEY HANDLE ATTACHED TO OPERATING STEM.	0	-	_	2.3,	3.5	_		_	] 3/4
		TOTAL FIXTURE UNITS	<u> </u>	<u> </u>	41	+	52		1	<u> </u>	<u> </u>
		TOTAL TIATURE UNITS			41	1	ı JZ				

\* PER 2012 IPC SECTION 604.1, THE WATER PIPE SIZE TO CONFORM TO AN ACCEPTED ENGINEERING PRACTICE.

PIPE SIZE IS BASED ON USING IAMPO RECOMMENDATIONS THAT IS AN ACCEPTED ENGINEERING PRACTICE AND IS BASED ON LOW FLOW FIXTURES.

\*\* FIXTURE SERVICE PIPE SIZE SHALL BE THE SIZE INDICATED WITH REDUCER (IF REQ'D) AS CLOSE TO FIXTURE CONNECTION AS POSSIBLE

WATER HEATER SCHEDULE	
MARK	WH1 & WH2
ENTERING WATER TEMPERATURE (DEG. F)	60
LEAVING WATER TEMPERATURE (DEG. F)	140
RECOVERY RATE (GPH)	31
STORAGE VOLUME (GAL.)	55
ELECTRICAL INPUT (KW)	6
VOLTS/PHASE/HZ	480/3/60
REFERENCE	BRADFORD WHITE
	LE255T3-5
EXPANSION TANK	AMTROL
REFERENCE	ST-12
RELIEF VALVE SETTING (PSIG)	150
NOTES	1 THRU 5
1. WATER HEATER SHALL BE UL LISTED.	
2 DECOVEDY DATE COHEDINED IS FOD SEA LEVEL	

2. RECOVERY RATE SCHEDULED IS FOR SEA LEVEL.

3. HEATING ELEMENTS ARE NON-SIMULTANEOUS.

4. PROVIDE HEAT TRAP FITTINGS AT COLD & HOT WATER CONNECTIONS EQUAL TO "WATTS". 5. PROVIDE RECIRCULATION PUMP EQUAL TO ARMSTRONG ASTRO 225, 1/25 HP, 115/1/60.


MECHANICAL ENGINEERING, L.L.C.

 5447 East Fifth Street # 112
 520/327-7611

 Tucson, Arizona 85711
 520/327-0432

 Designers Mech: MQ Plumb: KGW Project #: 24-21

architects planners 1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4



PROJECT NO: 23.21.00 JUNE 2024

# DATE DESCRPITION ISSUED TO


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS

Plumbing Schedules

ER



FAN COIL UNIT SCHEDULE	
RK	VRF-FC-1 AND 2
TCHING CONDENSING UNIT MARK	VRF-HP 1
E	CASSETTE
MINAL TONNAGE	3/4
MINAL COOLING CAPACITY (MBH)	9.1
MINAL HEATING CAPACITY	10.0
TAL SUPPLY AIR (CFM)	247
TAL OUTSIDE AIR (MAX)	20
_TS/PHASE/HZ	208/1/60
T AMPS	0.3
GHT (LBS.)	30
TER HOUSING SIZE	INTEGRAL
TER SIZE	INTEGRAL
ERENCE	SAMSUNG
	AC009BNNDCH/AA
TES	1,2,3,4,6
SCHEDULE CAPACITY SHALL BE FOR 3267 FT. ELEVATION	AT ENTERING AIR

- CONDITIONS AS SPECIFIED. PROVIDE ALL NECESSARY INTERCONNECTING PIPING (& REFRIGERANT ACCESSORIES) &
- CONTROL WIRING BETWEEN FAN COIL UNIT, CONTROLLER (AS REQUIRED) & MATCHING CONDENSING UNIT.
- UNIT SHALL HAVE SINGLE POINT POWER CONNECTION. UNIT DISCONNECT MEANS TO BE PROVIDED BY ELECTRICAL.
- 4. PROVIDE WASHABLE FILTER AND WALL MOUNTED PROGRAMMABLE THERMOSTAT . PROVIDE EXTERNAL CONDENSATE PUMP EQUAL TO LITTLE GIANT MODEL VCMA-20ULS,
- 1/30 HP, 115/1/60, 1.5 AMPS, 93 WATTS. 5. PROVIDE FACTORY INSTALLED INTERNAL CONDENSATE PUMP

VRF HEATPUMP UNIT SCHEDULE	
MARK	VRF-HP 1
TYPE	HEAT PUMP
INDOOR UNIT TYPE	CASSETTE
NOMINAL TONNAGE	1.5
NUMBER OF CONNECTED INDOOR UNITS	2
NOMINAL TOTAL COOLING CAPACITY (MBH)	18.0
COOLING AMBIENT TEMPERATURE (DEG. F)	95
NOMINAL HEATING CAPACITY (MBH)	22.0
HEATING AMBIENT TEMPERATURE (DEG. F)	47
UNIT ENERGY EFFICIENCY RATIO (SEER)	18.8
VOLTS/PHASE/HZ	208/1/60
UNIT MCA	16.5
UNIT MOCP	20
WEIGHT (LBS)	175
REFRIGERANT TYPE	R410A
REFERENCE	SAMSUNG
	AJ020BXJ2CH/AA
NOTES	1 THRU 5

1.	. SCH	EDULE	CAP	ACIT	Y SH	ALL	BE	FOF	R 3267	FT.	ELEVAT	ON.	CAPA	CITY	OF
	UNIT	SHALL	. BE	AS	SCHE	DUL	LED	TO	PROVID	E RI	EQUIRED	CAF	PACITY	FOR	
	ALL	CONNE	CTED	INI (	OOOR	UN	ITS.								

- 2. PROVIDE SINGLE POINT POWER CONNECTION. UNIT DISCONNECT MEANS TO BE PROVIDED BY ELECTRICAL.
- 3. PROVIDE ALL NECESSARY CONTROLS TO PREVENT COMPRESSOR RAPID
- RECYCLING AND ALL FEATURESSTANDARD TO THE UNIT SCHEDULED. 4. PROVIDE ADDITIONAL REFRIGERANT AS REQUIRED BY MANUFACTURER'S
- LITERATURE FOR SUM TOTAL OF ALL LINE SETS ON SYSTEM. 5. PROVIDE LOW AMBIENT COOLING KIT TO MINIMUM 20 DEG F.

SUPPLY FAN SCHEDULE							
MARK	SF-1	SF-2					
TYPE	IN-LINE	IN-LINE					
WHEEL TYPE	FC	FC					
AIR FLOW (CFM)	85	85					
E.S.P. (IN W.G.)	0.25	0.25					
DRIVE TYPE	DIRECT	DIRECT					
MAXIMUM FAN SPEED (RPM)	838	838					
MAXIMUM SONES	1.2	1.2					
MOTOR HP	31 WATTS	31 WATTS					
VOLTS/PHASE/HZ	115/1/60	115/1/60					
MAXIMUM OPERATING WEIGHT (LBS)	25	25					
REFERENCE	COOK	COOK					
	GN-148	GN-148					
NOTES	1 THRU 7	1 THRU 6, 8					
1 COUEDUIE CADACITY CHALL DE FOD 720	1 CONTROLLE CARACITY CHALL DE FOR 7207 ET ELEVATION						

- SCHEDULE CAPACITY SHALL BE FOR 3267 FT ELEVATION.
- P. FAN PERFORMANCE SHALL BE AMCA CERTIFIED.
- . PROVIDE WALL CAP WITH BIRSCREEN
- 4. PROVIDE DISCONNECT SWITCH AND FACTORY INSTALLED SPEED CONTROLLER
- 5. PROVIDE (NEOPRENE) HANGING ISOLATOR KIT WITH BRACKETS.
- 6. PROVIDE INLET AND DISCHARGE DUCT COLLARS.
- . INTERLOCK WITH VRV-FC 1, VRV-FC 2, FC-3, AND FC-4 FAN MOTOR
- 8. INTERLOCK WITH FC-3 THRU FC-8 FAN MOTOR

EVAPORATIVE COOLER SCHEDULE	
MARK	EC-1 & EC-2
TYPE	SINGLE INLET
MINIMUM ADIABATIC EFF. (%)	89
SUPPLY AIR FLOW (CFM)	10,950
EXT. STATIC PRESSURE ("w.g.)	0.5
FAN TYPE	CENTRIFUGAL
FAN MOTOR HP	3
VOLTS/PHASE/HZ	460/3/60
PUMP MOTOR HORSEPOWER	1.7 AMPS
VOLTS/PHASE/HZ	115/1/60
MEDIA TYPE	8" CELdek
MAXIMUM OPERATING WEIGHT (LBS.)	1200
REFERENCE	PHOENIX
	ID601
NOTES	1,2,3
1. SCHEDULE CAPACITY SHALL BE FOR 3270 FT. ELEVATION.	

. PROVIDE RECIRCULATION PUMPS AND BLEED/FLUSH KITS; COMPLETE WITH BLEED LINES.

. PROVIDE SINGLE POWER CONNECTION WITH FACTORY INSTALLED DISCONNECT SWITCH

EXHAUST FAN SCHEDULE							
MARK	EF-1 THRU 4	EF-5	EF-6	EF-7	EF-8	EF-9	
TYPE	CEILING	CEILING	ROOFTOP	ROOFTOP	ROOFTOP	ROOFTOP	
WHEEL TYPE	F.C.	F.C.	B.I.	B.I.	B.I.	F.C.	
AIR FLOW (CFM)	150	50	1150	3075	1000	100	
E.S.P. (IN W.G.)	0.25	0.25	1	0.25	0.25	0.25	
DRIVE TYPE	DIRECT	DIRECT	BELT	BELT	BELT	DIRECT	
MAXIMUM FAN SPEED (RPM)	825	688	1231	746	1128	909	
MAXIMUM SONES	2.5	1	10.6	8.9	7	1.5	
MOTOR HP	61 WATTS	23 WATTS	1/2	1/2	1/4	34 WATTS	
VOLTS/PHASE/HZ	115/1/60	115/1/60	460/3/60	460/3/60	115/1/60	115/1/60	
MAXIMUM OPERATING WEIGHT (LBS)	25	25	200	200	125	25	
REFERENCE	СООК	COOK	COOK	COOK	COOK	COOK	
	GC-186	GC-128	ACRU-165	ACE-195	ACE-120	GC-148	
NOTES							

FAN COIL UNIT SCHEDULE					
MARK	FC-1	FC-2 AND FC-3	FC-4 THRU FC-8	FC-9 AND FC-10	FC-11
MATCHING CONDENSING UNIT MARK	HP-1	HP-2 AND HP-3	HP-4 THRU HP-8	HP-9 AND HP-10	HP-11
TYPE	CASSETTE	CASSETTE	CASSETTE	WALL MOUNTED	WALL MOUNTED
MINIMUM TOTAL COOLING CAPACITY (MBH)	9.1	9.1	9.1	18	12
MINIMUM TOTAL HEATING CAPACITY (MBH)	10	10	10	N/A	N/A
ENTERING AIR TEMPERATURE (DEG. DB/WB)	80/67	80/67	80/67	80/67	80/67
TOTAL SUPPLY AIR (CFM)	247	247	247	533	374
OUTSIDE AIR (CFM)	15	10	15	N/A	N/A
DRIVE TYPE	DIRECT	DIRECT	DIRECT	DIRECT	DIRECT
VOLTS/PHASE/HZ	208/1/60	208/1/60	208/1/60	208/1/60	208/1/60
FULL LOAD AMPS	65	65	65	27	27
MAXIMUM OPERATING WEIGHT (LBS.)	30	30	30	30	25
REFERENCE	SAMSUNG	SAMSUNG	SAMSUNG	SAMSUNG	SAMSUNG
	AC018BNNDCH/AA	AC018BNNDCH/AA	ACO18BNNDCH/AA	AR18CSDABWKNCV	AR12CSDABWKNCV
NOTES	1 THRU 6				

- . SCHEDULE CAPACITY SHALL BE FOR 3267 FT. ELEVATION.
- 2. PROVIDE ALL NECESSARY INTERCONNECTING PIPING (& REFRIGERANT ACCESSORIES) & CONTROL WIRING BETWEEN FAN COIL UNIT & MATCHING CONDENSING UNIT.
- 3. FAN COIL UNIT SHALL HAVE SINGLE POINT POWER CONNECTION.
- . REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS FOR LONG LENGTH APPLICATIONS.
- . MANUFACTURER SHALL PROVIDE ALL NECESSARY DEVICES, VALVES, ETC. AS REQUIRED FOR THIS APPLICATION.
- S. PROVIDE MODEL WIRED WALL MOUNTED CONTROLLER.
- 7. PROVIDE INTERNAL CONDENSATE PUMP

CONDENSING UNIT SCHEDULE			
MARK	HP-1 THRU HP-8	HP-9 AND HP-10	HP-11
MATCHING FAN COIL UNIT MARK	FC-1 THRU FC-8	FC-9 AND FC-10	FC-11
COOLING AMBIENT TEMPERATURE (DEG. DB)	95	95	95
MINIMUM SEASONAL ENERGY EFFICIENCY RATIO (SEER)	21	21	23
UNIT MCA	10.9	21	12.5
UNIT MOCP	15	30	20
VOLTS/PHASE/HZ	208-230/1/60	208-230/1/60	208-230/1/60
MAXIMUM OPERATING WEIGHT (LBS.)	150	225	150
REFERENCE	SAMSUNG	SAMSUNG	SAMSUNG
	AC009BXADCH/AA	AR18CSDABWKXCV	AR12CSDABWKXCV
NOTES	1 THRU 6	1 THRU 6	1 THRU 6
1. CAPACITY OF UNIT SHALL BE AS SCHEDULE FOR MATC	HING FAN COIL UNIT.		

- 2. PROVIDE ALL FEATURES STANDARD TO THE UNIT SCHEDULED. FAN RELAY, LIQUID LINE FILTER CONTROL (TO PREVENT RAPID COMPRESSOR RECYCLING) & START RELAY/CAPACITOR KIT ( FOR
- 3. PROVIDE LOW AMBIENT CONTROL TO 25 DEG. F.
- 4. PROVIDE 5 YEAR COMPRESSOR WARRANTY
- 5. MOUNT ON 3/4" WAFFLE STYLE ISOLATORS EQUAL OF MASON INDUSTRIES 'SUPER W' OR EQUIVALENT.
- . PROVIDE ROOF CURB FOR CONDENSING UNIT.

UNIT MOCP

REFERENCE

NOTES

HP-10	HP-11	MARK	H-1 THRU H-
FC-10	FC-11	TYPE SEP	ARATED COMB
	95	ENERGY SOURCE	NATURAL GA
	23	NATURAL GAS INPUT (CFH)	60
	12.5	MINIMUM COMBUSTION EFF %	83
	20	NUMBER OF STAGES	2
/1/60	208-230/1/60	AIR FLOW (CFM)	750
	150	BLOWER MOTOR HP	1/6
NG	SAMSUNG	VOLTS/PHASE/HZ	115/1/60
BWKXCV	AR12CSDABWKXCV	MAXIMUM OPERATING WEIGHT (LBS)	100
J 6	1 THRU 6	REFERENCE	REZNOR
			UDAS-60
DRIER, AN	TI-RECYCLING	NOTES	1 THRU 6
OR EASY	STARTING).	1. SCHEDULE CAPACITY SHALL BE FOR 3267 FT. ELEV	ATION.
		2. PROVIDE TWO-STAGE NATURAL GAS VALVE.	
		3. PROVIDE 409 STAINLESS STEEL HEAT EXCHANGERS.	
		4. PROVIDE VERTICAL COMBUSTION AIR/VENT KIT.	

IR CONDITIONING UNIT SCHEDULE (PACKAGED ROC	PFTOP)		
ARK	AC-1	AC-2	AC-1
OMINAL TONNAGE	3		3
INIMUM TOTAL COOLING CAPACITY (MBH)			
INIMUM SENSIBLE COOLING CAPACITY (MBH)			
OOLING AMBIENT TEMPERATURE (DEG. F)	110		
NTERING AIR TEMPERATURE (DEG/DB/WB)			
INIMUM SEASONAL ENERGY EFFICIENCY RATIO (SE	ER)		
INIMUM NUMBER OF COMPRESSORS			
YPE OF HEATING CAPACITY	NATURAL GAS	NATURAL GAS	NATURAL GAS
INIMUM HEATING CAPACITY (MBH)			
EATING AMBIENT TEMPERATURE (DEG.F)			
AXIMUM NATURAL GAS INPUT (CFH)			
INIMUM NUMBER HEATING STAGES			
NTERING AIR TEMPERATURE (DEG DB)			
UPPLY AIR (CFM)			
INIMUM OUTSIDE AIR (CFM)			
XT. STATIC PRESSURE ("w.g)			
RIVE TYPE	DIRECT	DIRECT	DIRECT
AXIMUM OPERATING WEIGHT (LBS)	750	1500	750
OLTS/PHASE/HZ	460/3/60	460/3/60	460/3/60
NIT MCA	9	28	9

15

CARRIER

48GCD04

40

AAON


15

CARRIER

48GCD04

UNIT HEATER SCHEDULE	
MARK	H-1 THRU H-4
TYPE	SEPARATED COMBUSTION
ENERGY SOURCE	NATURAL GAS
NATURAL GAS INPUT (CFH)	60
MINIMUM COMBUSTION EFF %	83
NUMBER OF STAGES	2
AIR FLOW (CFM)	750
BLOWER MOTOR HP	1/6
VOLTS/PHASE/HZ	115/1/60
MAXIMUM OPERATING WEIGHT (LBS)	100
REFERENCE	REZNOR
	UDAS-60
NOTES	1 THRU 6
1. SCHEDULE CAPACITY SHALL BE FOR 326	7 FT. ELEVATION.

5. PROVIDE CONTROL POWER TRANSFORMER & LOW VOLTAGE REMOTE T'STAT. 6. INSTALL UNIT HEATERS AS PER MANUFACTURER'S INSTRUCTIONS.



Breckenridge

architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

PROJECT NO: 23.21.00

JUNE 2024

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



MECHANICAL ✓ ENGINEERING, L.L.C. 5447 East Fifth Street # 112 Tucson, Arizona 85711

520/327-7611 520/327-0432 Designers Mech: MQ Plumb: KGW Project #: 24-21

#### I.I QUALITY ASSURANCE

- A. DESIGN, FURNISH, AND INSTALL COMPLETE AUTOMATIC WET-PIPE FIRE SPRINKLER SYSTEMS IN ALL AREAS OF NEW CONSTRUCTION AS INDICATED IN THE DRAWINGS
- B. THE FIRE SPRINKLER SYSTEMS SHALL INCLUDE ALL ITMES OF A MINOR NATURE NECESSARY TO COMPLETE THE INSTALLATION
- C. THE DESIGN SHALL BE BASED ON HYDRAULIC CALCULATIONS FOR THE HAZARD OCCUPANCIES NOTED ON THE DRAWINGS OR AS DETERMINED BY LOCAL AUTHORITIES. THE HYDRAULIC CALCULATIONS SHALL PROVIDE A MINIMUM OF 5PSI OR 10% (WHICHEVER IS GREATER) SAFETY 2.2 ACCEPTABLE MANUFACTURERS MARGIN BETWEEN THE SYSTEM DEMAND AND THE AVAILABLE WATER SUPPLY.
- D. ANY ITEM SUCH AS COVERAGE OF THE BUILDING, PIPE SIZES, HEAD SPACING, AND OTHER REQUIREMENTS OF THE AUTHORITIES HAVING JURISDICTION SHALL BE INCLUDED. WHETHER SPECIFICALLY SHOWN ON THE DRAWINGS OR NOT.

#### PART 2 - PRODUCTS

#### 2.1 DESIGN INTENT

- A. MATERIALS AND EQUIPMENT SHALL BE UL LISTED FOR USE IN FIRE PROTECTION OR SHALL CONFORM TO THE REQUIREMENTS OF FM GLOBAL FOR SYSTEMS OF THE TYPE INDICATED. THE CONTRACTOR SHALL SUBMIT PROOF THAT THE ITEMS FURNISHED UNDER THIS SPECIFICATION CONFORM TO SUCH REQUIREMENTS. LISTING IN THE FM APPROVAL GUIDE WILL BE ACCEPTABLE EVIDENCE THAT THE ITEMS MEET THIS REQUIREMENT
- B. ALL MATERIALS, EQUIPMENT, AND SYSTEM COMPONENTS SHALL BE NEW AND INSTALLED IN ACCORDANCE WITH THEIR LISTING AND MANUFACTURERS RECOMMENDATIONS.

- C. THE NAMING OF MANUFACTURERS IN THESE SPECIFICATIONS SHALL NOT BE CONSTRUED AS ELIMINATING THE MATERIALS, PRODUCTS OR SERVICES OF OTHER MANUFACTURERS AND SUPPLIERS PROVIDING APPROVED EQUIVALENT ITEMS.
- D. THE DIMENSIONS AND RATINGS OF EQUIPMENT HEREIN SPECIFIED, OR INDICATED ON DRAWINGS, ARE INTENDED TO ESTABLISH THE D. DESIRED OUTLINES AND CHARACTERISTICS OF PERMITTED TO ALLOW MANUFACTURERS EQUIPMENT ACCOMMODATION. DEVIATIONS OF PHYSICAL DIMENSIONS OF EQUIPMENT, WHICH IMPACT UPON SPACE ALLOCATED TO WORK AREAS OF OTHER EQUIPMENT SHALL NOT BE PERMITTED.
- A. SPRINKLER HEADS AND ACCESSORIES:
- VICTAULIC TYCO
- RELIABLE VIKING
- GROOVED FITTINGS
- TYCO
- VIKING
- VICTAULIC

#### 2.3 SPRINKLER HEADS

NEW 6" FIRE RISER, FDC, & 6" ELEC BELL—

6" C900/

NEW 6" FIRE PROTECTION UG-

- A. INSTALL ALL SPRINKLERS IN ACCORDANCE WITH THEIR I ISTING AND WITH THE DEFLECTOR PARALLEL TO THE CEILING OR ROOF.
- B. MAINTAIN CLEARANCES BETWEEN THE SPRINKLER DEFLECTOR AND OTHER OBSTRUCTIONS IN ACCORDANCE WITH NFPA 13 FOR EACH SPRINKLER TYPE (STANDARD SPRAY, ESFR, ETC).

- C. IN AREAS WITH SUSPENDED, GYPSUM BOARD, OR FINISHED CEILINGS, RECESSED PENDENT TYPE GLASS BULB SPRINKLER HEADS WITH SATIN CHROME FINISH INCLUDING TWO-PIECE ADJUSTIBLE ESCUTCHEONS WITH MATCHING FINISH SHALL BE PROVIDED. LOCATE HEADS 12" FROM A CEILING "T" ON 3 SIDES OR IN THE
- CENTER OF 2 X 4 CEILING TILES. SPRINKLERS IN EXPOSED CONSTRUCTION SHALL BE BRASS UPRIGHT OR PENDENT TYPE.
- SUCH EQUIPMENT. MINOR DEVIATIONS WILL BE E. SPRINKLERS IN AREAS SUBJECT TO FREEZING TO BE DRY-PENDENT OF THE APPROPRIATE TYPE FOR THE HAZARD (STANDARD SPRAY, ESFR, ETC). DRY BARREL SPRINKLERS IN FREEZING AREAS SHALL BE SEALED IN ACCORDANCE WITH NFPA 13 REQUIREMENTS AND MANUFACTURER RECOMMENDATIONS USING EITHER A RUBBER BOOT ASSEMBLY OR APPROVED SEALANT IN THE PENETRATION. BARREL LENGTH SHALL BE SELECTED TO PREVENT FREEZING IN THE WET PIPE SPRINKLER SYSTEM ABOVE.
  - 2.4 PIPE, FITTINGS AND HANGERS
  - A. OVERHEAD SPRINKLER PIPING SHALL BE STEEL TYPE APPROVED FOR FIRE SPRINKLER SERVICES IN NFPA 13 AND MANUFACTURED TO ASTM A53, AI35 OR A795. ALL THREADED PIPE SHALL BE SCHEDULE 40.
  - WET PIPE SPRINKLER PIPING SHALL NOT BE INSTALLED IN AREAS SUBJECT TO FREEZING, INSTALL PIPING ABOVE FREEZERS/COOLERS
  - AND UTILIZE DRY-PENDENT SPRINKLERS. C. BOLTED, GROOVED TYPE COUPLINGS AND FITTINGS MAY BE USED.
  - D. SECTIONS OF BRANCH LINES, CROSS MAINS, OR RISERS MAY BE WELDED SUBJECT TO LIMITATIONS AS OUTLINED IN NFPA 13.
  - E. USE OF MECHANICAL TEE FITTINGS WILL NOT BE PERMITTED AS PART OF NEW CONSTRUCTION WORK.
  - F. PLAIN END FITTING SHALL NOT BE USED.
  - G. EXCEPT AS PERMITTED BY NFPA 13, THREADED BUSHINGS SHALL NOT BE USED.

- PART 3 EXECUTION
- 3.1 INSTALLATION
- THE FIRE PROTECTION SYSTEM SHALL BE DESIGNED, FABRICATED, AND INSTALLED BY A FIRE SPRINKLER CONTRACTOR LICENSED IN THE STATE OF NORTH CAROLINA AND EXPERIENCED IN THIS TYPE OF SYSTEM DESIGN AND INSTALLATION WITH A MINIMUM FIVE (5) YEARS EXPERIENCE.
- SPRINKLER HEAD LOCATIONS SHALL BE COORDINATED WITH LIGHT FIXTURES AND HVAC IN AREAS WITH CEILINGS. UNLESS NOTED OTHERWISE, PRIORITY OF LOCATION IS GIVEN TO LIGHT FIXTURES AND HVAC
- CAREFULLY OBSERVE OBSTRUCTION RULES FOR SPRINKLERS AND PROVIDE ADDITIONAL SPRINKLERS WHERE REQUIRED UNDER OBSTRUCTIONS.
- CUTTING OF STRUCTURAL MEMBERS FOR THE PASSAGE OF SPRINKLER PIPING OR FOR PIPE HANGER FASTENINGS WILL NOT BE PERMITTED WITHOUT THE ARCHITECT'S AND STRUCTURAL 3.2 FINAL SUBMITTAL ENGINEER'S APPROVAL
- E. ALL HANGERS, HANGER SPACING TO MEET NFPA 13 REQUIREMENTS.
- SCHEDULE 40 AND/OR THIN WALL PIPE OF A F. THE FIRE PROTECTION CONTRACTOR SHALL GUARANTEE TO REPAIR OR REPLACE ANY DEFECT IN MATERIAL, EQUIPMENT, OR WORKMANSHIP FOR A PERIOD OF ONE (I) YEAR BEGINNING WITH THE DATE OF FINAL ACCEPTANCE BY THE ARCHITECT. SUCH DATE WILL BE ESTABLISHED BY WRITTEN COMMUNICATOIN OF ARCHITECT
  - G. THE FIRE PROTECTION CONTRACTOR SHALL BE RESPONSIBLE DURING THE DESIGN, INSTALLATION, TESTING, AND GUARANTEE PERIODS FOR ANY DAMAGE CAUSED BY THE FIRE PROTECTION CONTRACTOR'S WORK, MATERIALS, OR EQUIPMENT.
  - THE FIRE PROTECTION CONTRACTOR SHALL PROVIDE EMERGENCY REPAIR SERVICE FOR THE SPRINKLER SYSTEM WITHIN FOUR (4) HOURS OF A REQUEST FOR SUCH SERVICE BY THE OWNER DURING THE WARRANTY PERIOD. THIS SERVICE SHALL BE AVAILABLE ON A 24-HOUR PER DAY, 7-DAY PER WEEK BASIS.

#### 3.2 INSPECTIONS AND TESTING

- A. PERFORM HYDROSTATIC TESTS AS REQUIRED BY NFPA 13. HYDROSTATICALLY TEST PIPING SYSTEM AT THE GREATER OF 200PSI OR 50PSI ABOVE MAXIMUM SYSTEM PRESSURE FOR NOT LESS THAN TWO (2) HOURS. UPON COMPLETION OF THE TEST AND WHEN SATISFACTORY RESULTS HAVE BEEN OBTAINED. CERTIFY IN WRITING THAT ALL REQUIRED TESTS HAVE BEEN PERFORMED AND THAT APPROVAL OF THE SYSTEM HAS BEEN OBTAINED FROM THE AHJS.
- ALL TESTS SHALL BE PERFORMED IN THE PRESENCE OF THE LOCAL AHJ. GENERAL CONTRACTOR, ARCHITECTS REPRESENTATIVE, AND OWNER'S REPRESENTATIVE.
- C. THE FIRE PROTECTION CONTRACTOR SHALL FURNISH THE ARCHITECT WITH ONE ELECTRONIC AND ONE HARD COPY OF ALL PERTINENT TEST CERTIFICATES.

- A. FURNISH 2 BOUND COPIES OF COMPLETE INSTRUCTIONS, INCLUDING CATALOG CUTS, DIAGRAMS, DRAWINGS, AND OTHER DESCRIPTIVE DATA COVERING THE PROPER TESTING, OPERATION, AND MAINTENANCE OF EACH TYPE OF SYSTEM INSTALLED, AND THE NECESSARY INFORMATION FOR ORDERING REPLACEMENT PARTS.
- B. FURNISH COMPLETE AS-BUILD DRAWINGS SHOWING ALL CHANGES MADE IN THE FIELD. BASED ON A RED-LINED SET MAINTAINED IN THE FIELD DURING CONSTRUCTION.

FIRE FLOWS: IFC BIO3.

THE FIRE CODE OFFICIAL IS AUTHORIZED TO REDUCE THE FIRE-FLOW REQUIREMENTS FOR SMALL COMMUNITIES WHERE DEVELOPMENT OF FULL FIRE-FLOW REQUIREMENTS IS IMPRACTICAL.

TUBAC FIRE DEPARTMENT ALLOWS THE USE OF NFPA 1142 TO DETERMINE FIRE FLOWS.

NFPA 1142: WATER SUPPLIES FOR SUBURBAN AND RURAL FIRE FIGHTING

- CHAPTER 4: CALCULATING MINIMUM WATER SUPPLIES (I) OCCUPANCY HAZARD:
- (2) Type of Construction:
- (3) STRUCTURE DIMENSIONS:
- (4) EXPOSURES:

#### 4.3: STRUCTURES WITH EXPOSURE HAZARDS

WS: MINIMUM WATER SUPPLY IN GAL VS: TOTAL VOLUME OF STRUCTURE IN CU.FT OHC: OCCUPANCY HAZARD CLASSIFICATION NUMBER (CHAPTER 5) CC: CONSTRUCTION CLASSIFICATION NUMBER (CHAPTER 6)

NFPA 1142 TABLE 4.6.1 DICTATES THAT, FOR WATER TANKS OVER 20,000GAL, THE WATER DELIVERY RATE SHALL BE A MINIMUM OF 1,000 GPM.

WHERE THE BUILDING IS PROTECTED BY AN AUTOMATIC SPRINKLER SYSTEM, THE AHJ IS PERMITTED TO REDUCE THE MINIMUM REQUIRED FIRE FLOWS AS INDICATED IN IEC SECTION BIO3.1 AND NEPA 1142 APPENDIX E.

NFPA 1142 SECTION 4.4 (WITH APPENDIX MATERIAL) ALLOWS THE AHJ TO REDUCE THE WATER DELIVERY RATE TO A MINIMUM FLOW OF 600 GPM WHEN THE BUILDING IS PROTECTED BY AN NFPA 13 SPRINKLER SYSTEM USING QUICK-RESPONSE SPRINKLERS THROUGHOUT THE BUILDING. THE AHJ HAS CONFIRMED THAT A FIRE FLOW OF 600 GPM IS ACCEPTABLE ON THIS PROJECT AS LONG AS QUICK-RESPONSE SPRINKLERS ARE USED THROUGHOUT THE BUILDING IN ACCORDANCE WITH SECITON A4.4.

TUBAC FIRE STATION #1 4.3: STRUCTURES WITH EXPOSURE HAZARDS BUILDING AREA: 9,632 SQ.FT.

VS = 243,000 (ESTIMATE)OHC = 7 (CHAPTER 5)CC = 1.5 (CHAPTER 6)

WS = 78,107 GAL (MINIMUM REQUIRED WATER SUPPLY VOLUME) FLOW RATE = 600 GPM (NFPA 1142 A4.4 QUICK RESPONSE REDUCTION) EPCOR WATER SUPPLY MEETS THE MINIMUM FLOW & VOLUME REQUIREMENTS

AUTOMATIC FIRE SPRINKLER MINIMUM WATER SUPPLY ESTIMATE: REFER TO NFPA 13 FIGURE II.2.3.1.1 AND TABLE II.2.3.1.2

NFPA 13: LIGHT HAZARD (DORM & OFFICE AREAS) DENSITY: 0.10 GPM/SQ.FT AREA: 1,500 SQ.FT SPRINKLER OVERFLOWS: 30%

SPRINKLER SYSTEM DEMAND: 195 GPM EXTERIOR HOSE STREAM: 100 GPM

MINIMUM TOTAL WATER FLOW: 295 GPM MINIMUM WATER SUPPLY DURATION: 60 MINUTES

NFPA 13: ORDINARY GROUP I HAZARD (APPARATUS BAY) DENSITY: 0.15 GPM/SQ.FT AREA: 1,500 SQ.FT SPRINKLER OVERFLOWS: 40%

SPRINKLER SYSTEM DEMAND: 315 GPM EXTERIOR HOSE STREAM: 250 GPM

MINIMUM TOTAL WATER FLOW: 565 GPM MINIMUM WATER SUPPLY DURATION: 90 MINUTES

AUTOMATIC FIRE SPRINKLER MINIMUM PRESSURE ESTIMATE: NFPA 13: ORDINARY HAZARD (APPARATUS BAY) K-FACTOR: 8.0 SPRINKLER AREA: 130 SQ.FT DENSITY: 0.15 GPM/SQ.FT

END HEAD PRESSURE: 7 PSI ELEVATION LOSS: 12 PSI BACKFLOW PREVENTER: 4 PSI FRICTION LOSSES: 6 PSI [LARGE DIAMETER PIPING IS REQUIRED] MARGIN OF SAFETY: 5 PSI (OR 10%, WHICHEVER IS GREATER)

REQUIRED PRESSURE AT SOURCE: 34 PSI @ 565 GPM



**MECHANICAL** ENGINEERING, L.L.C. 5447 East Fifth Street # 112 Tucson, Arizona 85711

520/327-043 Designers Mech: MQ Plumb: KGW Project #: 2

architects planners 1735 e ft. lowell rd. #12 tucson arizona 85719


5 2 0 . 8 8 2 . 9 9 4 4

85646

9

Station

Tubac



23.21.00

JULY 31, 2024

# DATE DESCRPITION

CHECKED BY: CDA THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS O BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR


ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. AN' IAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF


HIS DRAWING, WHETHER IN WHOLE OR IN PART, IS

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &



Fire Protection Site Plan





#### FIRE SPRINKLER GENERAL NOTES

- ALL WORK SHALL COMPLY WITH NFPA 13 (2016), NFPA 1142 (2017), AND ALL OTHER REFERENCED STANDARDS PER THE PLANS, SPECIFICATIONS, AND OWNER AND AHJ REQUIREMENTS. AND SHALL BE INSTALLED IN ACCORDANCE WITH ALL CODES, LAWS, RULES, AND REGULATIONS OF ALL NATIONAL, STATE, COUNTY, AND LOCAL AUTHORITIES HAVING JURISDICTION (AHJ) OVER THE PREMISES. IN CASE OF A CONFLICT BETWEEN THESE PLANS AND ANY REQUIREMENTS OF THE AFOREMENTIONED CODES AND AUTHORITIES, THE MOST STRINGENT SHALL APPLY
- SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL BY THE OWNER CONCURRENT TO SUBMISSION TO THE AHJ. ALL APPROVALS SHALL BE OBTAINED PRIOR TO INSTALLATION.
- SECURE AND PAY FOR ALL PERMITS, INSPECTIONS, AND CERTIFICATES REQUIRED BY THE FOREGOING AUTHORITIES. INSPECTIONS SHALL BE CONDUCTED IN THE PRESENCE OF THE AHJ. SUBMIT SIGNED OVERHEAD AND UNDERGROUND TEST CERTIFICATES AS EVIDENCE OF SATISFACTORY TESTS.
- NO PIPE SHALL BE CONNECTED TO THE ABOVEGROUND LINE UNTIL AN UNDERGROUND FLUSH HAS BEEN COMPLETED, INCLUDING LEAD-IN PIPING, AS REQUIRED BY NFPA I3 AND NFPA 20 AS EVIDENCED BY A SIGNED UNDERGROUND TEST CERTIFICATE.
- THE FIRE DEPARTMENT CONNECTION (FDC) SHALL CONSIST OF NO FEWER THAN TWO 2½" INLETS AND SHALL BE INSTALLED WITHIN 150' OF A FIRE HYDRANT OR PER LOCAL AHJ REQUIREMENTS.
- F. COORDINATE ALL SPRINKLER HEAD AND PIPING LOCATIONS WITH STRUCTURE, CEILINGS, MECHANICAL DUCTWORK & PIPING, ELECTRICAL & LIGHTING, AND WORK OF OTHER TRADES. ADDITIONAL OFFSETS REQUIRED FOR COORDINATION PURPOSES SHALL BE INCLUDED AT NO ADDITIONAL COST TO THE OWNER.
- G. ALL SPRINKLER SYSTEM COMPONENTS SHALL BE UL LISTED OR FM APPROVED FOR FIRE PROTECTION USE.
- H. VERIFY ALL EXISTING CONDITIONS BEFORE BIDDING AND INCLUDE ALL REQUIRED ITEMS FOR A COMPLETE AND OPERABLE CODE COMPLIANT SYSTEM READY FOR OWNER USE, WHETHER INDICATED ON THE DRAWINGS OR NOT. OFFSETS MAY BE REQUIRED FOR COORDINATION WITH OTHER TRADES OR UNFORSEEN FIELD CONDITIONS AND SHALL BE ACCOUNTED FOR IN CONTRACTOR'S BID.
- PIPING AND VALVE CONFIGURATIONS INDICATED ARE SCHEMATIC IN NATURE AND ARE TO BE USED FOR REFERENCE ONLY. ACTUAL CONFIGURATION TO BE DETERMINED BY THE CONTRACTOR TO MEET THE REFERENCED STANDARDS AND AHJ REQUIREMENTS AS REFLECTED ON THE CONTRACTOR'S SHOP DRAWINGS.
- ALL SPRINKLER SYSTEM DRAINS AND INSPECTOR'S TESTS SHALL BE PIPED TO THE BUILDING EXTERIOR. COORDINATE WITH ARCHITECT FOR ACCEPTABLE LOCATIONS FOR EXTERIOR DRAIN PENETRATIONS.
- .. ALL SPRINKLERS TO BE QUICK RESPONSE TO QUALIFY FOR A REDUCTION IN WATERS SUPPLY FOR MANUAL FIRE FIGHTING AS ALLOWED BY NFPA 1142 A4.4.

#### FIRE PROTECTION SYSTEM HAZARDS AND CRITERIA

- PROVIDE HYDRAULICALLY CALCULATED DESIGN FOR FIRE SPRINKLER SYSTEM TO FULLY COVER THE ENTIRE BUILDING. THE SYSTEM SHALL BE DESIGNED FOR THE HAZARD CLASSIFICATIONS NOTED BELOW, PER NFPA 13, NFPA 20, NFPA 1142 AND ANY OTHER REQUIREMENTS DESCRIBED HEREIN. ALSO REFER TO (AND COMPLY WITH) ALL REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
- A. OFFICES, CONFERENCE ROOMS, RESTROOMS, DORMS, AND SIMILAR AREAS: LIGHT HAZARD, 0.1/1500 [GPM/SQ.FT] WITH 100 GPM HOSE STREAM.
- B. STORAGE CLOSETS, MECH ROOM, APPARATUS BAY, AND SIMILAR AREAS:
  ORDINARY HAZARD GROUP 1, 0.15/1500 [GPM/SQ.FT] WITH 250 GPM HOSE STREAM.
- 2. WATER SUPPLY: PROVIDED BY EPCORE (REFER TO FLOW TEST RESULTS IN THE PLAN NOTES ON THIS SHEET)
- 3. AUTHORITIES HAVING JURISDICTION:
  - A. SANTA CRUZ BUILDING DEPARTMENT
- B. TUBAC FIRE DEPARTMENT

#### SCOPE OF WORK

- I. INSTALL ONE NEW WET SPRINKLER SYSTEM COMPLYING WITH ALL SPECIFIED DESIGN DOCUMENTS FOR THE NEW TUBAC FIRE STATION #1.
- 2. PROVIDE A MINIMUM 6" RISER & MAIN. OVERSIZED PIPING [MAINS AND/OR BRANCHLINES] MAY BE REQUIRED TO ACCOMMODATE THE AVAILABLE WATER SUPPLY. ALL PIPE SIZES TO BE DETERMINED BY HYDRAULIC CALCULATIONS.
- 3. PROVIDE AND INSTALL ONE NEW FIRE PUMP IN THE REMOTE PUMP HOUSE COMPLYING WILL ALL SPECIFIED DESIGN DOCUMENTS.
- 4. SYSTEM TYPE: WET PIPE, HYDRAULICALLY CALCULATED DESIGN, REFER TO FIRE PROTECTION NOTES ON THIS PAGE FOR HAZARD CLASSIFICATION AND DESIGN REQUIREMENTS.




 Brockenridge

Frank Parker

Transfer of the second of the

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Fire Station #1



PROJECT NO: 23.21.00

JULY 31, 2024

REVISION SCHEDULE:
# DATE DESCRPITION ISSUED TO

DRAWN BY: JCG

CHECKED BY: CDA

HIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION
URPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF
RECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR

RCHITECTURAL DRAWINGS AND DESIGNS ARE AFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY NAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION ( HIS DRAWING, WHETHER IN WHOLE OR IN PART, IS

CONSENT.

CONSENT.

CONSENT.

CONSENT.

CONSENT.

Fire Protection Water Supply

#### **ABBREVIATIONS**

AMERICANS WITH DISABILITES ACT (1990) ADA AFF ABOVE FINISHED FLOOR ABOVE FINISHED GRADE AMPERES INTERRUPTING CAPACITY **AMP** AMPACITY ALTERNATING CURRENT

AMERICAN WIRE GAUGE NUMBER OF CONDUCTORS CONDUIT

**EWC** ELECTRIC WATER COOLER **EMC ELECTRICAL METALLIC TUBING** 

**EXISTING** 

**FUSE** FMC FLEXIBLE METAL CONDUIT

GFI GROUND FAULT INTERRUPTER GROUND FAULT CIRCUIT INTERRUPTER

G,GND GROUND HORSEPOWER KILOWATTS

kVA **KILOVOLT AMPERES** LFMC LIQUID TIGHT FLEXIBLE METAL CONDUIT

MAIN CIRCUIT BREAKER MCP MOTOR CIRCUIT PROTECTOR MAIN LUGS ONLY

MOTOR MOTOR CONTROL CENTER

MANUFACTURER NATIONAL ELECTRICAL CODE

NEMA NATIONAL MANUFACTURERS ASSOCIATION

N, NEU NEUTRAL NEW PHASE

PAIR POLYVINYL CHLORIDE

REMARK RGS RIGID GALVANIZED STEEL

STRANDED BARE COPPER SDBC SHLD,SH SHIELDED **SOLID NEUTRAL** 

SPARE **TYPICAL** 

UNDERWRITERS LABORATORIES UPS UNINTERRUPTABLE POWER SOURCE UNLESS OTHERWISE NOTED

**VOLTS** WATTS WEATHERPROOF TRANSFORMER

#### **SYMBOLS**

#### **LIGHT FIXTURES**

WALL MOUNTED LUMINAIRE

RECESSED OR SURFACE MOUNTED LUMINAIRE

LINEAR SUSPENDED LUMINAIRE

RECESSED 2' x 2' LUMINAIRE

RECESSED 1' x 4' LUMINAIRE RECESSED 2' x 4' LUMINAIRE

SURFACE MOUNTED 2' x 2' LUMINAIRE

0 SURFACE MOUNTED 1' x 4' LUMINAIRE 0

Ċ SURFACE MOUNTED 1' x 4' LUMINAIRE

SURFACE MOUNTED 2' x 4' LUMINAIRE

STRIP LIGHT LUMINAIRE, SURFACE OR PENDANT

#### LIGHT FIXTURES W/ BATTERY BACK UP

WALL MOUNTED LUMINAIRE

RECESSED OR SURFACE MOUNTED LUMINAIRE

LINEAR SUSPENDED LUMINAIRE

RECESSED 2' x 2' LUMINAIRE

RECESSED 1' x 4' LUMINAIRE RECESSED 2' x 4' LUMINAIRE

SURFACE MOUNTED 2' x 2' LUMINAIRE

SURFACE MOUNTED 1' x 4' LUMINAIRE


SURFACE MOUNTED 2' x 4' LUMINAIRE SURFACE MOUNTED 1' x 4' LUMINAIRE

STRIP LIGHT LUMINAIRE, SURFACE OR PENDANT

UNIVERSALLY MOUNTED EXIT SIGN WITH ARROWS AND SHADING AS INDICATED

2-HEAD EMERGENCY BATTERY PACK LIGHT

#### LIGHT FIXTURE DESIGNATION



#### **LIGHTING CONTROL**

SINGLE POLE SWITCH, 20 AMPERE OR LOW VOLTAGE TYPE. MAX. HEIGHT = 42" TO CENTER LINE UON.

THREE WAY SWTICH, 20 AMPERE

DIMMER SWITCH AS INDICATED ON DRAWINGS

WALL MOUNTED OCCUPANCY SENSOR SWITCH

#### **CONSTRUCTION PHASE LEGEND**

EXISTING TO BE REMOVED/REPLACED **EXISTING TO REMAIN** 

#### **POWER DEVICES**

JUNCTION BOX

DUPLEX RECEPTACLE OUTLET, NEMA 5-20R, MOUNTED 18" AFF

DUPLEX RECEPTACLE OUTLET, NEMA 5-20R, ABOVE 42" COUNTER GROUND FAULT CIRCUIT INTERRUPTER RECEPTACLE 20

AMPERE FEED THROUGH TYPE QUADRAPLEX - TWO DUPLEX RECEPTACLE UNDER A TWO

GANG RING, MOUNTED 18" AFF

TOGGLE SWITCH TYPE MANUAL MOTOR STARTER

SPECIAL PURPOSE RECEPTACLE AS NOTED ON PLANS.

EXTERNALLY OPERATED NON-FUSED DISCONNECT SWITCH. 30A/3P SIZE AND PHASE AS INDICATED. 3R INDICATES NEMA 3R TYPE ENCLOSURE, NO NUMBER INDICATES NEMA 1 TYPE ENCLOSURE.

EXTERNALLY OPERATED FUSED DISCONNECT SWITCH. SIZE, POLES, FUSE SIZE & QUANTITY AS INDICATED. 3R INDICATES (3) 30A FU NEMA 3R TYPE ENCLOSURE, NO NUMBER INDICATES NEMA 1 TYPE ENCLOSURE.

COMBINATION MOTOR STARTER FUSED DISCONNECT. SIZE, FUSE SIZE, PHASE AND QUANTITY AS INDICATED ON PLANS.

M = MOTOR OR G = GENERATOR

#### **WIRING SYMBOLS**

HOMERUN TO PANEL. 'LP' INDICATES PANEL DESIGNATION. 'LP'-1,3,5 1,3,5 INDICATES CIRCUIT BREAKER NUMBER **NEW CONDUIT** 

UNDERGROUND CONDUIT

FLEXIBLE CONDUIT NUMBER OF SLASHES INDICATE NUMBER OF WIRES

(WHEN MORE THAN TWO). PROVIDE GROUND WIRE IN ALL CONDUITS (SIZE GROUND PER NEC 250.122, U.O.N.); GROUNDS ARE NOT SHOWN BY SLASHES. SLASHES WHERE SHOWN ARE FOR CONVENIENCE OF THE

CONTRACTOR ONLY; PROVIDE NUMBER OF CONDUCTORS AS REQUIRED BY CIRCUIT FUNCTION.

#### **SPECIAL SYSTEMS DEVICES**

TELEPHONE/DATA SYSTEM OUTLET. FLUSH 4S BOX WITH 2 GANG RING & BLANK COVER AND 3/4" C. STUBBED OUT ABOVE ACCESSIBLE CEILING WITH PLASTIC BUSHING, OR AS NOTED.

#### **FIRE ALARM SYMBOLS**



COMBINATION SMOKE & CO ALARM, BRK SERIES #SMIC0110. PROVIDE INTERCONNECT WIRING BETWEEN SMOKE/CO ALARM AS REQUIRED.



Plans

Breckenridge


architects

planners

1735 e ft. lowell rd. #12

tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4



PROJECT NO: 23.21.00

**JUNE 2024** 


REVISION SCHEDULE:

DRAWN BY: NT

CHECKED BY: EG THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &





2051 W. SUNSET RD. SUITE NO. 101

TEL. (520) 293-1488 FAX. (520) 293-8349 M3ENG.COM

#### **GENERAL NOTES:**

- A. MAINTAIN ALL NEC REQUIRED WORKING CLEARANCES FOR ALL ELECTRIC EQUIPMENT.
- B. ALL WIRING SHALL BE (2) #12 AWG, #12 AWG GND. (U.O.N.).
- C. ALL BRANCH CIRCUITS TO HAVE DEDICATED NEUTRALS. SHARED NEUTRALS NOT ALLOWED (NEC ARTICLE 200.4).
- ). ALL LIGHT FIXTURE(S) SHOWN WITH HALF SHADE (INTEGRAL BATTERY PACK) REQUIRES AN UNSWITCHED CIRCUIT.
- LOW-VOLTAGE WIRING BETWEEN LOW-VOLTAGE CONTROL DEVICE & LIGHT FIXTURE(S) ARE NOT SHOWN ON THIS DRAWING. REFER TO CONTROL DIAGRAMS, FOR ADDITIONAL INFORMATION.




tucson arizona 85719

5 2 0 . 8 8 2 . 9 9 4 4

#### **#** KEYNOTES:

J-BOX FOR POWER CONNECTION OF MODULAR FURNITURE LIGHT FIXTURE. COORDINATE EXACT MOUNTING LOCATION WITH MODULAR PROVIDER PRIOR TO ROUGH-IN.

# ubac Fire Station #1



PROJECT NO: 23.21.00

JUNE 2024

REVISION SCHEDULE:
# DATE DESCRPITION ISSUED 1

DRAWN BY: NT CHECKED BY: EG

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



SCALE: 1/8" = 1'-0"



2051 W. SUNSET RD.
SUITE NO. 101
TUCSON, ARIZONA 85704
TEL. (520) 293-1488
FAX. (520) 293-8349
M3ENG.COM

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS &



#### LIGHT FIXTURE SCHEDULE TYPE MANUFACTURER/ MAX **FINISH REMARKS** MOUNTING **VOLTS LAMP** DESCRIPTION **CATALOG NUMBER** LED LITHONIA 2' x 4' LED VOLUMETRIC FIXTURE **MVOLT** STANDARD 39 VA (5169 LUMENS) 2BLT4-48L-ADP-EZ1-LP840 L2 LITHONIA 2' x 4' LED VOLUMETRIC FIXTURE MVOLT STANDARD 32 VA (4312 LUMENS) 2BLT4-40L-ADP-EZ1-LP840 STANDARD 23 VA **MVOLT** 4' LED INDUSTRIAL STRIP **SURFACE** (3000 LUMENS) CLX-L48-3000LM-SEF-FDL-MVOLT-EZ1-40K-80CRI LED **BRUSHED WALL ABOVE MVOLT** 2' VANITY LED FIXTURE (1302 LUMENS) NICKEL MIRROR FMVTRL-24IN-MVOLT-30K-90CRI-BN LED STANDARD PENDANT 166 VA LED LINEAR HIGH BAY IBE-L24-22000LM-L/LENS-MD-MVOLT-GZ10-40K-80CRI-DWH (22,859 LUMENS) LED LITHONIA STANDARD 2' x 2' LED VOLUMETRIC FIXTURE **MVOLT** GRID 32 VA 2BLT2-40L-ADP-EZ1-LP840 (4144 LUMENS) LITHONIA **UNDER** 120V 30" UNDERCABINET FIXTURE LED WHITE 14 VA CABINET UPS30-30K-90CRI-WH **UNDER** LITHONIA 120V LED 6.5 VA 14" UNDERCABINET FIXTURE WHITE UPS14-30K-90CRI-WH **CABINET** LED 6" LED DOWNLIGHT **MVOLT** RECESSED CLEAR 23 VA (2006 LUMENS) LDN6-40/20-L06-AR-LSS-MVOLT-GZ10 LED LITHONIA RECESSED **MVOLT** CLEAR 4" LED DOWNLIGHT 13 VA (1045 LUMENS) LDN4-40/10-L04-AR-LSS-MVOLT-GZ10 PROVIDE IP65 RATED. WALL MOUNT @ DARK LITHONIA LIGHTING **MVOLT** LED WALL SCONCE (3887 LUMENS) 11'-0" AFF **BRONZE** PROVIDE FULL CUTOFF DSXW1LED-20C-530-30K-T2M-MVOLT-DDBXD LED WALL MOUNT VISA LIGHTING LED WALL READING LIGHT WHITE 3 VA (190 LUMENS) CB1800-L35K-L-MVOLT-TOUCHDIM-TW9016 ABOVE BED IN CLINIC SIDE, INTEGRAL BATTERY WALL/CEILING WHITE LED EXIT SIGN **MVOLT** LED LQM-S-G-120/277-ELN-SD PACKS SHALL BE PROVIDED


#### NOTES:

1. FIXTURE SCHEDULE INDICATES GENERAL DESCRIPTION OF LIGHTING FIXTURES AND MANUFACTURERS CATALOG NUMBERS. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO DETERMINE THE CORRECT CEILING CONFIGURATION AND PROVIDE THE FIXTURES WITH ALL NECESSARY TRIMS AND MOUNTING HARDWARE SO THAT BOTH THE CEILING SYSTEM AND THE FIXTURE CONSTRUCTION

2. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO VERIFY EXACT LOCATIONS OF ALL LIGHTING FIXTURES AND TYPE OF CEILING WITH THE ARCHITECTURAL REFLECTED CEILING PLAN PRIOR TO ANY WORK. REFER TO ARCHITECTURAL ELEVATION DRAWINGS FOR MOUNTING HEIGHTS OF WALL MOUNTED FIXTURES.

3. PROVIDE NUMBER OF FIXTURES AS INDICATED ON PLAN. PROVIDE ALL FITTINGS AND ACCESSORIES REQUIRED FOR A COMPLETE SYSTEM.

4. PROVIDE INTEGRAL. 1400 LUMEN. 90 MINUTE BATTERY BACK-UP FOR LIGHTING FIXTURES AS INDICATED ON PLANS.



N.T.S.

#### **TYPICAL WALL OCCUPANCY SENSOR CONTROL BLOCK DIAGRAM**

N.T.S.

TYPICAL LOW-VOLTAGE LIGHTING **CONTROL BLOCK DIAGRAM** 

2

#### LOW-VOLTAGE SYSTEM SYMBOLS LEGEND

LOW-VOLTAGE 360 DEGREE CEILING MOUNT SENSOR; MICROPHONIC-DUAL TECHNOLOGY, 12 TO 24 VOLT VDC/VAC. DEVICE SHALL CONTROL LIGHTING WITH-IN THE SPACE (U.O.N). "a,b,c" INDICATES LIGHTING ZONE(S) CONTROLLED WITHIN THE SPACE (U.O.N). SENSOR SHALL BE SET TO AUTO 'ON', AUTO 'OFF'.

- LOW-VOLTAGE DUAL TECHNOLOGY WALL SENSOR, RAISE/LOWER DIM CONTROL, 12 TO 24 VOLT VDC/VAC. (SENSOR SHALL BE SET MANUAL 'ON', AUTO 'OFF'). DEVICE SHALL CONTROL LIGHTING WITH-IN THE SPACE (U.O.N).
- LOW-VOLTAGE PASSIVE INFRARED WALL SENSOR, 12 TO 24 VOLT VDC/VAC. (SENSOR SHALL BE SET TO MANUAL 'ON', AUTO 'OFF'). IN RESTROOMS, SENSOR SHALL BE SET TO AUTO 'ON', AUTO 'OFF'. DEVICE SHALL CONTROL LIGHTING WITH-IN THE SPACE (U.O.N).
- LOW VOLTAGE PUSH-BUTTON SWITCH, SINGLE POLE, RAISE/LOWER DIMMING. DEVICE SHALL CONTROL LIGHTING WITH-IN THE SPACE (U.O.N).
- LOW VOLTAGE PUSH-BUTTON SWITCH, TWO POLE, RAISE/LOWER DIMMING. "a,b" INDICATES LIGHTING ZONE CONTROLLED WITHIN THE SPACE (U.O.N).
- LOW VOLTAGE PUSH-BUTTON SWITCH, FOUR POLE, RAISE/LOWER DIMMING. "a,b,c.." INDICATES LIGHTING ZONES CONTROLLED WITHIN THE SPACE (U.O.N).
- POWER PACK OF ROOM CONTROLLER AS REQUIRED BY SELECTED PP MANUFACTURER.

#### SYSTEM NOTES

- COORDINATE WIRING DIAGRAM AND INSTALLATION WITH SUPPLIED LOW-VOLTAGE SENSOR. SWITCH MANUFACTURER PRIOR TO ROUGH-IN.
- PROVIDE ALL NECESSARY MOUNTING ACCESSORIES, POWER PACKS, RELAYS, ETC. FOR A FULLY OPERATIONAL SYSTEM.
- SENSORS, POWER PACKS, AND LOW-VOLTAGE SWITCHES SHOWN ON THIS PLAN SHALL BE USED AS A MINIMUM GUIDELINE FOR BID PURPOSES, ACTUAL SENSOR, LOW-VOLTAGE SWITCHES, AND POWER PACK TYPES, LOCATIONS, QUANTITIES AND MOUNTING HEIGHTS MAY VARY, PROVIDE ADDITIONAL DEVICES ETC. AS REQUIRED BY SENSOR MANUFACTURER WITHOUT ADDITIONAL COST TO THE OWNER. COORDINATE RECOMMENDED MOUNTING LOCATION WITH SENSOR MANUFACTURER PRIOR TO ROUGH-IN.
- CONTRACTOR TO PROVIDE FULLY OPERATIONAL FACTORY SYSTEM DRAWINGS TO ENGINEER FOR REVIEW AND APPROVAL. FACTORY SYSTEM DRAWINGS SHALL INCLUDED, BUT NOT LIMITED TO, SENSOR LEGEND, SENSOR AND POWER PACK MODEL TYPES, SENSOR, POWER PACK, AND LOW-VOLTAGE SWITCH LOCATIONS, MOUNTING HEIGHTS, EACH LUMINAIRE CONTROLLED BY EACH SENSOR, SPECIFICATION CUTSHEET, WIRING DIAGRAMS, ETC. QUANTITY OF POWER PACKS, ROOM CONTROLLERS, ETC SHALL BE DETERMINED BY THE SELECTED MANUFACTURER. (1) ZONE SHALL BE CONSIDERED (1) RELAY.
- CONTRACTOR SHALL PERFORM ALL NECESSARY TESTS AND ADJUSTMENTS (SENSITIVITY SETTINGS, TIME DELAY SETTINGS, ETC.) REQUIRED EACH SENSOR FOR OPTIMUM PERFORMANCE. THESE TESTS AND ADJUSTMENTS ARE TO BE SCHEDULED AND PERFORMED UNDER THE SUPERVISION OF SENSOR MANUFACTURER'S FACTORY FIELD SUPERVISOR AT THE EXPENSE OF THE CONTRACTOR. NO ADDITIONAL FEES WILL BE PAID BY THE OWNER. THE CONTRACTOR SHALL ISSUE A TEST REPORT TO THE OWNER/ARCHITECT INDICATING THAT ALL DEVICES ARE WORKING PROPERLY AND MEET ALL FACTORY STANDARDS.
- ACCEPTABLE MANUFACTURERS: - nLIGHT - WATTSTOPPER 'DLM' - COOPER 'GREEN GATE'



M3-PN24015

113

3

4

2

1

7

**POWER PLAN** 

SCALE: 1/8" = 1'-0"

6

#### **GENERAL NOTES:**

- MAINTAIN ALL NEC REQUIRED WORKING CLEARANCES FOR ALL ELECTRIC
- ALL WIRING SHALL BE (2) #12 AWG, #12 AWG GND. (U.O.N.).
- ALL BRANCH CIRCUITS TO HAVE DEDICATED NEUTRALS. SHARED NEUTRALS NOT ALLOWED (NEC ARTICLE 200.4).
- COORDINATE EXACT LOCATION OF DEVICES WITH ARCHITECTURAL ELEVATIONS PRIOR TO ROUGH-IN.
- FURNITURE LAYOUT SUBJECT TO CHANGE. COORDINATE FINAL REQUIREMENTS WITH FURNITURE, MILLWORK AND EQUIPMENT PROVIDERS.
- ALL RECEPTACLES WITH-IN 72 INCHES OF SINKS SHALL BE GFCI.
- ACCESS AND WORKING SPACE OF ALL NEW ELECTRICAL EQUIPMENT SHALL COMPLY WITH ARTICLE 110.26 OF THE NEC. THERE SHALL NOT BE ANY PIPING, DUCTS, LEAK PROTECTION APPARATUS OR OTHER EQUIPMENT FOREIGN TO THE ELECTRICAL INSTALLATION 6'-0" ABOVE THE ELECTRICAL EQUIPMENT PER ARTICLE 110.26(E)(1).

#### **KEYNOTES:**

- COORDINATE RECEPT HEIGHT IN LOCKER WITH ARCHITECT PRIOR TO ROUGH-IN.
- J-BOX FOR CONNECTION OF CORD REEL. COORDINATE EXACT MOUNTING LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.
- DOOR OPENER OPERATOR PROVIDED WITH DOOR OPERATOR. COORDINATE EXACT MOUNTING LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.
- GARAGE DOOR OPENER WITH INTERNAL STARTER. COORDINATE EXACT MOUNTING LOCATION WIH ARCHITECT PRIOR TO ROUGH-IN.
- WALL MOUNT J-BOX FOR CONNECTION OF SYSTEMS FURNITURE. COORDINATE EXACT MOUNTING LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.

#### **EQUIPMENT KEYNOTES:**


- SERVICE ENTRANCE METER & MCB SECTION 'SES-1'.
- DISTRIBUTION SECTION 'DS1'.
- PANEL 'IT'
- PANEL 'P3'.



## architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

# Station FIF **Tubac** 



PROJECT NO: 23.21.00

JUNE 2024

REVISION SCHEDULE:

DRAWN BY: NT

CHECKED BY: EG THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN


COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



2051 W. SUNSET RD. SUITE NO. 101 TUCSON, ARIZONA 85704 TEL. (520) 293-1488 FAX. (520) 293-8349 M3ENG.COM


#### **ENLARGED KITCHEN POWER PLAN**

SCALE: 1/4" = 1'-0"




#### **ENLARGED ELECTRIC RM POWER PLAN**

SCALE: 1/4" = 1'-0"



#### **ENLARGED BREAK RM POWER PLAN**


SCALE: 1/4" = 1'-0"



### **EQUIPMENT KEYNOTES:**

PANEL 'P1'.

**AUTOMATIC TRANSFER SWITCH 'ATS-OS1'** 



**GENERAL NOTES:** 

MAINTAIN ALL NEC REQUIRED WORKING CLEARANCES FOR ALL ELECTRIC

ALL WIRING SHALL BE (2) #12 AWG, #12 AWG GND. (U.O.N.).

NEUTRALS NOT ALLOWED (NEC ARTICLE 200.4).

ELECTRICAL EQUIPMENT PER ARTICLE 110.26(E)(1).

ELEVATIONS PRIOR TO ROUGH-IN.

PROVIDERS.

ALL BRANCH CIRCUITS TO HAVE DEDICATED NEUTRALS. SHARED

COORDINATE EXACT LOCATION OF DEVICES WITH ARCHITECTURAL

FURNITURE LAYOUT SUBJECT TO CHANGE. COORDINATE FINAL REQUIREMENTS WITH FURNITURE, MILLWORK AND EQUIPMENT

ALL RECEPTACLES WITH-IN 72 INCHES OF SINKS SHALL BE GFCI.

ACCESS AND WORKING SPACE OF ALL NEW ELECTRICAL EQUIPMENT


SHALL COMPLY WITH ARTICLE 110.26 OF THE NEC. THERE SHALL NOT BE

ANY PIPING, DUCTS, LEAK PROTECTION APPARATUS OR OTHER EQUIPMENT FOREIGN TO THE ELECTRICAL INSTALLATION 6'-0" ABOVE THE



1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Fire



PROJECT NO: 23.21.00

JUNE 2024

DRAWN BY: NT CHECKED BY: EG

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS






#### **ENLARGED IT/ELEC. RM POWER PLAN**

SCALE: 1/4" = 1'-0"

2051 W. SUNSET RD. SUITE NO. 101 TUCSON, ARIZONA 85704 TEL. (520) 293-1488 FAX. (520) 293-8349 M3ENG.COM

# Tubac Fire Station #1



Preliminary Plans

PROJECT NO: 23.21.00
DATE:

JUNE 2024

REVISION SCHEDULE:
# DATE DESCRPITION ISSUED TO

DRAWN BY: NT CHECKED BY: EG

CHECKED BY: EG

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION
PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF
BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR
DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS





	AUTOMATIC TRANSFER SWITCH SCHEDULE						
MARK AMPERE NO. OF AIC SERVING BRANCH MANUFACTURER NOTES NEM							NEMA
ATS-OS1'	600A	3	35K	OPTIONAL STANDBY	ASCO 7000 DELAYED TRANSITION TRANSFER SERIES OR APPROVED EQUAL		NEMA-1
					-		

#### SINGLE LINE DIAGRAM

N.T.S.

NOTE: COORDINATION WITH UNISOURCE IS PENDING, AND IT IS UNKNOWN IF 3-PHASE SERVICE WILL BE OBTAINED.

#### **GENERAL NOTES:**

- ALL ELECTRICAL ROOMS SHALL BE IDENTIFIED WITH SIGNAGE THAT READS "ELECTRICAL ROOM". THE SIGN SHALL BE INSTALLED ON A 4"X8" ALUMINUM WITH WHITE REFLECTIVE LETTERS ON RED REFLECTIVE BACKGROUND.
- COORDINATE REQUIREMENTS WITH TEP AND SUBMIT SWITCHBOARD METER AND UNDERGROUND PULL SECTIONS TO TEP METER SHOP FOR

#### **KEYNOTES:**

- (N) PAD MOUNT UTILITY TRANSFORMER.
- INSTALL COPPER GROUNDING ELECTRODE CONDUCTOR SIZED AS INDICATED AND BOND TO BUILDING STRUCURAL STEEL, STEEL GAS PIPING, COLD WATER PIPING AND (2) 3/4" X 10'-0" COPPER CLAD GROUND RODS SEPARATED A MINIMUM OF 6'-0" PER ARTICLE 250 OF THE NEC.
- UTILITY METER PER UNISOURCE REQUIREMENTS.




## architects planners

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

Plans

## **Station** Fire




23.21.00

JUNE 2024

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS






## GENERAL NOTES:

- A. UTILITY CONDUIT ROUTING IS APPROXIMATE. CONTRACTOR SHALL INSTALL CONDUIT(S) AND TRENCHING PER UTILITY COMPANY REQUIREMENTS (APS & COMMUNICATION UTILITY). REFER TO UTILITY COMPANY DRAWINGS PRIOR TO INSTALLATION. PROVIDE ADDITIOINAL PULL BOX(ES), HANDHOLE(S), CONDUIT AND EQUIPMENT AS REQUIRED PER UTILITY COMPANY REQUIREMENTS.
- PROVIDE A TRACER WIRE FOR ALL UNDERGROUND SITE CONDUITS PER ARIZONA STATE STATUTE REF. 40-360.22-M.
- CONTRACTOR TO BLUE STAKE ALL (E) UTILITIES PRIOR TO INSTALLING ANY (N) UNDERGROUND CONDUITS.

#### **#** EQUIPMENT KEYNOTES:


- SERVICE ENTRANCE METER & MCB SECTION 'SES-1'.
- 2 (N) PROPOSED LOCATION OF UNISOURCE PAN MOUNT TRANSFORMER. PROVIDE PAD PER UNISOURCE REQUIREMENTS.



#### **LIGHT POLE DETAIL**

N.T.S.

2






## Breckenridge g r 0 u p a r c h i t e c t s p l a n n e r s

1735 e ft. lowell rd. #12 tucson arizona 85719 5 2 0 . 8 8 2 . 9 9 4 4

## a**c rii'e Statiuli 44 i** -19 Frontane RD., Tuhac, AZ 85



PROJECT NO: 23.21.00 DATE:

JUNE 2024

REVISION SCHEDULE:

# DATE DESCRPITION

DRAWN BY: NT CHECKED BY: EG

CHECKED BY: EG

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



PLOT 7/1/2024 1:55:28 PM

\_2\_\_

1-19 FRONTAGE

ROAD

SITE PLAN

SCALE: 1" = 20'-0"


#### **GENERAL NOTES:**

- MAINTAIN ALL NEC REQUIRED WORKING CLEARANCES FOR ALL ELECTRIC
  - ALL WIRING SHALL BE (2) #12 AWG, #12 AWG GND. (U.O.N.).
- ALL BRANCH CIRCUITS TO HAVE DEDICATED NEUTRALS. SHARED NEUTRALS NOT ALLOWED (NEC ARTICLE 200.4).
- COORDINATE EXACT LOCATION OF DEVICES WITH ARCHITECTURAL ELEVATIONS PRIOR TO ROUGH-IN.
- FURNITURE LAYOUT SUBJECT TO CHANGE. COORDINATE FINAL REQUIREMENTS WITH FURNITURE, MILLWORK AND EQUIPMENT PROVIDERS.
- ALL RECEPTACLES WITH-IN 72 INCHES OF SINKS SHALL BE GFCI.
- ACCESS AND WORKING SPACE OF ALL NEW ELECTRICAL EQUIPMENT SHALL COMPLY WITH ARTICLE 110.26 OF THE NEC. THERE SHALL NOT BE ANY PIPING, DUCTS, LEAK PROTECTION APPARATUS OR OTHER EQUIPMENT FOREIGN TO THE ELECTRICAL INSTALLATION 6'-0" ABOVE THE ELECTRICAL EQUIPMENT PER ARTICLE 110.26(E)(1).

#### **KEYNOTES**:

- 4' H X LENGTH AS REQUIRED X 3/4" D PLYWOOD BACKBOARD PAINTED ON ALL SIDES WITH T20 COATS OF FIRE RETARDANT PAINT.
- GROUND BUS BAR. REFER TO DETAIL #2, THIS SHEET.
- 1-1/4" EC W/ PULLCORD.
- ROUTE CONDUIT OF 6" ABOVE ACCESSIBLE CEILING SPACE.

2



**COMM ROOM GROUND BUS BAR (TMGB)** 

N.T.S.

CHECKED BY: EG ARCHITECTURAL DRAWINGS AND DESIGNS ARE SAFEGUARDED BY THE FEDERAL COPYRIGHT ACT. ANY UNAUTHORIZED USE, REPRODUCTION, OR DISTRIBUTION OF THIS DRAWING, WHETHER IN WHOLE OR IN PART, IS


COPYRIGHT 2024 BRECKENRIDGE GROUP ARCHITECTS & PLANNERS



2051 W. SUNSET RD. SUITE NO. 101 TUCSON, ARIZONA 85704

TEL. (520) 293-1488 FAX. (520) 293-8349 M3ENG.COM





PROJECT NO: 23.21.00 JUNE 2024

DRAWN BY: NT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNTIL SEALED AND SIGNED BY ARCHITECTS OF BRECKENRIDGE GROUP ARCHITECTS/PLANNERS, OR DESIGNATED CONSULTANTS.

EXPRESSLY PROHIBITED WITHOUT PRIOR WRITTEN